

D-12g



WASTEWATER FACILITIES PLAN



CITY OF PLUMMER, IDAHO
BENEWAH COUNTY

RECEIVED

SEP 30 2002

DEQ-Coeur d'Alene
Regional Office

W Y A T T E N G I N E E R I N G , I N C .

North 1220 Howard Street ♦ Spokane, Washington 99201 ♦ (509) 328-5139 ♦ fax (509) 328 0423

SEPTEMBER 2002


RECEIVED

OCT 02 2002

#7249

EQ-Coeur d'Alene
Regional Office

The work product following this signature sheet was prepared under my direction. This work was authorized by the client to provide engineered opinions preparatory to final design. This work is not to be construed as a final design document for any reason by any party.



9-30-02

Professional Engineer's License
State of Idaho #7804


Alan E. Gay, P.E.

0-12-9
See
Comments
12/6/02
- JGG



ENGINEERING • LAND SURVEYING • PLANNING • MATERIALS TESTING

FACSIMILE TRANSMITTAL

TO: Gary Gaffney

DATE: November 13, 2002

CO: IDEQ

PROJ.: Plummer Wastewater

DEPT: Couer d' Alene

SUBJ.: Attached Facility Plan Executive Summary

FAX#: 208-769-1404

W.O.#: 685900

NO. OF PAGES (Including this transmittal):

5

The information in this fax is confidential and proprietary and is intended only for the individual or entity named on the cover sheet. If you do not receive all of the pages or have received this fax in error, please notify us immediately at (907) 276-4245.

ORIGINAL:

KEPT IN OFFICE

☒

TO FOLLOW VIA:

☐ Regular Mail☐ Courier☐ Overnight Service☐ E-mail**MESSAGE:**

Gary:

Following is the executive summary for Plummer.

Alan Gay, P.E.

WYATT ENGINEERING, INC. US&A<http://www.us&a.com>

□ 101 Train Road Lewiston, ID 83501 phone: (208) 746-2661 fax: (208) 746-6825
■ 1220 North Howard Spokane, WA 99201 phone: (509) 328-5139 fax: (509) 328-0423

WASTEWATER FACILITIES PLAN, PLUMMER IDAHO EXECUTIVE SUMMARY

The City of Plummer is an incorporated City situated in northwest Benewah County, approximately 40 miles south of Coeur d' Alene. Access to Plummer is provided by State Highway 95 which joins Highway 5 in Plummer. The community is located on the Coeur d' Alene Indian Reservation with the economy historically being based on forest and agriculture. Major employers are the School District, the Coeur d' Alene Tribe, Pacific Northwest Fiber and the re-tooled lumber mill. Figure 1.1 is a location map showing the City of Plummer in relation to prominent geographic features of the surrounding area.

The town's population has grown from 610 in 1980 to 990 in 2000. In 20 years, the town's population grew by 62%. With continued expansion of Coeur d' Alene Tribal interests, Plummer expects to continue its growth at a rate of 2.5% annually. The current estimated population in 2002 is 1,040. The projected population in 2022 is 1,700, and by 2028, the design year for the proposed facility, the population is projected to reach 1,977.

The City owns and operates a wastewater collection and treatment system which provides sanitary sewer service to the residents of the City. The effluent from the existing system discharges into Plummer Creek during the winter and spring, and is land applied during the summer. Plummer Creek is a stream with seasonally variable flow which provides the principal drainage for the area. Storage of wastewater is required for the time between land application season and discharge to Plummer Creek. In some years this period can last for two months.

The town has a great deal of inflow to the sewer system caused by stormwater leaking into the sewer collection system through manholes and leaky pipes. This causes more wastewater to flow to the treatment plant than it was designed for. In addition to this deficiency, the treatment plant will soon be required to meet much more strict discharge limits if it continues to discharge to Plummer Creek. Among the most stringent limits will be a very low limit on the amount of phosphorus into Plummer Creek, since phosphorus aids algae growth, which in turn depletes the oxygen available for other aquatic life.

As a result of these factors and an exhaustive analysis of various treatment and discharge alternatives, Wyatt Engineering proposes to help the city meet its wastewater treatment needs in a two phase program. The first phase will involve fixing the leaks in the collection system, and then monitoring sewer flow for a year to determine how effective that fix will be. Following the monitoring, Wyatt Engineering will use the collected flow data to size a new mechanical wastewater treatment plant. This new plant will treat waste to a high enough level for safe application to a wetland. The new treatment wetland will be located in the same area as the current land application system. It will include a pump-back feature to prevent discharge to surface water, including overland flow to Plummer Creek.

The total cost of the improvements is projected to be ~~\$5,503,000.~~

Does a water balance explain
how wastewater will be disposed of? Wetlands ET + seepage?
What makes the engineer think this will work?

IT

DATE: 1029/02		BUDGET INFORMATION-- CONSTRUCTION PROGRAMS	
PROJECT		PLUMBER WASTE WATER TREATMENT PLANT #11	
COST CLASSIFICATION		TOTAL COSTS	COSTS NOT ALLOWABLE For participation
			TOTAL ALLOWABLE COSTS (COL A-B)
1	Collection System	\$ 43,000.00	
	Treatment Plant	\$ 132,000.00	
2	Lncls, Right-of-way a, roads etc	\$ 30,000.00	
3	Relocation expenses		
	Collection System	\$ 202,000.00	
	Treatment Plant	\$ 678,500.00	
5	Other A/Engineering costs	IN # 4	
6	Project Inspection Fees	IN # 4	
7	Interest on Eng. Fees (1yr @ 5%)	\$ 44,000.00	
	Collection System	\$ 10,000.00	
	Treatment Plant	\$ 34,000.00	
8	Demolition & Removal		
	Collection System	\$ 917,500.00	
	Treatment Plant	\$ 2,798,000.00	
10	Equipment		
11	Miscellaneous//CITY COSTS	\$ 25,000.00	
12	SUB TOTAL		
13	Contingencies	\$ 632,500.00	12%
14	SUB TOTAL	\$ 5,503,000.00	
15	Project Income	\$	
16	TOTAL PROJECT COSTS	\$ 5,503,000.00	
Fed Assistance enter eligible costs from line 16c X		%	

Phase I

202

917.5

43K

0

10K

1.1725 + 12% Cont. = 1.3M

Phase II

678.5

2,798.5

132K

30K

34K

3.673K + 12% = 4.15M

- 175K

4.15M

= 4.845.5

+ 632 Contingencies

= 5.5M

Total




FIGURE 1.1
CITY OF PLUMMER CURRENT LOCATION MAP

SCALE: N/A

©Wyatt Engineering, Inc.
Project #685900
September 26, 2002


3

sitemap.dwg
Plummer Wastewater
Facilities Plan

Start: 08/01/02
Finish: 01/02/07

Plummer WWTP

Page #1



From: "Alan Gay" <AGay@uskh.com>
 To: <ggaffney@deq.state.id.us>
 Date: 11/21/02 12:17PM
 Subject: FW: Plummer Questions and Concerns

Gary: Following is the text of an email exchange that I had with Scott Fields. I hope this helps in your review of the Plummer Facility Plan

Thanks,

Alan

-----Original Message-----

From: Alan Gay

Sent: Thursday, November 14, 2002 5:25 PM

To: 'Scott Fields'

Subject: RE: Questions and Concerns

Scott:

Thank you for the very thoughtful questions. We wrestled with many of these in preparing our conceptual design. Where I can answer, I have. Some items will require further study.

Issues with using overland flow filtration at the Plummer WWTP.

1. Ground Water contamination

a. ~~Will the ground water be contaminated?~~ No; first, effluent will be treated to advanced secondary level before discharge to the overland flow wetland. Secondly, the nutrient levels will be below 2 mg/L TKN, and below 2 mg/L TP.

b. Are there any ~~drinking wells~~ (currently or planned) in the area that will be affected by the treated waste water entering the water table? No.

c. Does the ~~ground water enter into Plummer~~ Creek? Most likely; our hydrogeologic assessment indicates that this is the case.

d. How will the ~~ground water be monitored~~ for possible pollution associated with this plan? This has not been determined yet; however, we may use the existing lysimeters, and we may supplement those with monitoring wells if necessary; one upgradient and one or two downgradient.

2. Soil permeability

a. Are the soils on the site permeable enough to accept the design flow of the plan? ~~Yes~~

b. If a re-circulation pump is planned in the design does this mean that the engineers are skeptical of the ability of the plan to accept the design flows? ~~No, the recirculation will improve treatment.~~ There is sufficient permeability in the soil. ~~2~~

c. Area residents often have standing water on their land associated only with rainfall and snowmelt. Given this information how do the engineers expect the proposed area to continue to infiltrate significant amounts of water when other adjacent areas will not? There will be more head driving the infiltration. In addition, the use of this land for over twenty years for land application at daily rates in excess of what we are proposing indicates that the existing area is capable of infiltrating at the necessary rate.

d. How will the plan deal with severe winter weather and the problems associated with icing and soil frosts? There will be subsurface drains located at each berm that will pass water under ice during the winter. These drains will be sized so that there will be sufficient hydraulic head to create ponding.

e. What will happen during Rain on Snow events which are known to occur at least every 2 years in this area? This will only add 2 to 3" to the total depth of

*A lot of the
irrigated
water is
used
by
crops.
(ET)*

flow in the worst case, because off-site run-on will be prevented by the berms around the area.

3. Nutrient Removal.

a. How will the design deal with long term phosphorus (P) removal once the soils have adsorbed all the P they can? Phosphorus uptake by the wetland plants will be continuously remove phosphorus. The plants will be harvested once a year to remove the biomass and nutrients.

b. Will the total P and Nitrogen levels fluctuate seasonally due to temperature related bacteria growth rates. Yes.

4. Over flow contingency.

a. Is there a contingency plan if the overland flow filtration area becomes overwhelmed? There will be equalization ahead of the treatment works. In addition, a potential backup (not in the plan) is to supplement the overland flow with an irrigated drip system in the trees on tribal trust land south of the overland flow area.

b. How will waste water releases be mitigated? Other than the notion that there won't be any, any release would be highly treated even before it reaches the overland flow area.

Thanks again for the questions.

I hope these answers help in your evaluation.

Alan

Pilot the wetlands alternative.

Table of Contents

1.00	INTRODUCTION	1
1.01	Purpose and Scope of Work	1
1.02	System Description	1
1.03	Regulatory Framework	2
2.00	BACKGROUND INFORMATION	5
2.01	Geologic Setting	5
2.02	Soil Conditions	5
2.03	Local Hydrogeology	5
2.04	Surface Hydrology	5
2.05	Service Area	5
2.06	Land Ownership and Availability	6
2.07	Population Analyses	6
3.00	INFILTRATION AND INFLOW ANALYSIS	9
3.01	Introduction	9
3.02	Flow Monitoring	9
3.03	Flow Monitoring Conclusions	9
3.04	Corrective Actions	11
3.05	Infiltration and Design Loading	11
4.00	Design Criteria	12
4.01	Introduction	12
4.02	Wastewater Flow and Loading	12
4.03	Wastewater Disposal System Improvements Criteria	13
5.00	Collection System Evaluation	16
6.00	Treatment Options Evaluation	17
6.01	Option #1 Modify Existing Lagoons/Discharge to Plummer Creek	17
6.02	Option # 2 - Mechanical Biological Treatment Plant/Discharge to Plummer Creek & Land	18
6.03	Option #3 - Total Containment	19
6.04	Option #4 - Modify Existing Lagoons/Discharge to Cascading Wetland	19
6.05	Option #5 - Modify Existing Lagoons/ Discharge to Dripline Subsurface Disposal	20
6.06	Option #6 - Mechanical Biological Treatment/Discharge to Dripline	21
6.07	Option #7 - Mechanical Biological Treatment/Discharge to Cascading Wetland	21
6.08	Cost Comparison of Seven Wastewater Treatment Options	22
7.00	Selected Options	30
8.00	Financing	30

Tables and Figures

Table 3-1	Recorded Average Monthly Flows to Existing Treatment Facility	10
Table 3-2	Recorded Monthly Peak Flows to Existing Treatment Facility	11
Table 3-3	Projected Average Wastewater Flows	12
Table 4-1	1993 and 2001 Wastewater Analysis Results	13
Table 4-2	NPDES Permit Effluent Limitation	14
Table 4-3	2001-2002 NPDES Permit Violations	14
Table 4-4	Land Application Standards/Proposed Points of Compliance	15
Table 4-5	2002 Proposed Permit Effluent Limitations, Discharge to Plummer Creek	15
Table 6-1	Opinion of Probable Cost Tabulation (Treatment Facilities Only)	22

Figure 1-1	Plummer Location Map	3
Figure 1-2	Map of Existing Wastewater Facilities	4
Figure 2-1	Geologic Map showing WWTDF Vicinity	7
Figure 2-2	City of Plummer Zoning Map	8
Figure 6-1	Option #1 - Modified Existing Lagoon Treatment Plant	23
Figure 6-2	Option #2 - Mechanical Biological Treatment Plant	24
Figure 6-3	Option #3 - Total Containment	25
Figure 6-4	Option #4 - Modified Existing Lagoon Discharge to Cascading Overland Flow	26
Figure 6-5	Option #5 - Modified Existing Lagoon Discharge to Subsurface Disposal System ..	27
Figure 6-6	Option #6 - Mechanical Biological Treatment Plant Discharge to Subsurface Disposal System	28
Figure 6-7	Option #7 - Mechanical Biological Treatment Plant Discharge to Cascading Overland Flow	29
Figure 7-1	Hydraulic Profile(Piping to and From New STP)	31
Figure 7-2	Hydraulic Profile(Existing Piping)	32
Figure 7-3	Hydraulic Profile(Cascading Wetland)	33
Figure 7-4	Schedule	34
Figure 8-1	Flood Plain Map	36

Appendices

Appendix I	2000 CDBG Application (Wyatt Engineering)
Appendix II	1999 - 2002 Flow Data
Appendix III	2002 Hydrogeologic Report (Wyatt Engineering)
Appendix IV	Wastewater Quality Lab Data
Appendix V	Calculations
Appendix VI	Wastewater Treatment Plant Cost Estimate Data
Appendix VII	1982 NPDES Permit
Appendix VIII	2002 WLAP Permit
Appendix IX	2002 EPA Compliance Order
Appendix X	Selected Correspondence

The work product following this signature sheet was prepared under my direction. This work was authorized by the client to provide engineered opinions preparatory to final design. This work is not to be construed as a final design document for any reason by any party.

Professional Engineer's License
State of Idaho #7804

Alan E. Gay, P.E.

1.00 INTRODUCTION

The City of Plummer is an incorporated City situated in northwest Benewah County, approximately 40 miles south of Coeur d'Alene. Access to Plummer is provided by State Highway 95 which joins Highway 5 in Plummer. The community is located on the Coeur d'Alene Indian Reservation with the economy historically being based on forest and agriculture. Major employers are the School District, the Coeur d'Alene Tribe, Pacific Northwest Fiber and the re-tooled lumber mill. Figure 1.1 is a location map showing the City of Plummer in relation to prominent geographic features of the surrounding area.

The town's population has grown from 610 in 1980 to 990 in 2000. In 20 years, the town's population grew by 62%. With continued expansion of Coeur d'Alene Tribal interests, Plummer expects to continue its growth at a rate of 2.5% annually. The current estimated population in 2002 is 1,040. The projected population in 2022 is 1,700.

The City owns and operates a wastewater collection and treatment system which provides sanitary sewer service to the residents of the City. The effluent from the system discharges into Plummer Creek during the winter and spring. Plummer Creek is a stream with seasonally variable flow which provides the principal drainage for the area.

The City of Plummer's wastewater treatment and disposal facilities (WWTDF) were designed by H & V Engineering, Inc., in November 1979. The facilities consist of five cells, including two aerated/facultative lagoons, a chlorine contact lagoon, and two sand filters. In August of 1981, Interwest Engineering completed the Wastewater Treatment Facilities Operations & Maintenance Manual for the City of Plummer. This manual has been the written guidance for operation of the plant since its publication. No other original treatment plant design documents are known to exist.

1.01 Purpose and Scope of Work

The primary purpose of the Plummer Wastewater Facilities Plan is to evaluate treatment alternatives and costs, including re-evaluating the existing facility to assess whether or not it requires an upgrade. The evaluation is to be conducted with the goal of recommending a feasible alternative to treat and dispose of Plummer's wastewater ~~in accordance with State and Federal guidelines and in accordance with the surface water quality goals set by the Coeur d'Alene Tribe.~~ This evaluation will be completed using flow and water quality data compiled in preparing monthly discharge monitoring reports (DMRs) dated since 1993.

1.02 System Description

Plummer's wastewater collection system includes approximately **45,000 linear feet of sewer main** (Indian Health Service, 2000), and **398 service connections**. Of these, 345 are residential, 50 are commercial, and the remaining three are industrial customers.

The City of Plummer employs a wastewater superintendent and an assistant to maintain its collection system. Collection system piping is primarily 8" concrete and 8" PVC, with some 10" PVC in the lower reaches of the system close to the treatment plant. Manholes are either constructed of precast concrete ~~or brick.~~ Many ~~manholes have~~ **bricks**, and those placed in gravel roadways have the frame and lid placed below several inches of gravel surfacing to avoid snowplow damage during the winter.

The sewer discharges from the west and south into a single manhole located immediately west of the entrance to the WWTDF just northeast of the intersection of Seltice Avenue and Pine in the northeast corner of the City. Wastewater flows from that manhole to the east into the headworks of the WWTDF, just ahead of the first cell of the plant. Figure 1.2 depicts the City's existing wastewater facilities.

The headworks, a concrete structure with two flow channels, includes a comminuter in one

channel and a Miltronics flow meter in the other channel. The flow meter is equipped with a continuous data recorder.

1.03 Regulatory Framework

In May, 2002, the City of Plummer received a compliance order issued by the Environmental Protection Agency's Region 10 Water Quality program. This compliance order required that the City of Plummer ~~complete~~ its inflow and infiltration (I&I) removal program **by December 31, 2004**, and comply with the water quality standards in its NPDES permit by that same date. On August 20, 2002 the compliance order was revised by EPA. It now states that I&I is to be removed by December 31, 2004, and the WWTDF is to be in compliance with the percentage removal requirements in the NPDES permit by **January 1, 2007**.

This facility plan is being prepared for review and acceptance by the Idaho Department of Environmental Quality (IDEQ). IDEQ also issues and has jurisdiction over the Wastewater Land Application Permit (WLAP) for the City's WWTDF. IDEQ's review of this facility plan will be made using what are commonly referred to as the "Ten State Standards", a set of engineering standards for wastewater facilities compiled by the Great Lakes-Upper Mississippi River Board of State and Provincial Public Health and Environmental Managers.

Water quality criteria, if necessary, are being set by the Water Resource Program of the Coeur d' Alene Tribe. Once criteria are developed, they will be forwarded for review by the EPA's Region 10 Water Quality program. EPA will develop the next NPDES permit and fact sheet based on the Coeur d' Alene Tribe's water quality criteria.




FIGURE 1.1
CITY OF PLUMMER CURRENT LOCATION MAP

SCALE: NA




FIGURE 1.2

CITY OF PLUMMER EXISTING SEWER TREATMENT PLANT

SCALE: NA

© Wyatt Engineering, Inc.
Project #685900
September 26, 2002

sitemap.dwg
Plummer Wastewater
Facilities Plan

2.00 BACKGROUND INFORMATION

2.01 Geologic Setting

The major geologic formations in the Plummer area include the Pre-Cambrian Striped Peak Formation, Miocene Columbia River Basalt, the Miocene Latah Formation, and the Quaternary Palouse Formation. The Plummer Creek watershed creek bottom land is mapped as Miocene and possibly Oligocene sediments. The hills in the northern and western portion of the land application site to the northeast of the City are mapped as the upper member of the Wallace Formation of the Pre Cambrian Belt Supergroup.

The surficial geology in the middle elevations between the hilly uplands and the creek lowlands is the Pleistocene Palouse Formation, composed of loess soils. These soils exhibit high water storage capacities and some Holocene ash layers which may increase water retention.

The existing and proposed land application areas lie wholly within creek bottom lands mapped as Miocene and Oligocene sediments. This formation is described as deeply weathered orange to yellow silt and clay, with pebbles and sand in some areas, overlying Columbia River Basalt (within the land application area). The typical thickness is 30'. Refer to Figure 2.1, Geologic Map, showing the WWTDF vicinity.

2.02 Soil Conditions

The predominant soils in the vicinity of the City are ~~near the surface~~ near the surface, and ~~loams from 30 to 60 inches below the ground surface~~ loams from 30 to 60 inches below the ground surface. The silty clay loams are approximately 1/2 clay, with much of the area subject to frost action and ~~that may contribute to infiltration and inflow problems in the sanitary sewer collection system~~ that may contribute to infiltration and inflow problems in the sanitary sewer collection system.

The soil in the vicinity of the treatment plant is somewhat more permeable, including stony clay loam and shallow unweathered bedrock. (USDA SCS, 1980)

2.03 Local Hydrogeology

As required by the Department of Environmental

Quality, a hydrogeologic study was performed by Wyatt Engineering, on August 27, 2002. This study is intended to partially address Receiving Water Study Requirements under the City of Plummer's NPDES Permit ID-002278-1. This study, the text of which is included ~~in the~~

~~study~~ concludes that it is possible that ~~the clay in the land application area soil is sufficient to seal off deeper groundwater underlying the land application area from surface irrigation~~. From all that is known of the local stratigraphy and groundwater elevations, it appears that the direction of groundwater flow under the land application area is southeast toward Lake Chatcolet. ?

Piezometer monitoring at the land application site will be necessary to verify the elevation of shallow ground water at that site. The shallow water table is most likely responsive to runoff from both precipitation and irrigation. The ~~shallow water table~~ most likely discharges to Plummer Creek via the north bank of the creek in the vicinity of the existing WWTDF lagoons.

2.04 Surface Hydrology

As part of the monitoring of Plummer Creek, stream flow data is being recorded to not only correlate with water quality data, but also to characterize the surface water hydrology of the drainage basin above the wastewater treatment facility. The area draining toward Plummer Creek above the WWTDF includes approximately ~~7,300 acres~~ 7,300 acres. The surfaces include approximately ~~44~~ 44 acres of ~~impermeable surface~~ impermeable surface, primarily in the City of Plummer and Highway 95. In addition, approximately 4,900 acres are forested, 2,340 acres are agricultural, 35 acres are graveled, 380 acres are undeveloped and un-forested and 100 acres are developed as pervious surfaces such as lawns and landscaped areas.

Using a basic watershed model (SCS TR55 Method), Wyatt Engineers was able to simulate a ~~2-year return frequency runoff~~ 2-year return frequency runoff that approximates recorded discharges in December, 1998.

size
\$1.5
who owns?

2.05 Service Area

The service area for the WWTDF includes the incorporated area of the City of Plummer, plus contracted service for the Riley Creek Mill, Pacific Northwest Fiber, and various services to the Coeur d' Alene Tribe and its agencies in the area immediately northwest of and adjacent to the City limits. Figure 2.2 shows the zoning for the City of Plummer.

2.06 Land Ownership and Availability

(1)
The area around and including the existing WWTDF facilities is owned by several different entities. The more northerly area of the lagoons, chlorination and filtration facilities is ~~located by the City from Coeur d' Alene Tribe members who hold tribal allotments.~~ The lease is administered through the Coeur d' Alene Tribe. The City ~~leases the remaining southerly portion of the plant site from the Union Pacific Railroad.~~ Multiple ownership of the existing lagoon site has made it difficult for the City of Plummer to make practical long-range decisions affecting the property. This has made ownership of nearby property more attractive for siting a new treatment facility.

The ~~land application portion of the WWTDF is owned by the U.S. EPA in trust for the City.~~ The area adjacent to the ~~west~~ side of the existing land application area is currently ~~Coeur d' Alene tribe~~ allotment land owned by several individual tribe members. This area is now under tribal control, and the ownership status is very similar to that of the existing wastewater treatment lagoon facilities.

size
~~Potential areas for new facilities~~ include the land immediately to the west of the existing lagoons across Leitz Road. This area is owned by the State of Idaho for use by the Idaho State Department of Transportation as a ~~gravel pit~~. The readily accessible gravel has already been mined from the pit, leaving a large flat area that is suitable for a mechanical wastewater treatment facility.

Another potential ~~area~~ for a new treatment facility is located just to the south of the above-mentioned gravel pit. Two adjacent lots bounded by Leitz Road on the east, a tributary to Plummer Creek on the north, and Pine Street on the south were for

sale at the time that this facility plan was under preparation (September, 2002). These two lots together may be suitable for a wastewater treatment facility, although grading work and possibly soil stabilization work site would be necessary for a plant located on what are now the two private lots.

2.07 Population Analyses

There are currently 345 residential services (2000), and 53 commercial and industrial services in the City of Plummer service area. Based on water usage figures supplied by the City of Plummer, the 53 commercial and industrial services are equivalent to 100 residential services. This yields a total of 445 equivalent residential units (ERUs).

Based on the population growth trend since the 1980 U.S. Census, it is reasonable to project the following growth for the City of Plummer over the 20 years that the new plant will be in operation:

	Year	Population	ERUs
186	1980	610	248
	1990	796	359
194	1993	857 (est.)	387 (estimate)
	2000	990	436
	2002	1040 (est.)	445
	2008	1206 (est.)	516 (estimate)
	2028	1977 (est.)	846 (estimate)

The Coeur d' Alene Tribe plans to develop 80 acres of tribal land to the northwest of the intersection of Highway 95 and Highway 5, just outside the existing city limits. This area of mixed-use development, commonly referred to as the Celebration Grounds, is projected to contribute 50,000 gallons of wastewater per day. The tribe has indicated that it wishes to reach an agreement with the City of Plummer for the City to accept this flow.

(2)

size





Figure 2-1 Geologic Map Showing WWTDF Vicinity

Worthless



CITY OF PLUMMER, IDAHO




FIGURE 2-2
CITY OF PLUMMER CURRENT ZONING MAP

SCALE: 1"=1000'

3.00 INFILTRATION AND INFLOW ANALYSIS

3.01 Introduction

EPA Guidelines regarding excessive I&I state that if the average dry weather flow is less than 120 gallons per capita per day (gpcd), no further infiltration analysis work is required.

Based on 990 residents (2000 U.S. Census data), the maximum dry weather flow recommended by EPA guidelines would be 118,800 gallons (990 x 120 gpcd). Assuming constant growth towards 1,977 residents in 2028, the 2002 population is 1,040. With 1,040 residents, the maximum dry weather flow may be 120 gpcd, equivalent to 124,800 gallons (1,040 x 120 gpcd).

Flow data indicates that the minimum dry weather flow in Plummer is approximately 50,000 gallons per day (gpd) and that maximum dry weather flow is approximately 150,000 gpd. The [REDACTED] (December 8, 2001).

Based on this flow data, it was determined that [REDACTED] was entering the Plummer Sewer System, primarily from wet weather inflow. The area contributing inflow has been tentatively identified and an I&I removal project has been recommended by Indian Health Service. This project is scheduled for design and construction within the next twelve months. Following construction, the collection system will be monitored for twelve months to determine the success of the I&I removal project.

3.02 Flow Monitoring

The influent flow monitoring data was gathered between [REDACTED]. Summary charts of the flow data are included in Appendix II.

The selected time period includes dry weather periods in the summers and falls of 1999 through 2001. Monitoring continues as part of the operation of the wastewater treatment facility and to continue monitoring higher flows which may correlate to I&I.

How accurate?

The flow monitoring uses a permanent flow meter installed in the influent flume in the headworks prior to wastewater entry to the treatment lagoons. The flow meter is a Miltronics flow meter, which uses an ultra-sonic (US) sensor.

Flow rates are calculated using the known correlation between the depth of flowing water over the "throat" of the flume and the number of cubic feet per second that flow through the flume at that depth. The table of depths and the correlating flow rates are programmed into the memory of the flow meter.

Data is gathered continuously and then averaged over a one minute interval. After one minute, the data is logged into the flow meter memory.

The data is recorded using the totalizer feature of the flow meter on a daily basis. This data is then recorded by hand onto the daily record for the treatment facility.

Appendix II contains data from the flow monitoring station in a tabular format.

3.03 Flow Monitoring Conclusions

In general, the flow monitoring data shows that there is very little dry weather infiltration, and that a great deal of wet weather inflow and infiltration was removed with the construction of the sewer collection system improvement project in 1996-1998.

Seasonal storms still appear to contribute to elevated inflow rates during the months of November through June. The information in Table 3-1 would indicate that I&I has not been significantly reduced about from the flows recorded in 1993. However, water quality data indicates otherwise, as explained further in this section.

3 1/2 yrs

Table 3-1 Recorded Average Monthly Flows to Existing Treatment Facility

Month	Year	Avg. Flow (mgd)*	Avg. I&I (mgd)
January	1993	0.146	0.059
February	1993	0.117	0.030
March	1993	0.103	0.016
April	1993	0.087	0.000
May	1993	0.099	0.012
June	1993	0.081	0.000
July	1993	0.130	0.043
August	1993	0.080	0.000
September	1993	0.080	0.000
October	1993	0.080	0.000
November	1993	0.083	0.000
December	1993	0.129	0.042

1993 Overall Averages 0.101 0.017

Month	Year	Avg. Flow (mgd)*	Avg. I&I (mgd)
July	2001	0.079	0.000
August	2001	0.072	0.000
September	2001	0.068	0.000
October	2001	0.076	0.000
November	2001	0.072	0.000
December	2001	0.202	0.101
January	2002	0.143	0.042
February	2002	0.128	0.027
March	2002	0.137	0.036
April	2002	0.077	0.000
May	2002	0.055	0.000
June	2002	0.058	0.000

2001 - 2002 Overall Averages 0.097 0.017

of January through April include relatively high average flow rates. This is due to high peak flow events, which still result from inflow to flow to the collection system. The base flow rates are lower than those in 1993, though the population has increased by over 10 percent.

Proposed improvements to the wastewater treatment facilities will require hydraulic and treatment process sizing in accordance with flow data in Table 3-1. In addition, the portion of the treatment plant designed to handle influent flows must be sized to handle anticipated peak wastewater flow rates. The peak recorded daily flow rate for each of the monitored months was used to compile Table 3-2. The highest non-anomolous peak flow event was a 406,000 gpd flow, occurring on January 27, 2002.

Table 3-2 Recorded Monthly Peak Flows to Existing Treatment Facility

Month	Year	Average Flow (mgd)*	Peak Day Flow (mgd)
January	1993	0.146	0.150
February	1993	0.117	0.150
March	1993	0.103	0.150
April	1993	0.087	0.130
May	1993	0.099	0.130
June	1993	0.081	0.100
July	1993	0.130	0.300
August	1993	0.080	0.080
September	1993	0.080	0.080
October	1993	0.080	0.080
November	1993	0.083	0.100
December	1993	0.129	0.300

Overall Peaks 0.146 0.300

The information in Table 3-1 provides a long-term view of the monthly flow trends in the City's collection system following collection system improvements made between 1996 and 1998. As can be seen from the data in Table 3-1, the months

Inflow sources? Service line work?

Table 3-2 (Continued) Recorded Monthly Peak Flows to Existing Treatment Facility

Month	Year	Average Flow (mgd)*	Peak Day Flow (mgd)
July	2001	0.079	0.107
August	2001	0.072	0.085
September	2001	0.068	0.080
October	2001	0.076	0.132
November	2001	0.072	0.242
December	2001	0.202	0.840
January	2002	0.143	0.406
February	2002	0.128	0.397
March	2002	0.137	0.316
April	2002	0.077	0.196
May	2002	0.055	0.420
June	2002	0.058	0.122

Overall Peaks 0.202 0.840

The peak flow rate recorded on December 6, 2001, is considered to be an anomaly. That flow rate is significantly greater than any other recorded flow rate since 1993. The next highest flow rate occurred January 29, 1998, at a rate of 0.477 mgd. There are other instances of flow over 0.400 mgd recorded since 1993. However, based on the quality of the data and the correctable sump conditions connected with the highest flows, 377,000 gpd was selected as the highest peak flow rate under the present conditions.

3.04 Corrective Actions

The average wastewater flow rate over the recently recorded period is under 120 gallons per capita per day, but it may be cost-effective to construct additional collection system piping and manhole improvements as a means of reducing the significant wet-weather-related inflow shown in Table 3-2. This is because the peak storm water inflow rate is significantly greater than the average daily flow, and impacts the treatment plant's capacity and ability to meet water quality standards. High flow rates dilute the influent flow, lowering the concentration of organic and solids. At high flow rates, the plant is not capable of achieving the required removal percentages for

organic material and solids prior to discharge to Plummer Creek. As a result, this facility plan includes recommendations for an inflow removal program to reduce peak wet-weather flow rates. There is no assurance that additional inflow reduction can be achieved. Therefore, based on the available information, and assuming that no further I&I reduction is likely, we will use 200,000 gpd for in-town generated flow and 50,000 gpd of projected flow generation from the Coeur d'Alene Tribe's Celebration Grounds. This results in a total design flow of 250,000 gpd. This is an increase of 150,000 gpd above the existing flow rate. Adding 150,000 gpd to the existing peak flow for the new treatment system, a peak flow of 527,000 gpd was derived. This is equivalent to an average daily wastewater flow of 126 gpcd based on the 2028 estimated population of 1977, or 101 gpcd if the projected flow from the Celebration Grounds is not included in the gpcd calculation.

Average Daily Design Flow: 126 gpcd

3.05 Design Loading

The sewage flow forecast for Plummer is for a 6-year and a 25 to 30-year projection. Most of the demand will be from single family residences, but there is projected to be a significant percentage from non-residents and commercial sources.

We assume that a 2.5% annual population increase toward the total projected for 2028 (1977) will occur during the next six years, so that the projected population in 2008 would be 1206. At that time, assuming a flow rate of 101 gpcd for additional residents, the average daily flow will be approximately 121,800 gpd. 101 gpcd for new connections is a reasonable assumption because of the likely manhole sump condition origin of the existing high wet-weather inflow. Using the same assumption, the projected total population of 1977 would result in a 2028 flow rate of 200,000 gpd, 250,000 with Celebration Ground flows. Table 3-3 showing the Projected Wastewater Flow Forecast was derived using the formula:

$$\begin{aligned} \text{Average Daily Sewer Flow Forecast} \\ = \text{Existing Flow} + (\text{Average Daily Demand}) \times \\ (\text{new residents}) + \text{Celebration Ground Flow} \\ = 97,000 + (101 \text{ gpcd} \times 987) + 50,000 \approx 250,000 \text{ gpd} \end{aligned}$$

Table 3-3 Projected Average Wastewater Flows

Year	Projected Population	Wastewater Flow, gpd
2002	1,040	105,400
2003	1,066	107,700
2004	1,093	110,400
2005	1,120	113,100
2006	1,148	115,900
2007	1,177	118,800
2008*	1,206	171,800
2028*	1,977	250,000

*These figures include 50,000 gpd for the Coeur d' Alene Tribe's Celebration Grounds.

4.00 Design Criteria

4.01 Introduction

The design criteria in this report is summarized in this section.

Average Daily Flow: The average amount of wastewater effluent treated and disposed of during one 24-hour period.

Effluent Quality: The treated effluent quality (prior to discharge) must conform to guidelines set forth by the State of Idaho and/or the Coeur d' Alene Tribe.

Land Application: Wastewater that is applied directly to the ground, either above or below ground surface, must meet groundwater quality standards set forth by the State of Idaho.

Based on the conclusions of the geotechnical study undertaken for this project, the engineer believes that a shallow perched water table condition is likely to develop under natural conditions in the soils beneath the site. Accordingly, it is concluded that some drainfield or wetland effluent infiltrating to the silt layer would probably flow across the shallowest clay lense. Flow moving across this clay lense would eventually discharge through soil pores to a possible unconfined shallow perched aquifer

above the primary drinking water source aquifer for the City of Plummer.

A copy of this study is in Appendix III.

Design and Construction Standards: The design engineer will furnish plans and written specifications outlining the materials to be used, the installation procedures, and any required testing procedures. The materials, installation and required testing will be consistent with that commonly used for wastewater facilities and systems, and will conform to all requirements outlined in IDAPA 58.01.02, 58.01.03, and 58.01.17 regarding design and construction of sewage works, on-site sewage systems, and land application systems, respectively.

4.02 Wastewater Flow and Loading

The City of Plummer population has increased steadily from 610 in 1980 to its present population of approximately 1040 in 2002. Since 1990, the population has been growing at a rate of approximately 2.5 percent per year. The following presents historical population data for the City:

Year	Population
1930*	469
1940*	539
1950*	454
1960*	444
1970*	458
1980	610
1990	796
2000	990 (U.S. Census)
2002	1040 (estimate)

*Figures prior to 1980 are based on Benewah County data.

As discussed previously, wastewater flow rates at the treatment facility have been measured constantly since at least January, 1993. A flow meter is installed in the headworks of the wastewater treatment facilities to determine flow rates. Measured flow rates ranged from 0.05 MGD to 0.30 MGD over the first study period from January 1, 1993 through December 31, 1993. Measured flows ranged from 0.002 mgd to 0.840 mgd over the second study period, from January

not complete

Actually EPA

1, 1999, through June 30, 2002. The average daily flow rate for 2002 was determined to be 0.097 MGD in Section 3, with approximately 17%, or 0.017 MGD, determined to be I&I. As a result of the flow monitoring discussed in Section 3, the design criteria for flow has been established to be 97,000 gpd for present flows, and 250,000 gpd for ultimate flow in 2028.

Loading characteristics are measured daily as part of the Discharge Monitoring Reporting requirements for the facility. Table 4-1 presents the analytical results of that sampling. The data in Table 4-1 was selected to correspond with the data in Section 3 on flow data.

Table 4-1 1993 and 2001 Wastewater Analysis Results

Parameter	1993 Average	2001-2002	2001 Peak
BOD ¹ in	71 mg/L	157 mg/L	337 mg/L
BOD ¹ out	11 mg/L	11 mg/L	20 mg/L
TSS ² in	119 mg/L	156 mg/L	367 mg/L
TSS ² out	17 mg/L	14 mg/L	30 mg/L
fecal c. ³ in	No test	No test	No test
fecal c. ³ out	79/100 mL	8/100 mL	300/100 mL
flow in	0.101 mgd	0.097 mgd	0.840 mgd

1. BOD = Biochemical Oxygen Demand (5-day), based on the arithmetic mean of samples taken.
2. TSS = Total Suspended Solids, also based on the arithmetic mean of samples taken.
3. Fecal C. = Fecal Coliforms, reported in the number of colonies detected per 100 milliliter sample. The average values are the geometric mean.

As noted in Section 3, by 2001 average daily flow had increased to approximately 97,000 gallons/day. At the same time, influent concentrations of constituents increased significantly. The increase in average influent concentrations indicates that the I&I reduction program effectively reduced "clean water" flows to the sewer system. Some improvement was made in the treatment efficiency of BOD, but not enough of an improvement to offset occasional wet-weather inflow-caused reductions in removal

efficiency. These reductions in removal efficiency have caused the facility to miss it's 1982 NPDES permit limits.

4.03 Wastewater Disposal System Improvements Criteria

The existing disposal system involves storage, evaporation, land application, and seasonal discharge to an intermittent stream. The existing wastewater treatment plant consists of two aerated facultative lagoons which were designed and constructed between 1979 through 1981. At the time they were constructed, the lagoons were intended to function as aerated facultative lagoons, using aeration to enhance biological activity in the wastewater with a long enough retention time to allow microbes to partially digest the biological matter in the wastewater. As the town has grown, flows have become progressively greater, inflow continues to introduce flows greater than the facility is able to treat, and the facility has discharged effluent to Plummer Creek that did not meet permit limits.

Discharge to Plummer Creek is limited by stream flow as well as permit limits. Based on discussions with the Coeur d' Alene Tribe's Water Resource Program Manager, Mr. Scott Fields, it is very likely that water quality based limits will be imposed on future discharges to Plummer Creek, especially phosphorus limits. It is also likely that other water quality parameters will become lower, including biochemical oxygen demand, total suspended solids and restrictions on the discharge of chlorine. Discharge to Plummer Creek is usually feasible between mid-November and mid-May. From mid-May to mid-November, the creek has a flow rate below ten times the average daily discharge from Plummer's treatment facility and is therefore too low to allow discharge.

Discharge to a conventional land application system such as the one currently in use by the City of Plummer is seasonally restricted to the needs of whatever crop is in use. In Plummer's case, through the 2002 growing season, that crop was oats. While oats requires a high liquid loading early in the summer, the required loading is greater than the City's existing pumps can deliver during five standard eight-hour shifts. The

harvest date of oats is September at the latest, which means land application must cease in early September each year. Therefore, the City will switch to cropping alfalfa with the 2003 growing season to extend the period available for land application. Once the switch is made to cropping alfalfa on its land application area, the City will be able to land apply wastewater through early October.

Due to the gap between either end of the land application season and either end of the feasible period for discharging to Plummer Creek, continuing to utilize a combination of these discharges will require an equalization storage basin.

The ideal discharge alternative will allow for year-round discharge with minimal equalization of flows resulting from high inflow or disruptions in the discharge schedule. Potential year-round discharges include subsurface disposal, leaky wetlands, and overland flow.

The 1982 National Pollutant Discharge Elimination System (NPDES) permit outlines the following limits.

Table 4-2 1982 NPDES Permit Effluent Limitations

Parameter	Average Monthly	Average Weekly
BOD¹	30 mg/L, 85% removal, 26 lb/day	45 mg/L, 85% removal, 39 lb/day
TSS²	30 mg/L, 85% removal, 26 lb/day	45 mg/L, 85% removal, 39 lb/day
Fecal Coliform	100#/100 mL	200#/100 mL
Flow	0.100 mgd	0.200 mgd
	No discharge from May 1 to November 30	
pH	Daily minimum ≥ 6.5 , Daily maximum ≤ 9	

1. BOD = Biochemical Oxygen Demand (5-day), based on the arithmetic mean of samples taken.
2. TSS = Total Suspended Solids, also based on the arithmetic mean of samples taken.
3. Fecal coliform limits are based on the geometric mean.

These limitations expired in 1987, but have been administratively extended by EPA Region 10. From July 2001 through June 2002, the following excursions beyond permit limits were recorded:

Table 4-3 2001-2002 NPDES Permit Violations

Date	Parameter	Limit	Actual Discharge	Unit
Dec. 2001	Monthly Avg. Flow	0.100	0.202	mgd
Dec. 5-14 2001	Weekly Avg. Flow	0.200	0.202 - 0.531	mgd
Jan. 2002	Monthly Avg. Flow	0.100	0.143	mgd
Feb. 2002	Monthly Avg. Flow	0.100	0.128	mgd
Feb. 24-26 2002	Weekly Avg. Flow	0.200	0.210 - 0.219	mgd
Mar. 2002	Flow	0.100	0.137	mgd
Mar. 24-29 2002	Weekly Avg. Flow	0.200	0.200 - 0.243	mgd
Apr. 2002	% removal, TSS	85%	73%	%

The above table illustrates that the primary problem with the existing facility is a lack of hydraulic capacity. With average weekly flows as high as 0.531 mgd, the existing facility simply can not keep discharges within permit limits. The high flows at the end of March 2002, for example, caused flow rate permit violations, and later a violation of percentage removal requirements in April 2002 for total suspended solids.

Under the Compliance Order issued by Region 10 of the EPA on April 26, 2002, the 1982 permit limitations were to be met by December 31, 2004. However, the EPA was persuaded to reissue the Compliance Order on August 20, 2002. The revised compliance order requires that the City of Plummer remove inflow and infiltration by December 31, 2004, and achieve the required

Remove
TSS & ex
compliance

Need EPA agreement with these

percent removal for BOD and TSS by December 31, 2004. The City's wastewater treatment facility has until January 1, 2007 to achieve the other water quality requirements in the NPDES permit.

As discussed in Section 2, the anticipated flows following build-out are expected to be 250,000 gpd, or 126 gpcd. Since the current system does not meet the effluent limitations specified in Table 4-2 while treating wastewater for the existing population of 1040 people, and the build-out population is significantly greater than 1040 residents, the treatment facility alternatives discussed in Section 6 must consider alternative disposal methods.

The Idaho Department of Environmental Quality has issued a Municipal Land Application Permit No. LA-000004-02 to the City of Plummer. This permit is to take effect in the 2003 growing season, beginning May 1 and ending on October 31. Table 4-4 illustrates the discharge parameter limitations under the Land Application Permit.

Table 4-4 Land Application Standards / Proposed Points of Compliance

Parameter	Maximum Contaminant Level	Proposed Point of Compliance
Total Coliform	230#/100 mL until August 1, 2004 23#/100 mL thereafter	End of Pipe
COD	50 lbs/acre/day	End of Pipe
N	150 lbs/acre/day	End of Pipe
P	27 lbs/acre/day	End of Pipe

The Coeur d' Alene Tribe's Water Resource Program Manager, Mr. Scott Fields, has discussed potential permit limits for Plummer Creek should the WWTF continue seasonal discharges to the creek. Table 4-5 is based on these discussions. The information in Table 4-5 is not currently in a discharge permit, but will likely be part of a future NPDES permit should the City of Plummer continue to discharge to Plummer Creek.

Table 4-5 2002 Proposed Permit Effluent Limitations, Discharge to Plummer Creek

Parameter	Average Monthly	Average Weekly
BOD ¹	20 mg/L, 85% removal, 42 lb/day	30 mg/L, 85% removal, 63 lb/day
TSS ²	20 mg/L, 85% removal, 42 lb/day	30 mg/L, 85% removal, 63 lb/day
DO ³	6.0 mg/L	
Fecal Coliform ⁴	100#/100 mL	200#/100 mL
TP ⁵	0.25 mg/L	0.50 mg/L
Flow	0.500 mgd Peak Daily, 0.250 mgd Average Monthly; Flow-paced discharge from Nov.15 to May 15.	
pH	Daily minimum >=6.5, Daily maximum <=9	

1. BOD = Biochemical Oxygen Demand (5-day), based on the arithmetic mean of samples taken.
2. TSS = Total Suspended Solids, also based on the arithmetic mean of samples taken.
3. DO = Dissolved Oxygen
4. Fecal coliform limits are based on the geometric mean.
5. TP = Total phosphorus.

This document has been prepared assuming that a treatment facility discharging to Plummer Creek must meet the discharge criteria outlined in Table 4-5.

As discussed in Section 2, the anticipated flows following build-out are expected to be 250,000 gpd, or 126 gpcd. Since the current system does not meet the effluent limitations specified in Table 4-5 while treating wastewater for the existing population of 1,040 people, and the build-out population is significantly greater than 1,040 residents, the facility alternatives discussed in Section 5 must consider alternative disposal methods.

Potential alternative disposal methods will have to meet the receiving water quality criteria of the respective receiving waters. Other than Plummer Creek, the only other feasible receiving waters are groundwater below a subsurface soil absorption system (SSAS), groundwater below surface

Non-meets

OK

OK

?

OK

?

Why?

draft

improvements

not have

EPA duty

Written anywhere?

Service line I/E?

vegetation in a continued land application system, and groundwater below a "leaky" artificial wetland or overland flow system. Groundwater quality criteria are found in the Idaho Administrative Rules (IDAPA) 58.01.11. IDAPA 58.01.17 defines the terms under which wastewater can be land applied. In addition, land application of wastewater is addressed as follows:

Land Application Facility Or Facility. Any structure or system designed or used to treat wastewater through application to the land surface.

Rapid Infiltration System. A wastewater treatment method by which wastewater is applied to land in an amount of twenty (20) to six hundred (600) feet per year for percolation through the soil. Vegetation is not generally utilized by this method.

Time Distribution of Flows. A measurement of the volume of wastewater distributed over a specified area during a specified time period. Typical unit of measure is inches per acre per week.

From a practical standpoint this document has been prepared with the principle that treatment systems evaluated for disposal, in whole or in part, to groundwater will meet or exceed groundwater quality standards at the end of the pipe from the treatment facility prior to the effluent entering the soil.

Specifically, the design criteria for ground water quality will be as defined in Table 4-4.

5.00 Collection System Evaluation

Indian Health Services (IHS) published the *Plummer Community Sewer System Condition Report* in February 2000, outlining a program to reduce the remaining inflow in the City of Plummer wastewater collection system. The IHS report was prepared to enable the City to end a moratorium on new construction caused by the lack of capacity in the existing wastewater facilities.

Wyatt Engineering has contracted with Missoula Blue Print to prepare an aerial photogrammetric map of Plummer, with ground control provided by Wyatt Engineering's surveyors. Based on this mapping, an inventory of the City's manholes will be conducted to update the IHS' document, and provide the basis for collection system improvement design. The inventory in the IHS document will be used as a guide for the most critical areas, and provide the basis for assessing which pipes to replace or improve. The IHS report's inventory will also serve as a comparison for the conditions noted by Wyatt Engineering. Once the supplemental inventory is complete, Wyatt Engineering will prepare a Collection System Design Report, which will be submitted to the Idaho Department of Environmental Quality for review and acceptance. Design documents will be prepared based on the IDEQ- accepted Collection System Design Report.

Collection system improvement options will include conventional trenching and pipe placement, pipe bursting, pipe slip-lining, manhole lid replacement, manhole replacement, manhole repair with pressure grout, and manhole slip-lining. The most critical portions of the collection system will be marked for replacement based on the program budget of \$1,264,000 that was defined in the IHS report.

Construction of collection system improvements will begin in spring, 2003, and be completed by November, 2003. Once the collection system improvements are complete, flow monitoring data collection will commence to determine the effectiveness of the I/I removal program. By November, 2004, after one year of collection system flow monitoring, the treatment system portion of this facilities plan will be re-evaluated. Should the collection system improvements cause significant reductions in inflow, the equalization requirements for the wastewater facility may be reduced in size accordingly.

6.00 Treatment Options Evaluation

Any of the treatment system improvement options described in this section would be constructed in one phase. As the current compliance order from EPA Region 10 requires achieving discharge limits to Plummer Creek by January 1, 2007, there is not sufficient time to accommodate any additional construction phases.

Based on the proposed schedule, it is anticipated that the construction project to improve the treatment facilities will begin in the spring or summer 2005, and will be completed by fall 2006.

Figures illustrating each treatment option can be found at the end of Section 6.00.

6.01 Option #1 - Modify Existing Lagoons to a Biological Treatment Plant Discharging to Plummer Creek and Land Application

As discussed, the existing treatment facility does not meet criteria established in the 1982 NPDES permit. It is therefore academic that the existing facility will not meet the more stringent water-quality requirements that are likely to be imposed on continued discharge to Plummer Creek. Therefore, an obvious option is to upgrade the existing facility to meet expected permit limits.

To achieve proposed water quality limits within the physical confines of the existing facility, several upgrades will be necessary. First, in the cover memo for the WLAP, Mr. Gary Gaffney wrote, "If and when the city undertakes upgrading of the wastewater treatment plant now being proposed and likely to occur within 5 to 10 years, DEQ will require that the project includes installation of a liner in each of the lagoons."

Prior to installing liners, the lagoons will need to be increased in size in order to provide sufficient volume for biological nutrient removal. The calculations for this increase are included on a spreadsheet printout labeled "PlummerProcTribe.xls", located in Appendix V. Since there is no more room on the existing site to expand horizontally, the lagoons must be made deeper. It is likely that there is a high water table in the vicinity of the lagoons, due to their

proximity to Plummer Creek. Therefore, a hypothetical de-watering procedure was developed. This procedure would include excavation of gravel-filled de-watering trenches drained by tile piping connected to a series of de-watering sumps. The de-watering system would be abandoned or partially converted into the routing for the sludge removal system, which is outlined below.

Other necessary upgrades to the facility for this alternative include **additional storage** for wastewater received between the middle of October, when land application ends, and the middle of November, when discharge to Plummer Creek is again allowed. Based on a water balance simulation using a spreadsheet model, Wyatt Engineering determined that the minimum basin size is **eight acres in area, approximately 10.5 million gallons at four feet deep**, enough to store 45 days of flow. A basin of this size will prevent discharge over a stochastically-simulated 20 year period of rainfall and average evaporation. A copy of the model print-out is in Option 1, Tribe, in Appendix V.

Another adaptation for this option is construction of a **sludge removal system**. To prevent damage to the lagoon liner and maintain the hydraulic capacity of the lagoon system, it will be necessary to construct a sludge pumping system. Sludge will be pumped to drying beds next to the site of the equalization lagoons, tentatively located at the site of the old state gravel pit across the road from the treatment plant.

To convert the lagoons into a **dual-train system** as required in the ten-state standards, and to provide flexible partitions for anoxic, aerobic, and anaerobic zones, a baffle system will be constructed to supplement the berm between the current first and second lagoon cells.

To achieve the proposed phosphorus discharge limits shown in Table 4-5, the plant will need to employ biological nutrient removal, chemical addition prior to wastewater entering the anaerobic cells, disinfection, and filtration. With this combination of treatments, it is probable that the strict limits proposed can be met. Probable phosphorus removal was calculated using standard removal efficiencies for the listed

processes, and an estimated phosphorus loading of 10 mg/L, with about 70% soluble (Clark et al, 1979). By using what has become known as a "Bardenpho" process, alternating anoxic, aerobic, and anaerobic treatments, bacteria specializing in those environments successively oxidize phosphorus and complex the resulting phosphates to achieve removal rates double or triple the 20 to 30 percent removal achieved with conventional activated sludge alone.

Chemical addition of alum achieves an additional 90 percent reduction in phosphorus by causing dissolved phosphate to sorb onto alum floc, which then settles to the bottom of the cell. Filtration following alum addition and settling will result in a further 50 percent reduction in phosphorus.

Prior to discharge, effluent will pass through ultraviolet radiation (UV) disinfection channels. UV disinfection is recommended because of the ease and safety to the operator and the lack of a residual chemical, such as chlorine, to either remove or poison the receiving water.

The existing aerators will be replaced with a fine-bubble diffusion aeration system that allows the operator to adjust where aeration takes place in the baffled system, and enables easy maintenance and replacement of diffusion heads.

The existing sand filters will be lined and retrofitted with a finer sand, and have an enhanced surface distribution system that evenly distributes wastewater from the anaerobic cell or equalization cell (the existing third cell) over the surface of the sand filter.

Discharge to Plummer Creek during the November 15 through May 15 period will be controlled by an in-stream flow meter that will throttle the effluent flow rate to no more than ten percent of the stream flow.

Additional land will be necessary for Plummer to continue to land apply during the growing season. Along with the additional land it will eventually be necessary to upgrade the existing 530 to 660 gpm capacity irrigation pumps. The existing pumps will function as both return-flow pumps and irrigation pumps. During discharge to Plummer Creek, they will circulate a side-stream

of anaerobically-treated wastewater from the down-stream end of what is now the second cell, back to the upstream end of what is now the first cell for anoxic treatment.

Other necessary enhancements include a computer system, a pump station located near the existing influent manhole, and additional piping. The computer system will assist the operator in selecting the correct valving and pumping options given current process parameters. It will also help the operator calculate those process parameters. The influent manhole pump station will be necessary to provide pump-back to the storage lagoon. Additional process piping will be necessary to provide the operator with the flexibility necessary to meet permit limits under changing flow, temperature and influent wastewater characteristics.

The estimated cost for this option for engineering, construction, and a 20 percent contingency is \$7.55 million. Cost estimate data was collected from suppliers, Means Construction Cost Index, and previous projects completed by Wyatt Engineering. Using an annual inflation rate of 4%, the present value of 20 years of operation of this option at \$125,000 per year is \$1.7 million.

6.02 Option #2 - Mechanical Biological Treatment Plant Discharging to Plummer Creek and Land Application

The second option is very similar to the first option in terms of the degree of treatment received and the discharge selection. The primary difference is that this option includes purchase of a package mechanical activated sludge plant capable of biological nutrient removal. As a result of this difference, the City of Plummer would no longer have its plant on leased ground, but instead it would be on land purchased from either the state or a private land owner near the existing plant site.

An equalization basin and pumping from the existing influent manhole would still be necessary for this option. The second cell of the existing facility would be converted into a lined cell to provide storage, or a new basin could be constructed on the state land to provide the

required 45 days of storage outlined in the text describing Option #1. Also as with the first option, additional land will be necessary for land application to crops.

B.S. In addition to the base package plant, sludge dewatering equipment and drying beds will be required, as will alum addition, UV disinfection, and polishing filtration, if necessary. The package mechanical plant will have an integrated, computerized operating system utilizing pneumatic valve actuation. The aeration will be provided by a fine-bubble diffusion aeration system that allows the operator to adjust where aeration takes place in the baffled system, and enables easy maintenance and replacement of diffusion heads.

N.D. Discharge to Plummer Creek during the November 15 through May 15 period will be controlled by an in-stream flow meter that will throttle the effluent flow rate to no more than ten percent of the stream flow. During periods near the beginning and end of each creek discharge season, plant operation may utilize the storage lagoon to prevent excess discharge to Plummer Creek.

This treatment alternative is capable of meeting or exceeding all of the discharge parameters listed in Table 4-5.

The estimate for this alternative is based on information supplied by Aero-Mod, who design, manufacture and support custom package wastewater treatment plants. The estimated cost for this option for engineering, construction, and a 20 percent contingency is \$5.13 million. Using an annual inflation rate of 4%, the present value of 20 years of operation of this option at \$101,000 per year is \$1.4 million.

6.03 Option #3 - Total Containment

This alternative consists of retrofitting the existing lagoons with impermeable membrane liners, and providing an additional 478 acres of membrane-lined evaporative lagoon(s). This much capacity would preclude the need for discharge, and provide sufficient capacity for the design flow rate discussed in Sections 3 and 4.

The required size of the additional evaporative lagoon was determined using a stochastic rainfall as a component of a water balance model. The stochastic rainfall approach utilizes historic average monthly precipitation data and both five-year high and five year low precipitation data to develop a random rainfall distribution for Plummer. By simulating 20 years of such precipitation, the result is a conservative estimate of the lagoon sizing necessary to prevent overflow for the statistically-likely high 20-year rainfall set within statistically-likely precipitation patterns. This simulation methodology is superior to using actual rainfall records, because it is at least as likely to predict future events as actual past rainfall, and it enables many different 20-year scenarios; each recalculation changes the random number generator, and thus instantly develops an additional 20-year scenario.

Evaporation rates for the lagoon model were determined using an average of the historic monthly pan evaporation data from Sandpoint and Moscow, Idaho. Pan evaporation was corrected to water body evaporation using the approach of Linsley et al (Linsley, Kohler, Paulhus, *Hydrology for Engineers*, 1986).

Since there would be no discharge to surface water, this alternative would eliminate the need for an NPDES discharge permit and discharge monitoring.

However, the estimated construction, engineering and contingency cost for this alternative is \$92.49 million. This figure is based on prevailing geomembrane installation costs, a 20% contingency, and engineering costs totaling 20% of construction costs. This option would include essentially zero operating cost.

6.04 Option #4 - Modify Existing Lagoons to a Biological Treatment Plant Discharging to Cascading Overland Flow/Wetland

This alternative would retrofit the existing lagoons with impermeable membrane liners. This alternative would preclude the need for discharge to Plummer Creek, and it would provide sufficient capacity for the design flow rate discussed in Sections 3 and 4.

1565
won't work
can't be approved.

What about lease
ownership
issue

The sizing analysis conducted for this alternative utilized the same approach as that for Alternative #3, with stochastic rainfall simulation and evaporative rates derived from historic Spokane Airport and Lind, Washington data. In addition, a very conservative estimate of infiltration equivalent to 1×10^{-5} cm/sec. was used to simulate the infiltration rate into the soil of the existing land application area. Even under constantly saturated conditions, it is very unlikely that the soils at this location have that low of a permeability. Converting Soil Conservation Service permeability from the Benewah County Soil Survey for the subject soils yields a worst-case permeability of 5×10^{-5} cm/sec.

Since there would be no discharge to surface water, this alternative would also eliminate the need for an NPDES discharge permit and discharge monitoring, though a state waste discharge permit is still required.

The existing lagoon system would need to be lined, as discussed under the first option. In addition, for this alternative, biological treatment and UV disinfection would be necessary to assure that the surface-applied wastewater met WLAP application standards. Nutrient removal would not be necessary, nor would there be a need to change the existing lagoon depth or area, as the current configuration is adequate to achieve the level of treatment required. The existing sand filters would be abandoned.

Process design calculations for this alternative are included in Appendix V under the spreadsheet "PlummerProcOverflowTribe.xls". These calculations show that the treatment plant will provide flow to the cascading overland flow system with a chemical oxygen demand of 60 mg/L or less, a nitrogen level of 10 mg/L or less, and a phosphorus level of 5 mg/L or less.

The estimated construction, engineering and contingency cost for this alternative is \$3,508,000. Cost estimate data was collected from suppliers, Means Construction Cost Index, and previous projects completed by Wyatt Engineering. Using an annual inflation rate of 4%, the present value of 20 years of operation of this option at \$120,000 per year is \$1.6 million.

6.05 Option #5 - Modify Existing Lagoons to a Biological Treatment Plant Discharging to Dripline Subsurface Disposal

The objective of this alternative is to meet land application water quality requirements in the current WLAP permit while utilizing the existing lagoon system. Several subsurface disposal options were investigated for feasibility and cost. Subsurface dripline wastewater disposal systems have recently been approved for use in Washington. These systems utilize shallow, small diameter perforated tubing laid out roughly along contours through existing native vegetation, without destroying that vegetation in the process. The tubes are installed by punching through the surface with a specially-designed installation machine. Other subsurface disposal systems that were investigated include conventional gravity systems and pressure mound systems. Due to terrain constraints, a conventional gravity system is not feasible. Subsurface drip systems were found to be less expensive than a mound system for the equivalent loading rate.

The existing lagoon system would need to be lined, as discussed under the first option. In addition, for this alternative, a modest degree of biological treatment would be necessary to assure that the subsurface-applied wastewater met WLAP application standards, with the exception of disinfection. Nutrient levels will need to be somewhat less than those allowed under normal land application, due to the year-round application schedule and somewhat less uptake by vegetation. There would be no need to change the existing lagoon dimensions, as the current configuration is adequate to achieve the level of treatment required. The existing sand filters would be abandoned.

Two expensive components of this option include replacing the land application pumps with an alternating dosing pump system, and the addition of additional lined storage to absorb high inflow loads beyond the design capacity of the drip line system. The alternating dosing system would use a timed dose to provide a measured amount of wastewater to each section of drip line, thus avoiding overloading of any of the drip line beds.

PHD permit
Pilot year
round use

1.6M

The new lined storage lagoon would be located on the state gravel pit site across the road from the existing WWTDF. The lagoon would cover about 7.5 acres, and hold 10 million gallons, about 40 days of storage at average daily flow rates.

The timed dose system will be provided by the drip-line manufacturer to insure that the system works together. It will be set up to dose at a rate of 0.2 gallons per square foot per day, with each drip line receiving two eleven-minute doses per day. Drip lines will be one-inch diameter polyethylene tubing, with pre-manufactured orifices placed every 12-inches along the length of the drip tubes. The drip lines will be clustered 4 drip lines per bed, with 21 or 22 beds per dosing zone. There will be 56 dosing zones, covering a total of 30 acres.

Process calculations are provided in Appendix V, in a memorandum from Tracy Johnson to Alan Gay.

This treatment alternative is capable of meeting or exceeding all of the discharge parameters listed in Table 4-4.

The estimated construction, engineering and contingency cost for this alternative is \$4,732,000. Cost estimate data was collected from suppliers, Means Construction Cost Index, and previous projects completed by Wyatt Engineering. Using an annual inflation rate of 4%, the present value of 20 years of operation of this option at \$120,000 per year is \$1.6 million.

6.06 Option #6 - Mechanical Biological Treatment Plant Discharging to Dripline Subsurface Disposal

The objective of this alternative is to meet groundwater quality requirements in the current and future WLAP permits without as much installation of expensive impermeable membrane liners required for retrofitting the existing facility. This alternative would utilize the same processes as those discussed for Option #2 for treatment, except no alum addition would be required, nor would there be any need for disinfection.

The equalization storage, no disinfection, and

discharge set-up requirements would be identical to those required for Option #5.

This treatment alternative is capable of meeting or exceeding all of the discharge parameters listed in Table 4-4.

The estimated construction, engineering and contingency cost for this alternative is \$6,467,000. Cost estimate data was collected from suppliers, Means Construction Cost Index, and previous projects completed by Wyatt Engineering. Using an annual inflation rate of 4%, the present value of 20 years of operation of this option at \$80,500 per year is \$1.1 million.

6.07 Option #7 - Mechanical Biological Treatment Plant Discharging to Cascading Overland Flow/Wetland

This system combines the advantages of operating a package mechanical wastewater treatment facility on ground to be owned by the City with the high loading, low maintenance and year-round discharge advantages of discharging to a cascading overland flow wetland area. This is the preferred option for treating and disposing of the City's wastewater in the future.

The subject overland flow site, now used for land application, meets the criteria for a cascading overland flow system set forth in *Natural Systems for Wastewater Treatment, 2nd Edition* (Water Environment Federation, 2001). The site soil profile shown in the *Soil Survey of Benewah County, Idaho* (USDA SCS, 1980) indicates that soils on the north side of State Route 28 are shallow silt loam, and cobbly or gravelly silt loam over bedrock. In addition, the hydrogeologic assessment conducted by Teresa Kristof of Wyatt Engineering indicates that the soils in the vicinity of the proposed overland flow system are moderate to deep clayey loess (wind-deposited volcanic ash/silt) overlying basalt.

We will employ a flow of 250,000 gallons per day for our design criteria, with peak flows of 527,000 gpd. With those influent flows, a conceptual geohydrologic model of the land application area indicates that using 20 acres of the available 27 acres now used for land application as a cascading overland flow wetland could hydraulically

accommodate a peak flow rate of 250,000 gallons per day year-round, with an annual peak month flow of as much as 1.1 mgd without a breakthrough.

The cascading overland flow system will be constructed with gravel underdrains for each soil berm defining a terrace of the cascading system. A header pipe will be installed in a french drain at the top of the overland flow system, running parallel to Toetly Road on the north end of the site. At the south, bottom end of the system will be a sump with a pump-back lift station that will work with a check valve to pump return flow, if any, back up to the header pipe along Toetly Road, preventing discharge to surface water.

As stated under Option #4, the nutrient and chemical oxygen demand loads will be quite small compared to the land application capacity of the site. Along with soil absorption, there will be uptake by the wetland plants that has not been calculated into the nutrient balance allowance.


The estimated present value cost for this alternative of \$4,239,000 is based on construction of a cascading ~~overland~~ flow system and a package mechanical treatment plant. The cost estimate for the cascading overland flow system assumes that wetland plants will be seeded as well as naturally re-establish over time to provide soil stabilization and nutrient uptake. Other estimate information for the system was obtained from, Means Construction Cost Data, an inflation rate of 4%, a 20% contingency, and engineering costs totaling 20% of construction costs. The annual operations and maintenance expenses for the total wastewater facilities are estimated to be \$120,427, including \$74,000 to operate and maintain the new treatment facility. The present value cost for 20 years of operation assuming a 4 percent annual inflation rate is \$1.6 million. The operations and maintenance estimate includes the cost of anticipated tests, routine maintenance, and permit renewal costs every five years for land application permitting.

6.08 Cost Comparison of Seven Wastewater Treatment Options

The seven alternative treatment technologies are compared in Table 6-1.

Table 6-1 Opinion of Probable Cost Tabulation, Treatment Facilities Only

Option	Capital	Capital less Engineering	Engineering	20 Yrs Operations
#1	\$7,552,000	\$6,341,000	\$1,211,000	\$1,698,000
#2	\$5,131,000	\$4,310,000	\$822,000	\$1,378,000
#3	\$92,485,000	\$77,681,000	\$14,803,000	\$0
#4	\$3,508,000	\$2,946,000	\$562,000	\$1,635,000
#5	\$4,732,000	\$3,973,000	\$759,000	\$1,636,000
#6	\$6,467,000	\$5,432,000	\$1,035,000	\$1,094,000
#7	\$4,239,000	\$3,560,000	\$679,000	\$1,003,000



©Wyatt Engineering, Inc.
Project #685900
September 26, 2002





FIGURE 6-2
OPTION 2 SCHEMATIC - MECHANICAL PACKAGE PLANT



won't work

EXISTING — — — —
 PROPOSED —————

FIGURE 6-3
OPTION 3 SCHEMATIC - TOTAL CONTAINMENT






FIGURE 6-4
OPTION 4 SCHEMATIC - MODIFIED LAGOONS DISCHARGE TO CASCADING OVERLAND FLOW



EXISTING ———
PROPOSED ———

FIGURE 6-5
OPTION 5 SCHEMATIC - MODIFIED LAGOONS DISCHARGE TO SUBSURFACE DRIPLINE






FIGURE 6-7
OPTION 7 SCHEMATIC - MECHANICAL PACKAGE PLANT DISCHARGE
TO CASCADING OVERLAND FLOW

7.00 Selected Options

Option #7 has been selected as the most feasible cost-effective approach to treating Plummer's wastewater in the coming years. This alternative was evaluated using the criteria established in Sections 3 and 4. In addition to the treatment facility, the inflow and infiltration reduction project outlined in Section 5 of this Report will begin immediately upon adoption of this report by IDEQ and the City Council of the City of Plummer. The projected total capital cost for the combined project is \$5,503,000.

Influent and effluent testing will address the concerns of the Department of Environmental Quality regarding effluent quality. Effluent must also meet quality standards to maximize the life of the cascading overland flow wetland. This will be accomplished by optimizing the operation of the treatment plant.

The ultimate configuration selected for the wastewater treatment facility will be decided in the design phase of the project. It may be decided that the final design will be most cost effective and provide the most operational flexibility if a combination of discharge alternatives with the selected overland flow discharge is used. In addition, property ownership remains problematic. It may be advantageous to site the new treatment facility uphill from the cascading overland flow wetland area, thus changing the property ownership scenario and reducing required pumping to one major lift station up to the treatment facility. The major disadvantages to this scenario are unknowns about soil stability, property ownership, and power availability north of the land application area.

Figures 7-1 through 7-3 illustrate the preliminary site plan and hydraulic profile for the selected alternative. Figure 7-4 shows the proposed project schedule.








FIGURE 7.3
CITY OF PLUMMER HYDRAULIC PROFILE (CASCADING WETLAND)

SCALE: 1"=200'











FIGURE 7.1
CITY OF PLUMMER HYDRAULIC PROFILE (PIPING TO & FROM NEW STP)

SCALE: 1"=200'



8.00 Financing

Financing is being arranged through the United States Department of Agriculture, Rural Development (RD). At this time, negotiations with RD have as a goal the commitment to fund all of the projected \$5.503 million of program capital costs. Of this, \$2,000,000 is being placed before the voters of Plummer in a bond election to take place in November, 2002. Grant money will make up the remaining RD funding that will be provided. The City of Plummer will adopt an ordinance increasing sewer utility fees from \$17 per month to \$43 per month to retire the \$2,000,000 loan and pay for increased operations and maintenance costs. Loan fees and interest over the 30 year period will cost an additional \$1,260,000 over the life of the loan.



**CITY OF
PLUMMER, IDAHO**

**NO CURRENT FLOOD ZONE
INFORMATION AVAILABLE**

**FIGURE 8-1
CITY OF PLUMMER FLOOD ZONE MAP**

SCALE: 1"=1000'

APPENDIX I

**2000 CDBG Application
(Wyatt Engineering)**

City of Plummer

P.O. BOX B
PLUMMER, ID 83851
PH. 208-686-1641

November 17, 2000

Mr. Gary Mahn, Director
Idaho Department of Commerce
700 W. State Street
P.O. Box 83720
Boise, Idaho 83720-0093

Dear Mr. Mahn:

The City of Plummer respectfully submits this application for an Idaho Community Development Block Grant. Our community has a thirty-five year old sewer system which has unfortunately served it's useful life.

Heavy inflow and infiltration combined with community growth has caused the system to reach capacity. During rainfall events and snow melt events, raw sewage bubbles out of our manholes and overflows our treatment facility directly to Plummer Creek. As you can imagine, the health and welfare of our citizens is compromised.

In addition, the EPA-Region 10 has issued a "Letter of Violation" and the Idaho Division of Environmental Quality has issued a sewer moratorium until we have a solution. This couldn't come at a worse time as the Coeur d'Alene Tribe is currently working on an 80 acre development that will include elderly housing, industry, meeting facilities and an RV park. Without solving our sewer crisis, they cannot connect to our system.

Therefore, we respectfully submit this request for a \$500,000 ICDBG grant to supplement our \$140,600 local match and \$2,311,750 federal assistance (IHS, EPA, USDA-RD) to allow us to provide our 863 residents (63% LMI) with a sewer collection and treatment system which will provide for their health and welfare and allow for the continued economic growth of this small Idaho community. Thank you for your consideration.

Yours truly,

Harold Whitley, Mayor
City of Plummer

Table of Contents

ICDBG APPLICATION INFORMATION FORM	01
THRESHOLD FACTORS	02
ELIGIBILITY OF APPLICANT	02
ELIGIBILITY OF ACTIVITY	02
ADMINISTRATIVE CAPACITY	02
PUBLIC PARTICIPATION	02
GENERAL PROJECT DESCRIPTION	03
COMMUNITY DESCRIPTION	03
COMMUNITY NEEDS ASSESSMENT	03
PROJECT DESCRIPTION	04
BENEFITS OF THE PROJECT	05
ICDBG BUDGET FORM	06
ASSURANCES	07
RATING AND RANKING CRITERIA	08
PROGRAM IMPACT	08
ELIGIBLE ACTIVITIES POINT FORM	09
NATIONAL OBJECTIVES	10
BENEFIT TO LMI	10
NEEDS OF LMI	10
IMPACT TO LMI	10
PUBLIC FACILITY RATING AND RANKING CRITERIA	11
PLANNING	11
PREVIOUS ACTIONS	12
DETAILED COST ANALYSIS	13
CERTIFIED GEM COMMUNITIES	13
FINANCIAL VIABILITY PROFILE	14
PROPOSED SCHEDULE	16
PROFESSIONAL AND AGENCY CONTACTS	18
ADVISORY COUNCIL POINTS	19
APPENDIX	21

D. APPLICATION INFORMATION - RULE 074.04

IDAHO COMMUNITY DEVELOPMENT BLOCK GRANT

Applicant: **CITY OF PLUMMER** Address: **P.O. Box B, Plummer, ID 83851
Benewah County, Idaho**

Chief Elected Official: **Harold Whitley, Mayor** Phone: **(208) 686-1641**

Application Prepared By: **Wyatt Engineering, Inc.** Phone: **(509) 328-5139**
Address: **1220 N. Howard
Spokane, WA 99201**

Architect/Engineer/Planner: **Wyatt Engineering, Inc.** Phone: **(509) 328-5139**
Address: **1220 N. Howard,
Spokane, WA 99201**

NATIONAL OBJECTIVES:
(please circle)

PROJECT CATEGORY:
(please circle)

PROJECT FINANCING:
(fill in)

LMI X

Public Facility X

ICDBG: \$ 500,000

Slum and Blight

Housing

Local: \$ 140,600

Imminent Threat

Economic Development

State:

Federal: \$2,311,750

Private:

Other:

TOTAL: \$2,952,350

Note: Send two (2) copies of all applications to Department of Commerce and one (1) copy to your regional Economic Advisory Council member. Attach Project Maps and LMI Survey Maps in Appendix.

Project Area Population: 863 Project Area LMI Population: 544 (63%)

1. Have any land, buildings easements or right-of-ways been purchased for this project?
How? _____ Yes No X
Date _____
2. Is anyone living on the land or in the structures at the proposed site? Yes No X
3. Is any business being conducted on the land or in the structures at the proposed site? Yes No X

DETAILED PROJECT DESCRIPTION:

Sewer system improvements including the replacement of manholes, collection lines and service lines to reduce the excessive inflow and infiltration (I/I) going into the sewer system and treatment facility during runoff and rainfall events. In addition, the improvements will include upgrading the 35 year old wastewater treatment facility. Even with the I/I removal, this facility is beyond it's original design capacity and cannot meet it's current discharge permit. This project will provide a response to the EPA "Letter of Violation"; will allow the Idaho Division of Environmental Quality (IDEQ) to lift their sewer moratorium; and will cease the overflow of raw sewage into Plummer Creek.

DESCRIBE LOCAL MATCHING FUNDS:

The City has committed \$89,600 cash toward the project and has completed \$47,000 in inflow and infiltration removal on the current system. In addition, the City has expended \$7,500 for planning activities and facility plan preparation.

APPLICATION CERTIFICATION:

The data in this application is true and correct. This document has been duly authorized by the governing body of the city or county and the city or county will comply with all required certifications, law and regulations if the application is approved and selected for funding.

Name (Typed): Harold Whitley

Title: Mayor

Signature: _____

Date: _____

E. THRESHOLD FACTORS - SECTION 074.05

Eligible Applicant:

The City of Plummer is an incorporated city in the State of Idaho with a population of less than 50,000 and therefore qualifies as an eligible applicant under Idaho Community Development Block Grant 2000 Administrative Rules (IDAPA 48.01.01) Section 012.

Eligible Activity:

The planning, administration, construction and installation of public works facilities to benefit a majority of LMI persons in a project area qualifies as an eligible activity under the following Sections:

024 – Public Facilities and Improvements

039 – Administrative Activities

The project also meets the State of Idaho objective of improving community infrastructure to encourage additional housing and economic development in communities.

The requested grant will provide for a portion of the funds needed to construct the project as outlined in this application. Due to economic growth pressures, it is incumbent upon the City to repair and upgrade our wastewater collection and treatment facilities.

Administrative Capacity:

An elected Mayor and four councilpersons govern the City of Plummer and employ a city staff of sixteen full and part-time persons, including a full-time City Clerk/Treasurer, Deputy Clerk and public works employees. Firefighting services are provided by the Gateway Fire District and police protection is provided by a city police officer, the Benewah County Sheriff's Department and the Coeur d'Alene Tribe.

The City has, after following the appropriate procurement practices, hired an Idaho Department of Commerce approved grant administrator to assist in the making of this application as well as a project engineer to make preliminary design and cost estimates as well as to create final construction documents. The administrator and engineer will, upon award of this grant, provide additional services for administration and construction of the proposed improvements.

Public Participation:

As required by Section 074.05(c), a Citizen Participation Plan has been adopted by the City and, in accordance with the plan and as required by Section 074.05(d). A Notice of Public Hearing was published in the local newspaper more than seven (7) days prior to the public hearing held October 26, 2000 to receive written and oral comments on the public's perception of the project and to review this application.

Dates of Publication of Public Notice: October 18, 2000
Date of Public Hearing: October 26, 2000

F. GENERAL PROJECT DESCRIPTION - SECTION 074.06

Community Description:

The City of Plummer is an incorporated City situated in northwest Benewah County, approximately 40 miles south of Coeur d'Alene. Access to Plummer is provided by State Highway 95 which joins Highway 5 in Plummer. The community is located on the Coeur d'Alene Indian Reservation with the economy historically being based on forest and agriculture. Major employers are the School District, the Coeur d'Alene Tribe, Pacific Northwest Fiber and soon the re-tooled Lumber Mill.

The town's population has grown from 610 in 1980 to 863 in 1994. The population in 1999 was estimated at 1113. In 14 years, the town's population grew by 41%. With continued expansion of Coeur d'Alene Tribal interests, Plummer expects to continue its growth at a rate of 3% annually.

Community Needs Assessment:

A town meeting was held on May 20, 1992 to assess community needs. This meeting was attended by over 50 people including representatives from the Idaho Department of Commerce, RECD, and IDEQ. Community needs including public facilities, public building, housing, transportation, education and recreation were all considered at this meeting. Public facility improvements of both the water and sewer systems were considered to be a critical priority by local residents. The original priority defined was the water system improvement and that priority has been addressed with recent projects.

Now the priority has shifted to a reliable sewer system.

The City of Plummer sewer system is overloaded by excessive inflow and infiltration (I/I). During rainstorms and spring melting, flows can jump from 100,000 gallons per day to in excess of 400,000 gallons per day. This volume cannot be handled by either the collection lines or by the treatment facility. The result is raw sewage flowing out of manholes and the treatment facility overflowing raw sewage directly to Plummer Creek. Both are an extreme health hazard for all residents of the City of Plummer.

These violations have caused the Idaho Division of Environmental Quality (IDEQ) to issue a sewer moratorium and not allow any new connections on the system until corrections are made. In addition to this moratorium, the City of Plummer has received notices of violation for repeated discharge from the treatment facility to Plummer Creek that are outside of the permit limits.

These moratoriums and violations could not come at a worse time for Plummer. The Coeur d'Alene tribal industrial area located in the southwest portion of town now includes the new Pacific Northwest Fiber facility to produce straw board. In addition, the old mill site is being re-tooled to allow a small log mill to begin operation. Finally, plans for the site include the opening of a new Ironman Safe manufacturing facility. All of these facilities provide jobs to the community.

In addition to these facilities, the Coeur d'Alene Tribal headquarters are now located in Plummer and they are now proceeding with development of 80 acres in the northwest corner of the community. The plans for this land include elderly housing, an RV park, museum, crafts shops, recreation areas, meeting grounds, and other uses. In addition to this development, a new business plaza is also being planned by the Coeur d'Alene Tribe which would create employment for 30 people and the Coeur d'Alene Tribal Housing Authority plans to build an average of 5 new homes each year for the foreseeable future.

With the sewer moratorium in place and violations commonplace, these projects cannot proceed and the health and welfare of all of the Plummer residents is in jeopardy. ***There is no stronger need to the Plummer community than correcting the sewer concerns.***

F. GENERAL PROJECT DESCRIPTION - SECTION 074.06 (cont.)

Project Description:

The older portion of the collection system where the I/I problem exists was constructed in the early 1960's and is constructed of eight inch diameter concrete pipe and cinder block manholes. In 1995, an I/I study was completed on the sewer system which confirmed that I/I flows caused system flows to fluctuate between 80,000 gallons per day to 450,000 gallons per day with rainfall and snowmelt events.

Corrections were made in a 1996-1997 CDBG project. The success of this project was confirmed by IDEQ which stated in their 1999 Annual Report dated 2/2/00 that

"...we noted a dramatic decrease in flow into the treatment facility from 58.7 million gallons in 1998 to 42.5 million gallons last year.....we compliment the city on the success of these efforts"

The Indian Health Service (IHS) completed its Plummer Community Sewer Systems Condition Report in February 2000, concluding that major improvements to the sewer systems are required for the continued good health of those residing and working in and around the City of Plummer. The report indicated that the City's wastewater treatment facilities are still overloaded due to inflow and infiltration (I&I) into the collection system. Identified improvements include manhole repair and replacement; sewer line replacement; service line replacement; roadway repair; and cleaning and video inspection of the sewer lines.

In addition, Wyatt Engineering completed a Wastewater Treatment and Disposal Facilities Plan in November of 2000. This plan concluded that even with I/I removal success, continued community growth along with changing discharge permit criteria into Plummer Creek would require a significant improvement to the existing treatment and disposal facility to achieve all goals. After review of several alternatives, the selected alternative was to expand land application area to the system for additional disposal; line the existing treatment lagoons to minimize seepage into the groundwater; and construction of additional treatment lagoons to provide detention time and needed capacity.

The I/I collection project improvements will be completed in two phases. The first phase incorporates an initial scope of work to address the most severe I&I problem spots and the engineering for the system's reconfiguration with the second phase correcting the remainder of the identified deficiencies. The project will include over 11,000 feet of sewer line replacement; 65 manholes either repaired or replaced; new service lines and connections; and video inspection and cleaning. This project is projected to begin construction in the summer of 2001 and be completed by the fall of 2001.

The treatment and disposal project will be completed after the I/I work has been done. This project will include adding new aeration, chlorination and filter cells; new building facilities; additional land application land and equipment; and lining the existing treatment cells. The project schedule is to complete the design in the summer and winter of 2001 and begin construction in the spring of 2002.

The sewer system improvements sought under this grant are those necessary to bring the community into agreement with current health and operation standards, to increase the capacity of the existing lagoons and to preclude overflowing of untreated effluent into Plummer Creek.

Cost estimates, vicinity maps and site maps for these projects are included in the appendix.

F. GENERAL PROJECT DESCRIPTION - SECTION 074.06(cont.)

Benefits of the Project:

Environmental Benefits: Critical problems with Plummer's sewer system include inflow and infiltration from rain water and snow melt which greatly overloads the treatment lagoons. This causes the lagoons to overflow which greatly shortens the treatment cycle and leads to large quantities of raw or partially treated effluent going into the creek and subsequently to Lake Coeur d'Alene. It has been said that the lower end of the lake is devoid of any game fish and plant life is limited to that which can survive in a virtually "dead" lake. It is possible the problem with the City of Plummer sewage system is contributing to this condition.

Economic Benefits: Additionally, improvements to the City's infrastructure system will help local businesses with future expansion plans and make Plummer a more attractive community for economic development (unemployment in Benewah County is 13.4% versus the statewide average of 6.6%). Continued expansion by the Coeur d'Alene Tribe, and the Tribal Housing Authority will bring additional new jobs to the City of Plummer. This will create new demands on a sewer system which is already critically deficient and at times virtually inoperative.

Regionalization Benefit: Without this project, the Coeur d'Alene tribal expansion cannot connect to the City of Plummer system due to the IDEQ moratorium. If this occurs, the Tribe has indicated that one potential solution would be to create a separate sewer and water system to handle only the tribal interests. This would create two proximate systems and would still leave Plummer without a solution. The benefit of this project would be to eliminate the need for a redundant system and regionalize the sewer collection and treatment needs.

National Objective: The project complies with the National Objective of developing viable communities by expanding economic opportunities and providing decent housing for persons of low and moderate incomes. The proposed activities specifically address the immediate sewer moratorium and raw sewage discharges to Plummer Creek both of which "pose a serious and immediate threat to the health and welfare of the community where other financial resources are not available to meet such needs".

State Objective: The project complies with State Objectives of the ICDBG program by assisting an Idaho community to make it possible for the City of Plummer to improve their infrastructure, develop their tax base and to provide growth opportunities. As stated above, the project will eliminate health and safety problems caused by the raw sewage discharges to Plummer Creek and the overflowing manholes after a rainfall or snow melt event. This project will principally benefit low and moderate income citizens through:

1. Improving community infrastructure to accommodate economic growth and eliminate health and safety problems through updating the sewer system in a city that is 63% LMI.
2. Providing for potential additional opportunities created by an infrastructure that allows for business expansion.
3. Improving the possibilities for economic viability of a town which, along with other small towns is excited about growth in their area of Idaho.
4. The project will also provide to the area the short term economic benefit of a public works project through its attendant payroll and material supply requirements.

Each of these benefits and objectives will be addressed by this project which is to be funded by a combination of City, IHS, EPA, USDA-RD and CDBG funds.

G. Budget
Community Development Project Budget

Applicant or Grantee: City of Plummer **Project Name:** Plummer Wastewater System Improvement Project

LINE ITEMS	ICDBG Cash	City Cash	City In Kind	Indian Health Services	EPA CWA-ISA	USDA-RD NA-SAF	Private Cash	Private In Kind	Other Cash	Other In Kind	Total
Administrative Expenses/Publications**	\$20,000					\$22,500					\$42,500
Project Planning & Design			\$7,500								\$7,500
Land, Structures, Rights of Way						\$30,000					\$30,000
Architectural/Engineering Base Fees		\$6,000	\$5,000	\$52,000	\$31,250	\$173,750					\$268,000
Inspection Fees			\$6,600	\$58,000	\$31,250	\$173,750					\$269,600
Relocation Expenses											
Relocation Payments to Businesses & Individuals											
Demolition & Removal											
Construction & Project Improvements	\$480,000	\$78,000	\$35,500	\$270,000	\$126,600	\$1,337,150					\$2,327,250
Legal						\$5,500					\$5,500
Audit		\$2,000									\$2,000
TOTAL COSTS**	\$500,000	\$86,000	\$54,600	\$380,000	\$189,100	\$1,742,650					\$2,952,350

*Identify funding source.

** Administrative expenses and project planning design costs, when totaled, shall not exceed 10% of the total ICDBG amount.

H. ASSURANCES - SECTION 074.08

In the event we, the City of Plummer, should receive a Community Development Block Grant, we certify we will comply with the requirements of:

- National Environmental Policy Act of 1969
- Civil Rights Act of 1964 Pub.L. 88-352
- Civil Rights Act of 1968 Pub.L. 90-284
- Age Discrimination Act of 1975
- Rehabilitation Act of 1973, Section 504
- Uniform Relocation Assistance and Real Property Acquisition Act of 1970, as amended (49 CFR Part 24)
- Housing and Community Development Act of 1974, as amended Pub.L. 93-383
- Davis Bacon Act (40 USC 276a-276a-5)
- Historic Preservation Act
- Section 106 of the Housing and Urban Recovery Act of 1983 certifying to:
 - Minimize displacement as a result of activities assisted with CDBG funds; and adopt and follow a residential anti-displacement and relocation assistance plan.
 - Conduct and administer its program in conformance with Title VI and Title VII, and affirmatively furthering fair housing.
 - Provide opportunities for citizen participation comparable to the State's requirements (those described in Section 104(a) of the Act, as amended).
 - Not use assessments or fees to recover the capital costs of CDBG-funded public improvements from low and moderate income owner occupants.
 - Abide by all State and Federal rules and regulations related to the implementation and management of Federal grants.
 - Assess and implement a Handicapped Accessibility Plan in accordance with Section 504 of the Rehabilitation Act of 1973, as amended.
 - Adopt and implement an Excessive Force Policy.
 - Adopt and abide by the Anti-Lobbying Certification.
 - Prohibition of Use of Assistance for Employment Relocation, Section 588 of the Disability Housing and Work Responsibility Act of 1998 Pub. L 105-276

Signed by Chief Elected Official

Date

Harold Whitley, Mayor
Typed Name

I. Rating and Ranking Criteria – Section 083

Following is a summary of the matching fund sources and commitments. Letters from each agency are provided in the Appendix. In addition, Ernest Stensgar, the Coeur d'Alene Tribal Chairman, has provided a letter of support and a letter requesting that the available Indian Set Aside moneys be utilized for this project.

<u>Source</u>	<u>Amount</u>
City Cash	\$ 86,000
City In-Kind Match	\$ 54,600
Indian Health Service	\$ 380,000
EPA-Indian Set Aside	\$ 189,100
USDA-RD - NA Set Aside	\$1,742,650
TOTAL MATCH FUNDS	\$2,452,350

i. Program Impact (320 Points) - Section 084.

- A. Percentage of ICDBG dollars in total project (50 Points)

$$\$500,000 \div \$2,952,350 = \underline{16.9\%}$$

- B. Percentage of Local Matching Funds as a percentage of local match + CDBG (60 points)
(Note: For each \$1.00 in cash on hand, use \$1.50 for calculation)

$$\begin{array}{rclcl} \text{Local Cash Multiplier} & \$86,000 & \times & 1.5 & = & \$129,000 \\ \text{Adjusted Local Match} & \$129,000 & + & \$54,600 & = & \$183,600 \end{array}$$

$$\$183,600 \div (\$500,000 + \$140,600) = \underline{28.7\%}$$

- C. ICDBG Dollars per Person (50 points)
ICDBG dollars divided by total persons directly benefitted by the project = ICDBG dollars per person

$$\$500,000 \div 863 = \underline{\$579.37} \text{ Dollars Per Person}$$

- D. Local Matching Funds per Person (60 points)
Local matching funds divided by total persons directly benefitted by the project = dollars per person (Note: for each \$1.00 in cash on hand, use \$1.50 for calculation)

$$\$183,600 \div 863 = \underline{\$212.75} \text{ Dollars Per Person}$$

- E. Eligible Activity Point Form (100 points)
(See eligible activity point form on the following page.)
- F. Environmental Considerations: List environmental impacts and any mitigating factors.

None of the proposed work should have any lasting detrimental impact to the environment. Quite the contrary. Currently, the sewer collection and treatment system cannot handle the existing flows which causes raw sewage to flow out of the manholes and treatment facility directly to Plummer Creek. This situation will be remedied with this project. There will be temporary impacts (dust, noise, etc) during construction and a JARPA permit is anticipated for work near Plummer Creek. Additional permitting will include an amendment to the Land Application permit (WLAP) and a revised NPDES permit.

ELIGIBLE ACTIVITIES POINT FORM - SECTION 084.05

IDAHO COMMUNITY DEVELOPMENT BLOCK GRANT PART OF RATING AND RANKING CRITERIA - PROGRAM IMPACT ITEM E

TOTAL ICDBG FUNDS REQUESTED \$ 500,000

SECTION NO.	ELIGIBLE ACTIVITY	ICDBG \$ ALLOCATED	% OF TOTAL ICDBG REQ	POINT VALUE	TOTAL POINTS
023.	Acquisition of Real Property			25	
023.	Acq. Real Property for Housing			50	
024.	Public Facilities & Improvements				
	-Health/Safety Related	\$480,000.00	96.0%	100	96
	-Housing Related			75	
	-Social Service			50	
	<u>Engineering</u>			<u>75</u>	
025.	Code Enforcement			50	
026.	Clear/Demolition			10	
027.	Removal of Architectural Barriers			50	
028.	Rental Income Payments			0	
033.	Disposition Property			10	
034.	Public Services			0	
036.	Completion of Urban Renewal Projects			0	
037.	Relocation Payments			25	
038.	Planning Activities			0	
039.	Administrative Activities	\$20,000.00	4.0%	100	4
040.	Grants to Nonprofit Community Orgs.			0	
045.	Grants to Nonprofit Orgs for Housing Project			75	
046.	Energy Planning			0	
051.	Housing Rehabilitation			75	
TOTALS		\$500,000.00		100%	100

I. PUBLIC FACILITIES RATING AND RANKING CRITERIA - SECTION 085

ii. National Objectives – Section 085

(choose either the benefit to LMI persons **or** the prevention and elimination of slum and blight)

OPTION ONE – LMI persons

BENEFIT TO LOW AND MODERATE INCOME PERSONS (Section 085.01)

Area Benefit Activities	<u> X </u>
Limited Clientele Activities	<u> </u>
Housing Activities	<u> </u>

Calculate percentage of LMI households below:

Total # of LMI persons ÷ Total # of persons = Percentage of LMI

544 LMI persons ÷ 863 Total persons = 63% LMI

How were LMI persons determined? Survey X Census Data

*Note: Attach survey report i.e., sample survey, description of the methodology used, and Survey Tabulation Form, project maps, etc. (See Survey Methodology Appendix 6)

Need and Impact

Describe all the needs of LMI persons (80 points).

In 1992 at public meeting held to complete a community needs assessment for Plummer, called for the immediate attention to health, safety and welfare standards for all community infrastructure. Critical public facility projects were listed for Plummer and the foremost were infrastructure projects related to water and sewer.

On April 28, 1998, Region 10 of the EPA issued a Warning Letter regarding the wastewater treatment facility being out of compliance due to excessive discharge of raw or partially treated wastewater to Plummer Creek. A second letter was issued on March 5, 1999 and an official "Letter of Violation" was issued on 4/15/99. Continued violation has already resulted in a sewer moratorium by IDEQ and may result in substantial fines to the City of Plummer.

This violation letter alone defines the critical need of the LMI persons and confirms that the existing system jeopardizes the health, safety and welfare of all residents of Plummer.

The City of Plummer is actively at work managing the growing influx of persons and businesses into the community. While much of the growth has been in the south east section of the city with ever enlarging Indian housing, the older part of town west of the railroad tracks is also being developed by the Coeur d'Alene Tribe with a new 80 acre mixed use development.

By potentially limiting residential and economic growth, the LMI households are directly affected by the potential loss of jobs related to the loss of such developments. This is critical as Benewah County's unemployment rate continues to decline with the county having almost 14 percent unemployment in October of 1998.

I. PUBLIC FACILITIES RATING AND RANKING CRITERIA - SECTION 085 (cont.)

Describe how the project will impact the LMI needs:

Specific project activities to meet the needs of 63% LMI population include the reduction of infiltration and inflow into the sewer system and the improvement and expansion of the treatment and disposal facility. By reducing the I/I, system capacity will be regained and the overflowing of the manholes and treatment facility will be remedied. By increasing the capacity of the treatment facility, remaining flows and future flows can be treated and disposed to meet the established NPDES discharge permit.

These projects will directly impact the health, safety and welfare concerns which have been documented by three extensive engineering studies and further by the "Letter of Violation" given to Plummer by EPA Region 10. Finally, completion of this project will allow the lifting of the IDEQ sewer moratorium.

In addition, LMI households will benefit through improved community infrastructure which will accommodate future economic growth. The long term impact to LMI households will be the construction of a dependable sanitary sewer system which will meet their needs.

iii. Project Categories (Section 090.01)

Planning, Previous Action and Schedule (160 points)

Describe Planning:

The following steps have been taken in the planning process:

1. Problem Identification: The City has known of their sewer problems for some time. However, problems with the system are beyond the ability of the City to correct utilizing local resources alone. Through town meetings, public hearings and city council meetings, the problems with the sewer system have been identified as a major concern to local residents.
2. The City of Plummer previously hired Hamilton and Voeller to perform a sewer system analysis. In 1994, the City retained Wyatt Engineering to assist a team of Gonzaga University School of Engineering to prepare a wastewater collection system analysis. In 2000, the Indian Health Service completed an additional Sewer System Condition Report to identify the remaining I/I concerns. Finally, the City retained Wyatt Engineering in September 2000 to complete a Wastewater Facilities Plan on the existing treatment and disposal systems.
3. Public Involvement: A public meeting was held in May 1992 to complete a community needs assessment. Personnel from IDOC, RECD, and IDEQ were in attendance. Over 50 residents attended this meeting during which it was determined that the water and sewer system problems were major concerns. This public hearing began the process to look for ways to finance the needed water and wastewater sewer system improvements.
4. In August of 2000, a meeting was held at Plummer. In attendance were representatives from the Coeur d'Alene Tribe, Indian Health Service, Wyatt Engineering, and the City of Plummer. The purpose of the meeting was to review the concerns of the CDA Tribe regarding potential limitations regarding growth due to the failing sewer system. At this meeting financial commitments were addressed and a decision was made to proceed with a CDBG application.

I. PUBLIC FACILITIES RATING AND RANKING CRITERIA - SECTION 085 (cont.)

Describe Planning: (Cont.)

5. Agency Involvement: The Idaho Department of Environmental Quality supports the recommendations outlined in the Wastewater Facilities Plan as well as the overall project. EPA also supports our efforts. Both support the need to preclude degradation of sewer effluent going into Plummer Creek and on to Coeur d'Alene Lake.
6. The City has selected Wyatt Engineering, Inc. for engineering services as well as grant writing and administration services. All procurement requirements were followed in the selection process.
7. The City has \$86,000 in cash in a reserve fund and has completed an in kind I/I removal project totaling \$47,000. Finally, the City has retained Wyatt Engineering to complete a wastewater facilities plan at a cost of \$7,500.
8. The City has adopted a Public Participation Plan and a comprehensive planning committee made up of City Council members and residents will continue to monitor the project.
9. The City completed a sewer rate study in October of 2000 and the sewer rates were adjusted to reflect the changing financial needs of the sewer system. These needs included preparing a capital improvement reserve fund to provide the local cash match for this project.

Describe Previous Actions:

The following previous planning actions have been accomplished:

1. The City, at its own expense, has twice hired consulting engineers to prepare a sewer system engineering report. In addition, the City has hired Wyatt Engineering to complete a Wastewater Treatment and Disposal Facility Plan. This plan was completed in November of 2000 and includes a detailed scope of work, cost estimates, and project schedule.
2. The Indian Health Services has completed a Sewer System Condition Report. This report identifies the collection system problems and outlines recommendations for correction. This report includes a detailed scope of work, cost estimate, and project schedule.
3. The City's matching funds for the project are committed. The City council entered into an agreement with the Indian Health Service to contribute \$86,000 of cash from the sewer reserve funds to support the I/I problems outlined in the IHS report described in item #2 above. In addition the City has completed \$47,000 in I/I removal projects and have spent \$7,500 on a Wastewater Treatment and Disposal Facility Plan.
4. Agency matching funds for the project are committed. The IHS has provided a letter of commitment providing \$380,000 for the project. These funds will be available after the Sewer Deficiency Survey (SDS) list is completed in January of 2001. The Environmental Protection Agency - Region 10 has provided a letter of commitment providing \$189,100 for the project. Finally, USDA-RD has provided a letter committing funds from the RD Native American Set-aside Funds. These funds have been officially requested by Ernest Stensgar, the Tribal Chairman of the Coeur d'Alene Tribe in the letter that is attached in the appendix. The total amount of the USDA-RD funds will be \$1,742,650.

I. PUBLIC FACILITIES RATING AND RANKING CRITERIA - (continued)

Describe Previous Actions: (Cont.)

5. The City of Plummer issued Requests for Proposals for administration and engineering of this wastewater system improvement project. In November, the City selected Wyatt Engineering to provide both the grant administration and engineering on the project. In addition, Wyatt Engineering was retained to complete a Wastewater Treatment and Disposal Facilities Plan to identify improvements to the treatment and disposal facilities to bring them into compliance with future flows and discharge permits.
6. The City Council has recently approved increases to the base sewer rates and the commercial sewer rates. The new commercial rate structure is based on water usage.

With the above actions, the City can insure that the construction of the sewer system improvements can begin in a reasonable time after the CDBG grant is awarded and that construction will be completed on the I/I project by the end of 2001.

iv. Detailed cost analysis (½ page) (40 points). See Rule Section 090.02.

Have costs been established by an engineer or architect?	Yes <u>X</u>	No _____
Have all costs been included, i.e. Davis-Bacon?	Yes <u>X</u>	No _____

A detailed cost estimate has been prepared by Wyatt Engineering and the Indian Health Service. A combination of these estimates have been compiled and are included in the appendix.

Plummer has committed \$140,600 to the project from sewer reserve funds. In a community with 63% LMI persons which is economically depressed, the City council and residents have determined that this is the maximum amount which the residents could afford through rate increases.

v. Certified Gem Communities (20 points). See Rule Section 090.03.

The Plummer Community Action Team was formed out of the GEM Community Committee to carry forth the original goals and projects. The group has changed membership over the years and has completed some of the projects, with many of them continuing. We meet monthly to conduct regular business. We intend to complete an updated GEM plan for the Department of Commerce in November of 2000.

We have a small membership. Our most recent large activity has been to open the Plummer Visitor Center this spring. It is open 20 hours per week on a year-round basis. The Center offers tourists information about the area, Idaho, and surrounding states. Several items are offered for sale at the Center, which help keep it going. A community access computer is available for the public to use for Internet access, work-processing, or other various activities. This summer we helped sponsor Internet classes for the public. We have also completed a draft Business Directory that will be completed soon and available to the public. New entrance signs for Plummer have also been completed; we are currently waiting on permits through the State Transportation Department to place them.

Our goals are to continue promoting Plummer through a community web page, supporting and promoting local businesses, providing free and low-cost computer education to the public, continuing to sponsor Clean Sweep Day, and continue operations at the Visitor Information Center.

Financial Viability Profile For Water And Sewer System Improvements

I. Type of organization: (check one) Water _____ Sewer X

(circle one)

Municipality

Water and/or Sewer District

Non-Profit Company

For-Profit Company

Homeowner's Association

Other (Explain) _____

II. System

A. Briefly describe the geographic area to which you supply services:

The City of Plummer is located in Benewah County and is located approximately 32 miles south of Coeur d'Alene, Idaho along US Highway 95. Service is provided to the entire community within the community boundaries of approximately 1 square mile.

B. Source of water or sewage treatment method:

Sewage is treated by an aerated lagoon system. The effluent is disinfected and discharged to a land application area during the growing season. During winter months, the effluent is chlorinated and then discharged to Plummer Creek after polishing in a sand filter. This discharge can only occur when the flows in Plummer creek exceed 1.5 cfs and the dilution rate is at least 10:1.

C. Number of people served: 990 current residents

D. Number of hook-ups on system: 399 connections

Approximate number of residential hook-ups: 345 connections

Approximate number of commercial hook-ups: 54 connections

Approximate number of industrial hook-ups: na

E. On average, how much water is provided/treated per day: 150,000 gpd

F. Does your organization have certified operators certified by EPA/DEQ: Yes

III. User Rates:

A. How are user rates charged: (circle one)

Per hookup (residential)

Per volume used (commercial)

Other (explain)

B. Current water and sewer user rates: \$ 17.00 per connection

If graduated or progressive rate structure, or different rates for different classes of users, please attach a separate explanation.) **See attached schedule**

C. When was the last rating change? October 1, 2000

D. Does your organization measure water use: Yes X No _____

If yes: (circle one) Meters at user hook-ups Master Meter

Other _____

E. Are testing practices in compliance with DEQ:

Yes X No _____

F. Does your organization have a reserve fund:

Yes X No _____

G. Does your organization have an assessment for some future special need:

Yes _____ No X

If yes, for what purpose and explain how it is assessed: _____

H. Reserve fund balance: \$25,856 is in the Sewer Reserve Fund

IV. Financial Condition:

A. Annual revenues

For customers through rates	\$ 93,900
From other sources (Explain)	\$ 2,000 Crop Revenue
Total Annual Revenues	\$ 95,900

B. Annual expenses

For operations and maintenance	\$ 22,195
For personnel	\$ 27,245
For overhead (office, legal, etc.)	\$ 33,309

For debt service

Federal (agency or program)	\$ 0
State (agency or program)	\$ 0
Private (company)	\$ 0
For other <u>Reserve Fund</u>	\$ 13,151
Total Annual Expense	\$ 95,900

C. Value and description of assets (Sewer Plant)

Land	\$ 0
Buildings	\$ 231,300
Waterworks	\$ 0
Equipment	\$ 62,929
Reserve Funds	\$ 25,856
Other	\$ 0
Total Asset Value	\$ 320,085

D. Outstanding indebtedness: **No outstanding debt**

	Years remaining	Annual payment	Whom to
Bonds	0	0	na
Loans	0	0	na
Other	0	0	na

V. Future needs (List any projects which need to be done within the next five years.)

<u>Description</u>	<u>\$ Amount</u>	<u>Purpose</u> (Renovation, Expansion Water quality, Supply, Etc.)	<u>Priority</u>
I/I Removal	\$ 916,500	Renovation	1
Treatment/Disposal	\$1,933,000	Renovation	2

VI. List two most vulnerable pieces of equipment (potentially subject to failure due to age, damage, out of compliance).

1. **Treatment Lagoons** - Old age has allowed excessive I/I to reach the system and overload the treatment and disposal facilities. This overloading has caused release of raw effluent into Plummer Creek and has resulted in a Letter of Violation from EPA. This system routinely fails and will continue to worsen as flows increase.
2. **Effluent Disposal System** - Due to the excessive flows, the land application area is too small to treat the increased effluent volume. Early spring flows has resulted in release of wastewater effluent on the land while it is still saturated. In addition, the permit limits outlined in the NPDES permit could change. If new limits were imposed which would not allow discharge into Plummer Creek, then the system could not function in the late fall through spring months without violations.

PROJECT SCHEDULE AND ACTIVITY SUMMARY

PROJECT ACTIVITY	Date Completed	Date to be Completed
Grant Writer Procured	November 2000	
Grant Write Contracted		November 2000
Engineering/Architect Procured	November 2000	
Engineering/Architect Contracted		November 2000
Appraiser Secured		November 2001
Acquisition & Relocation Notices Sent		December 2001
Other Agency Apps. Submitted		November 2000
Legal Services Secured	On-Going	
Bond Election Held	N/A	
Bonds Sold or Financing Secured	N/A	
National Objective Documentation Complete (LMI)	1992 (LMI Survey)	
Levy/Fee/Rates Review	October 2000	
Facility/Property Inventory	October 2000	
Reserve Fund Established	October 2000	
Project Maps Drawn	Feb & Nov 2000	
DEQ Facility Plan	November 2000	
Prelim. Engineering/Architect Plan Completed	November 2000	
Permits Identified & Approvals Secured		December 2000
Energy Efficiency Checks	N/A	
Zoning Permits Secured	N/A	
Fees & Special Assessments Identified	N/A	
Application Drafted	October 2000	
Submit Application	November 2000	
First Public Hearing Held	October 2000	
Fire Rating Class Scores	N/A	
State Fire Marshall Reporting	N/A	
Other Agency Approvals	November 2000	
Local Match Secured	Oct-Nov 2000	
Addendum Submitted		March 2001
Grant Award		April 2001
Program Income Reviewed	N/A	
Acquisition Complete and Deed Filed		February 2002
Environmental Review Officer Appointed		April 2001
Environment Review Complete		April 2001
FONSI Published		April 2001
Environmental Release		April 2001
Historic Preservation Cleared		May 2001
Asbestos/Lead Paint Removal Determined	N/A	
Other Environmental Conditions: Reviewed/Permits		June 2001
Demolition Begins	N/A	

PROJECT ACTIVITY	Date Completed	Date to be Completed
Relocation	N/A	
Adoption/Notification of 504 Grievance		April 2001
Adoption/Publication of 504 Policy		May 2001
Establish 504 Review Committee		May 2001
Complete 504 Self Evaluation & Transition Plan		May 2001
Establish Fair Housing Committee		May 2001
Adoption/Notification of Fair Housing Policy		May 2001
Fair Housing Assessment Complete		July 2001
Bid Document Approval		June 2001/Feb. 2002
Final Engineering/Architect Design Approved		July 2001/March 2002
MBE/WBE Solicitation		July 2001
Bids Advertised		July 2001/March 2002
Opening Bids		July 2001/March 2002
Debarred Check		July 2001/March 2002
Hold Preconstruction Conference		July 2001/March 2002
Civil Rights Requirements Completed		July 2001/March 2002
Notice of Bid Award		July 2001/March 2002
Start Construction		Aug 2001/April 2002
Second Public Hearing		September 2001
Construction 25% Complete		Sept 2001/May 2002
Construction 50% Complete		Oct. 2001/July 2002
Construction 75% Complete		Nov. 2001/Sept. 2002
Construction Complete		Dec. 2001/Dec. 2002
Certificate of Substantial Completion Issued		Dec. 2001/Dec. 2002
Monitoring Visit		November 2001
Final Report		Dec. 2001/Dec. 2002
Closeout		Jan. 2002/Jan. 2003
Accounting & Audits		Jan. 2002/Jan. 2003

I. PUBLIC FACILITIES RATING AND RANKING CRITERIA - SECTION 091

iv. Economic Advisory Council Points (Section 091) (200 points):

Describe the Community's ability to finance the project with pure local matching funds: local effort and commitment; the project's local and regional economic impact.

The Block Grant program is the only viable funding option to the City to finance the proposed sewer infiltration/inflow reduction project and the treatment/disposal project. Plummer has raised their sewer rates in 1999 and raised them an additional \$2/month in October of 2000. To leverage \$500,000 of additional local matching funds would increase the monthly bill by almost \$5.50/month! (\$500,000 over 20 years at 5% annual interest and 400 connections) In a community with 63% LMI persons and which is economically depressed (14% county unemployment), residents simply cannot afford another significant increase in utility rates. After addressing citizen concerns about the increase in user rates, the City Council determined that \$140,600 from reserve funds (\$86,000 in cash match plus \$54,600 in an I/I removal project and a wastewater facility plan) is the maximum amount that residents could afford to fund. These committed reserve funds are a result of the recent rate increases.

As discussed in the Previous Action section of the application, all possible measures have been taken to ensure that construction can begin as soon as the CDBG grant awards are announced. Local matching funds for the project have been secured and the project team selections complete. In addition, the numerous funding partners (IHS, EPA, USDA-RD) are all excited about the project and have committed their resources. This project is ready to go!

The impact of a successful Block Grant application will protect the health, safety and economy of the community by:

1. Preventing presently overflowing surcharged manholes from pouring excess rain water mixed with sanitary sewer flows out on to the city's streets
2. Preventing sewer lagoon overflow which goes into a creek that flows to Lake Coeur d'Alene
3. ***Respond to the EPA "Letter of Violation" and removal of the IDEQ sewer moratorium by meeting the NPDES permit requirements.***

Local economic impact: With the sewer moratorium lifted, additional business and home expansions planned as part of the Coeur d'Alene Tribe development on the north side of Plummer can proceed. This 80 acre project will create new jobs in Plummer and will allow the building of new homes (approximately 10 every other year) by the Coeur d'Alene Tribal Housing Authority, along with enhancing the potential for the community's future economic growth.

Regional Impact: The Coeur d'Alene Tribe has indicated that if this project cannot be funded that they may have to construct their own wastewater facility to treat the water from their new development. This would remove an important funding source from the City of Plummer in trying to improve their existing system. It would also create a redundant system while leaving Plummer's in a state of disrepair. By working together, all goals can be met and the health, safety and welfare of all of the Plummer citizens can be maintained and improved.

This project is a major undertaking brought on by the continuing interest of the Coeur d'Alene Tribe. The City has taken several major steps toward the solution outlined in this application. They have worked with various agencies, IHS, EPA, RECD, DEQ and IDOC to insure they are exploring all possible solutions. While the City of Plummer has the ability to fund a portion of the proposed sewer system improvements, the total scope of work is out of their reach.

I. PUBLIC FACILITIES RATING AND RANKING CRITERIA - SECTION 091 (Cont.)

iv. Economic Advisory Council Points (Section 091) (200 points): (Cont.)

Describe any other benefits of the project or extenuating circumstances why this project should be funded.

The City of Plummer respectfully submits the following reasons why the Advisory Council should fund the proposed waste water system improvement project:

1. The critical health and safety concerns of the residents are the paramount issues in funding this application. The "Letter of Violation" from the EPA and the sewer moratorium imposed by the IDEQ define a critical need. These issues cannot be ignored for Plummer to remain a viable community!
2. If the project is not funded, the Coeur d'Alene Tribe may construct their own facility to support their development. This non-regional solution would remove an important funding partner from the project and would create a redundant system while the City of Plummer system continued to worsen.
3. Plummer has only two possible sources of funding (CDBG and bonds). The City cannot afford to again finance through bonds having recently done so for a major water improvement project. Plummer has raised sewer rates for the last two years to secure the reserve funds committed to this project. Plummer needs the CDBG or they will be forced to abandon the project.
4. The continued creation of new jobs in Plummer would be in serious jeopardy if this project is not undertaken. With the sewer moratorium in place, new connections (both residential and commercial) are not allowed. If new business cannot connect then they will not locate in Plummer. The City needs this requested block grant in order to undertake this project.
5. The City has twice, at its own expense, retained consulting engineering firms to prepare engineering reports on the sewer system. In addition, the IHS has completed a sewer system report and Wyatt Engineering has recently completed a Wastewater Treatment and Disposal Facility Plan. Upon notification of a successful block grant application, construction of the inflow and infiltration removal project is ready to proceed and will be completed by late 2001.

This project will not only improve the health and safety of residents by providing safe handling of sewage but permit newly developed property to be added to the tax roles and other property to be available for development. The commitment of the City to plan and expend City funds in advance of the approval of this block grant is an indication of their feeling for the ultimate necessity for this project. The renovation of the sewer system will allow the City to continue to encourage the further development of residential areas and local industrial expansion and thus position Plummer for gains in economic vitality. It will show the commitment of the City and the Department of Commerce to react to the growth in this part of the State of Idaho by improving infrastructure in Plummer and, subsequently, prepare for oncoming much needed growth in this community.

J. Appendix -Additional Information from Applicant (Section 074.10)

1. ***Vicinity and Project Maps***
 - a. Vicinity Map
 - b. Site Map
 - c. I/I Reduction Map - IHS
 - d. Treatment and Disposal Flow Diagram - Wyatt
2. ***Engineers Cost Estimate***
3. ***Letters and Articles***
 - a. Journal of Business - Information Article - 11/8/00
 - b. IHS Letter - Letter of Financial Commitment & Support - 11/15/00
 - c. IDEQ Letter - Letter of Support - 11/14/00
 - d. US-EPA Letter - Letter of Financial Commitment & Support - 11/14/00
 - e. City of Plummer Letter - Local Construction Match - 11/13/00
 - f. County of Benewah Letter - Letter of Support - 11/6/00
 - g. USDA-RD Letter - Letter of Pending Financial Commitment & Support - 11/3/00
 - h. Coeur d'Alene Tribe Letter - Letter of Support - 10/31/00
 - i. Coeur d'Alene Tribe Letter - Letter Requesting Financial Support - 10/31/00
 - j. IDEQ Letter - Moratorium Letter Reminder 9/19/00
 - k. IDEQ Letter - 1999 Annual Report (concurrence with I/I success) - 2/2/00
 - l. EPA Letter of Violation - Request for Information - 4/15/99
 - m. EPA 2nd Warning Letter - 3/15/99
 - n. EPA Warning Letter - 4/29/98
 - o. Coeur d'Alene Tribe Letter - April 29, 1993
4. ***Resolutions and Publications***
 - a. Citizens Participation Plan
 - b. Notice of Public Hearings
 - c. Public Hearing Minutes
5. ***Procurement Documentation***
6. ***LMI Survey Methodology and Survey Form***
7. ***Financial Viability Profile***
8. ***Sewer Rate Study***

APPENDIX II

1999-2002 Flow Monitoring Data

City Of Plummer Month of Jan 1999

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1														
2											0.108			
3											0.149			
4	Cloudy	18				6.62		13	5	0.74	0.143	80	55	0.1
5	Clear	28							5		0.112	80	55	0.1
6	Cloudy	24				6.79		6	5	0.69	0.125	80	55	0.1
7	Snow	28							5		0.125	80	55	0.1
8	Cloudy	26				6.75		5	5	0.17	0.15	80	55	0.1
9											0.162			
10											0.159			
11	PrtCldy	36				6.95		6	5	0.3		80	55	0.1
12	Cloudy	30							5			80	55	0.1
13	PrtCldy	36				6.92		12	5	0.29		80	55	0.1
14	Rain	36							5		0.148	80	55	0.1
15	Rain	30				6.94		18	5	0.22	0.076	80	55	0.1
16														
17											0.095			
18	Cloudy	38				7		19	5	0.29	0.13	80	55	0.1
19	Cloudy	37							5		0.13	80	55	0.1
20	Rain	35				6.98		6	5	0.33	0.13	80	55	0.1
21	Snow	30									0.18	80	55	0.1
22	Snow	34				6.79		6	5	0.3	0.148	80	55	0.1
23											0.184			
24														
25	Cloudy	18				6.77		24	5	0.23	0.174	80	55	0.1
26	Cloudy	12							5		0.176	80	55	0.1
27	Cloudy	18				6.73		5	5	0.3	0.18	80	55	0.1
28	Cloudy	30							5		0.108	80	55	0.1
29	PrtCldy	30				6.77		15	5	0.42	0.108	80	55	0.1
30											0.078			
31											0.092			
AVG		28.7	ERR	ERR	ERR	6.8342	ERR	11.25	5	0.356667		80	55	0.1
MAX		38	ERR	ERR	ERR	7	ERR	24	5	0.74	0.307	80	55	0.1
MIN		12	ERR	ERR	ERR	6.62	ERR	5	5	0.17	0.067	80	55	0.1

City Of Plummer Month of Feb

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	Clear	18				6.84		21	5	0.62	0.098	80	55	0.1
2	Snow	30							5		0.188	80	55	0.1
3	PrtCldy	20				6.88		7	5	0.91	0.08	80	55	0.1
4	PrtCldy	25							5		0.249	80	55	0.1
5	Clear	16				6.81		23	5	0.98	0.287	80	55	0.1
6											0.182			
7											0.108			
8	Clear	22				6.98		20	5	0.59	0.266	80	55	0.1
9	Clear	16							5		0.148	80	55	0.1
10											0.128	80	55	0.1
11	Clear	16							5		0.068	80	55	0.1
12	Clear	18				6.81		13	5	1.15	0.081	80	55	0.1
13											0.086			
14											0.14			
15	PrtCldy	20				7.02		20	5	0.21	0.185	80	55	0.1
16	Snow	32							5		0.197	80	55	0.1
17	Cloudy	30				6.86		6	5	1.07	0.267	80	55	0.1
18	Clear	22							5			80	55	0.1
19	Snow	35				6.73		7	5	0.11	0.135	80	55	0.1
20											0.401			
21											0.263			
22	Cloudy	20				6.76		7	5	0.16	0.287	80	55	0.1
23	Cloudy	28							5		0.266	80	55	0.1
24	Rain	34							5		0.286	80	55	0.1
25	Rain	32							10		0.244	80	55	0.1
26	Cloudy	26				6.85		16	10	0.09	0.177	80	55	0.3
27											0.141			

28.
29
30
31

0.263

AVG	24.21053	ERR	ERR	ERR	6.854	ERR	14	5.526316	0.589		80	55	0.11
MAX	35	ERR	ERR	ERR	7.02	ERR	23	10	1.15	0.401	80	55	0.3
MIN	16	ERR	ERR	ERR	6.73	ERR	6	5	0.09	0.068	80	55	0.1

City Of Plummer Month of March 1999

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	Snow	28							10		0.277	80	55	0.5
2	Foggy	22							10		0.084	80	55	0.5
3	Cloudy	36				6.68		5	10	0.11	0.104	80	55	0.5
4	Snow	34							10		0.084	80	55	0.1
5	Cloudy	20				6.66		6	10	0.13	0.071	80	55	0.1
6											0.056			
7														
8	Cloudy	15				6.57		9	10	0.17		80	55	0.1
9	Cloudy	20							10		0.161	80	55	0.1
10	Foggy	20				6.53		15	5	0.17	0.141	80	55	0.1
11	Cloudy	18							5		0.04	80	55	0.1
12	PrtCldy	18				6.57		15	5	0.16	0.078	80	55	0.1
13											0.066			
14											0.098			
15	Cloudy	26				6.5		28	5	0.04	0.04	80	55	0.1
16	Cloudy	25							5		0.174	80	55	0.1
17	PrtCldy	23				6.57		20	5	0.06	0.133	80	55	0.1
18	PrtCldy	31							5		0.136	80	55	0.1
19	Clear	40				6.47		17	5	0.06	0.179	80	55	0.1
20											0.1			
21											0.117			
22	Foggy	32				6.65		10	5	0.13	0.152	80	55	0.1
23	Snow	28							5		0.112	80	55	0.1
24	Cloudy	26				6.67		8	5	0.12	0.108	80	55	0.1
25	Rain	34							5		0.135	80	55	0.1
26	Cloudy	30				6.7		10	5	0.15	0.304	80	55	0.1
27											0.261			
28											0.235			
29	Snow	32				6.65		8	5	0.19	0.301	80	55	0.1
30	Snow	28							5		0.274	80	55	0.1
31	Cloudy	20				6.69		9	5	0.1	0.212	80	55	0.1
AVG		26.34783	ERR	ERR	ERR	6.6085	ERR	12.308	6.521739	0.122308		80	55	0.1521739
MAX		40	ERR	ERR	ERR	6.7	ERR	28	10	0.19	0.304	80	55	0.5
MIN		15	ERR	ERR	ERR	6.47	ERR	5	5	0.04	0.04	80	55	0.1

City Of Plummer Month of April 1999

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	Clear	18							5		0.115	80	55	0.1
2	Clear	20				6.74		12	5	0.08	0.074	80	55	0.1
3											0.169			
4											0.244			
5	Snow	18				6.68		7		0.14	0.269	80	55	0.1
6	Foggy	16							5		0.193	80	55	0.1
7	Clear	16				7.73		6	5	0.08	0.174	80	55	0.1
8	Rain	30							5		0.274	80	55	0.1
9	PrtCldy	22				6.7		9	5	0.7	0.327	80	55	0.1
10											0.226			
11											0.183			
12	Cloudy	27				6.73		5	5	0.2	0.154	80	55	0.1
13	PrtCldy	32							5		0.143	80	55	0.1
14	Clear	26				6.7		5	10	0.4	0.177	80	55	0.1
15	Clear	45							10		0.124	80	55	0.1
16	Clear	39				6.7		5	10	0.04	0.086	80	55	0.1
17											0.124			

18.											0.125						
19 Cloudy	42					6.93		4	10	0.01	0.119	80	55	0.1			
20 Cloudy	37								10		0.126	80	55	0.1			
21 Clear	32					6.94		3	10	0.04	0.12	80	55	0.1			
22 Rain	32								10		0.117	80	55	0.1			
23 Clear	30					6.97		5	10	0.04	0.125	80	55	0.1			
24											0.114						
25											0.108						
26 Clear	33					6.83		5	10	0.04	0.135	80	55	0.1			
27 Clear	28								10		0.122	80	55	0.1			
28 Clear	32					7.25		4	10	0.04	0.12	80	55	0.1			
29 PrtCldy									10		0.122	80	55	0.1			
30 PrtCldy	34					7.31		7	10	0.05	0.113	80	55	0.1			
31																	
AVG	29	ERR	ERR	ERR	ERR	6.9392	ERR	5.9231	8.095238	0.143077	0.154067	80	55	0.1			
MAX	45	ERR	ERR	ERR	ERR	7.73	ERR	12	10	0.7	0.327	80	55	0.1			
MIN	16	ERR	ERR	ERR	ERR	6.68	ERR	3	5	0.01	0.074	80	55	0.1			

City Of Plummer Month of May

May 1999

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1											0.109			
2											0.114			
3 Rain	34								10	0.05	0.21	80	55	
4 Snow	25								10		0.32	80	55	
5 Clear	24										0.225	80	55	
6 Cloudy	20										0.16	80	55	
7 Cloudy	32										0.144	80	55	
8											0.201			
9											0.134			
10 Clear	18										0.129	80	55	
11 Foggy	20										0.122	80	55	
12 Cloudy	36										0.12	80	55	
13 PrtCldy	32										0.124	80	55	
14 Clear	34										0.112	80	55	
15											0.109			
16											0.105			
17 PrtCldy	45										0.102	80	55	
18 PrtCldy	40										0.099	80	55	
19 Sunny	38										0.106	80	55	
20 PrtCldy	32										0.102	80	55	
21 Clear	32										0.114	80	55	
22											0.11			
23											0.102			
24 Clear	40										0.101	80	55	
25 Clear	50										0.101	80	55	
26 Clear	37										0.095	80	55	
27 Clear	36										0.095	80	55	
28 Clear	40										0.092	80	55	
29											0.081			
30											0.066			
31											0.066			
AVG	33.25	ERR	ERR	ERR	ERR	0	ERR	0	6.666667	0.025	0.124839	80	55	ERR
MAX	50	ERR	ERR	ERR	ERR	0	ERR	0	10	0.05	0.32	80	55	ERR
MIN	18	ERR	ERR	ERR	ERR	0	ERR	0	0	0	0.066	80	55	ERR

City Of Plummer Month of June

June 1999

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1 Clear	40								20	0.22	0.082	80	55	
2 Rain	40								20		0.077	80	55	
3 Clear	40								20		0.106	80	55	
4 Clear	42								20	0.22	0.114	80	55	0.314
5									20		0.091			
6									20		0.084			
7 Clear	32								20		0.081	80	55	

8. PrtCldy	38								20		0.076	80	55	
9 PrtCldy	38								20		0.074	80	55	
10 PrtCldy	38								20	0.091	0.071	80	55	0.314
11 Clear									20		0.076	80	55	
12									20		0.076			
13									20		0.066			
14 Clear	51								20		0.067	80	55	
15 Clear	54								20	0.37	0.069	80	55	0.314
16 Clear	54								20		0.074	80	55	0.314
17									20		0.076			
18 Rain	54								20		0.076	80	55	0.314
19									20		0.073			
20									20		0.073			
21 Rain	48								20		0.075	80	55	
22 Cloudy	40								20		0.075	80	55	
23 Cloudy	48								20	0.1	0.071	80	55	0.314
24 Cloudy	42								20		0.067	80	55	
25 Rain	40								20		0.08	80	55	
26									20		0.117			
27									20		0.043			
28 Clear	34								20	0.06	0.057	80	55	0.314
29 PrtCldy	44								20		0.092	80	55	0.1345
30 Clear	48								20		0.092	80	55	0.1345
31														
AVG	43.25	ERR	ERR	ERR	ERR	ERR	ERR	ERR	20	0.151571	0.078367	80	55	0.2741111
MAX	54	ERR	ERR	ERR	ERR	ERR	ERR	ERR	20	0.37	0.117	80	55	0.314
MIN	32	ERR	ERR	ERR	ERR	ERR	ERR	ERR	20	0	0.043	80	55	0.1345

City Of Plummer Month of July

July 1999

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	Clear	48							10		0.111	80	55	
2	Clear	40							10	0.14	0.115	80	55	0.1545
3									10		0.095	80	55	
4									10		0.097	80	55	
5									10		0.107	80	55	
6	Clear	45							10	0.99	0.115	80	55	0.1845
7	Clear	50							10	0.5	0.097	80	55	0.1845
8	Clear	44							10	0.48	0.112	80	55	0.1845
9	Clear	40							10	0.42	0.088	80	55	0.1845
10									10		0.079			
11									10		0.072			
12	Clear	55							10	0.45	0.073	80	55	0.314
13	Clear	55							10	0.37	0.072	80	55	0.314
14	Clear	54							10	0.32	0.076	80	55	0.314
15	Clear	48							10		0.077	80	55	
16	Clear	48							10		0.072	80	55	
17									10		0.073			
18									10		0.067			
19	Foggy	40							10	0.28	0.069	80	55	0.314
20	Clear	45							10	0.19	0.073	80	55	0.314
21	Clear	50							10		0.075	80	55	
22	Clear	46							10		0.069	80	55	
23	Clear	48							10	0.36	0.073	80	55	0.314
24									10		0.068			
25									10		0.063			
26	Clear	44							10	0.24	0.07	80	55	0.314
27	Clear	46							10		0.071	80	55	
28	Clear	54							10		0.07	80	55	0.314
29	Clear	56							10	0.03	0.069	80	55	0.314
30	Clear	50							10		0.066	80	55	
31											0.076			
AVG		47.90476	ERR	ERR	ERR	ERR	ERR	ERR	10	0.366923	0.080968	80	55	0.2656071
MAX		56	ERR	ERR	ERR	ERR	ERR	ERR	10	0.99	0.115	80	55	0.314
MIN		40	ERR	ERR	ERR	ERR	ERR	ERR	10	0.03	0.063	80	55	0.1545

City Of Plummer Month of August

Aug 1999

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1											0.062			
2	PrtCldy	54							10	0.28	0.068	80	55	0.314
3	PrtCldy	56							10		0.067	80	55	
4	PrtCldy	62							10	0.23	0.061	80	55	0.314
5	Clear	54							10	0.23	0.073	80	55	0.314
6	Clear	54							10		0.079	80	55	
7									10		0.093			
8									10		0.117			
9	Foggy	46							10		0.092	80	55	
10	Clear	44							10	0.24	0.075	80	55	0.314
11	Clear	56							10		0.075	80	55	
12	Clear	46							10	0.28	0.074	80	55	0.314
13	PrtCldy	44							10	0.45	0.073	80	55	0.314
14											0.077			
15											0.071			
16	Clear	42							10	0.45	0.077	80	55	0.314
17	Clear	38							10		0.08	80	55	0
18	Clear	46							10	0.14	0.071	80	55	0.314
19	Clear	56							10		0.068	80	55	
20	Clear	48							10	0.34	0.063	80	55	0.314
21											0.063			
22											0.062			
23	Clear	40							10	0.44	0.059	80	55	0.314
24	Clear	52							10		0.063	80	55	
25	PrtCldy	56							10	0.44	0.064	80	55	0.314
26	Clear	42							10		0.06	80	55	
27	Clear	44							10	0.02	0.067	80	55	
28											0.06			
29											0.061			
30	Clear	50								0.57	0.051	80	55	0.314
31	Clear	46									0.055	80	55	
AVG		48.90909	ERR	ERR	ERR	ERR	ERR	ERR	10	0.316154	0.070355	80	55	0.2898462
MAX		62	ERR	ERR	ERR	ERR	ERR	ERR	10	0.57	0.117	80	55	0.314
MIN		38	ERR	ERR	ERR	ERR	ERR	ERR	10	0.02	0.051	80	55	0

City Of Plummer Month of Sept.

Sept 1999

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	Foggy	32							10	0.056	0.056	80	55	0.314
2	Foggy	35							10		0.073	80	55	
3	Foggy	42							10	0.055	0.059	80	55	0.314
4											0.058			
5											0.054			
6											0.059			
7	Clear	32									0.056	80	55	
8	Clear	25									0.061	80	55	
9	Clear	32									0.069	80	55	
10	Clear	44									0.074	80	55	
11											0.068			
12											0.058			
13	Clear	35									0.067	80	55	
14	Clear	30									0.065	80	55	
15											0.066			
16											0.064			
17											0.068			
18											0.065			
19											0.065			
20	Clear	36									0.077	80	55	
21	Clear	38									0.07	80	55	
22	Clear	38									0.068	80	55	
23	Clear	40									0.069	80	55	
24	PrtCldy	44									0.058	80	55	
25											0.062			
26											0.067			
27	Foggy	26									0.07	80	55	
28	Clear	20									0.073	80	55	
29	Cloudy	30									0.063	80	55	

30. Clear 28 0.065 80 55
31

	AVG	33.72222	ERR	ERR	ERR	ERR	ERR	ERR	ERR	10	0.0545	0.0649	80	55	0.314
MAX	44	ERR	ERR	ERR	ERR	ERR	ERR	ERR	ERR	10	0.056	0.077	80	55	0.314
MIN	20	ERR	ERR	ERR	ERR	ERR	ERR	ERR	ERR	10	0.055	0.054	80	55	0.314

City Of Plummer Month of October

Oct 1999

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	Clear	25									0.062	80	55	
2	Clear										0.061	80	55	
3											0.062	80	55	
4	Clear	25									0.066	80	55	
5	Cloudy	30							10		0.066	80	55	
6	Cloudy	35									0.065	80	55	
7	Cloudy	35								0.41	0.067	80	55	0.314
8	Cloudy	40							10	0.4	0.097	80	55	0.314
9											0.137			
10											0.088			
11	Cloudy	35								0.19	0.079	80	55	0.314
12	Cloudy	40							10		0.079	80	55	
13	Cloudy	45							10	0.14	0.074	80	55	0.314
14	Cloudy	35							15		0.076	80	55	
15	Clear	35									0.079	80	55	
16											0.08			
17											0.08			
18	Clear	30							15		0.085	80	55	
19	Clear	30							15	0.73	0.074	80	55	0.314
20	Clear	30							10		0.061	80	55	
21	Clear	30							10	0.23	0.063	80	55	0.314
22	Clear	30									0.061	80	55	
23														
24														
25	PrtCldy	32							15		0.088	80	55	
26		42							15		0.077	80	55	
27		30							15	0.74	0.07	80	55	0.314
28	Rain	42									0.0144	80	55	0.1
29	Cloudy	32									0.0158			
30											0.076			
31											0.076			
AVG		33.71429	ERR	ERR	ERR	ERR	ERR	ERR	11.53846	0.355	0.071697	80	55	0.28725
MAX		45	ERR	ERR	ERR	ERR	ERR	ERR	15	0.74	0.137	80	55	0.314
MIN		25	ERR	ERR	ERR	ERR	ERR	ERR	0	0	0.0144	80	55	0.1

City Of Plummer Month of Nov.

Nov 1999

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	Foggy	18									0.096	80	55	
2	Clear	28									0.072	80	55	
3	Clear	22									0.069	80	55	
4	Cloudy	33									0.071	80	55	
5	Cloudy	24									0.074	80	55	
6											0.087			
7											0.182			
8	Cloudy	34									0.081	80	55	
9	Foggy	38									0.083	80	55	
10	Rain	42									0.085	80	55	
11	Cloudy	42									0.086	80	55	
12	Cloudy	57									0.092	80	55	
13											0.136			
14											0.13			
15	Cloudy	28									0.092	80	55	
16	Cloudy	27									0.082	80	55	
17	Rain	38									0.083	80	55	
18	Clear	30									0.173	80	55	
19	Cloudy	34									0.11	80	55	

20-											0.102			
21											0.092			
22	Clear	25									0.06	80	55	
23	Cloudy	33									0.1	80	55	
24	Clear	35									0.113	80	55	
25											0.191			
26											0.247			
27											0.274			
28											0.171			
29	Clear	33									0.129	80	55	
30	Rain	38									0.088	80	55	
31														
AVG		32.95	ERR	ERR	ERR	ERR	ERR	ERR	ERR	ERR	0.115033	80	55	ERR
MAX		57	ERR	ERR	ERR	ERR	ERR	ERR	ERR	ERR	0.274	80	55	ERR
MIN		18	ERR	ERR	ERR	ERR	ERR	ERR	ERR	ERR	0.06	80	55	ERR

City Of Plummer Month of Dec.

Dec 1999

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	Snow	32							10		0.208	80	55	0
2	Rain	34							10		0.268	80	55	0.1
3	Clear	20				7.51		6	10	0.43	0.195	80	55	0
4											0.36			
5											0.232			
6	Snow	33				7.51		4	5	0.21	0.24	80	55	0.1
7	Cloudy	33							5		0.298	80	55	0.1
8	Cloudy	32				7.4		6	5	0.14	0.295	80	55	0.1
9	Snow	32							5		0.109	80	55	0.1
10	Cloudy	34				7.36		5	5	0.06	0.133	80	55	0.1
11											0.168			
12											0.126			
13	Clear	25				7.42		6	5	0.09	0.123	80	55	0.1
14	Snow	32							5		0.323	80	55	0.1
15	Rain	38							5		0.265	80	55	0.1
16	Cloudy	42							5		0.244	80	55	0.1
17	Foggy	28				7.36		6	5	0.11	0.18	80	55	0.1
18											0.276			
19											0.325			
20	PrtCldy	25				7.21		6	5	0.04	0.279	80	55	0.1
21	Cloudy	28							5		0.233	80	55	0.1
22	Cloudy	28				7.21		6	5	0.01	0.208	80	55	0.1
23											0.229			
24											0.22			
25											0.214			
26											0.22	80	55	0.1
27	Clear	28				7.16		5	5	0.01	0.22	80	55	0.1
28	Clear	25				7.1		6	5	0.02	0.156	28		
29											0.115			
30											0.112			
31														
AVG		30.5	ERR	ERR	ERR	7.324	ERR	5.6	5.833333	0.112	0.219133	77.26316	55	0.0888889
MAX		42	ERR	ERR	ERR	7.51	ERR	6	10	0.43	0.36	80	55	0.1
MIN		20	ERR	ERR	ERR	7.1	ERR	4	5	0.01	0.109	28	55	0
AVG		30.86111	ERR	ERR	ERR	7.3053	ERR	5.4667	ERR		0.122205			
MAX		42	ERR	ERR	ERR	7.51	ERR	6	ERR		0.401			
MIN		20	ERR	ERR	ERR	7.1	ERR	4	ERR		0.0144			

City Of Plummer Month of

Jan

2000

Date	Weather	Temp (F)	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1									0.102			
2									0.118			
3	Cloudy	20		7.04		6	5	0.02	0.122	80	55	0.1
4	Snow	30					5		0.11	80	55	0.1
5	Cloudy	25		7.06		10	5	0.11	0.231	80	55	0.1
6	Clear	20							0.262	80	55	0.1
7	Cloudy	30		6.7		8	5	0.12	0.2	80	55	0.1
8									0.2			
9									0.245			
10									0.297			
11	Cloudy	32				9	5	0.12	0.253	80	55	0.1
12	Clear	28				14	5	0.22	0.227	80	55	0.1
13									0.202			
14	Clear	36		6.92		8	5	0.06	0.135	80	55	0.1
15									0.24			
16									0.15			
17	Clear	20		7		7	5	0.13	0.115	80	55	0.1
18	Cloudy	18					5		0.266	80	55	0.1
19	Snow	25		6.92		12	5	0.13	0.306	80	55	0.1
20	Snow	28					5		0.257	80	55	0.1
21	Snow	28		6.9		4	5	0.03	0.257	80	55	0.1
22									0.21			
23									0.199			
24	Cloudy	28		6.85		10	5	0.14	0.191	80	55	0.1
25	Snow	30					5		0.189	80	55	0.1
26	Snow	26		6.84		16	5	0.01	0.188	80	55	0.1
27	Snow	25					5		0.187	80	55	0.1
28	Foggy	20		6.83		6	5	0.03	0.183	80	55	0.1
29									0.179			
30									0.178			
31	Snow	18		6.92	4	4	5	0.16	0.178	80	55	0.1
AVG		25.6316	ERR	6.90727	4	8.76923	5	0.098462	0.199258	80	55	0.1
MAX		36	ERR	7.06	4	16	5	0.22	0.306	80	55	0.1
MIN		18	ERR	6.7	4	4	5	0.01	0.102	80	55	0.1

City Of Plummer Month of

Feb

2000

Date	Weather	Temp (F)	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	Rain	34					5		0.186	80	55	0.1
2	Rain	37					5		0.232	80	55	0.1
3	Clear	15					5		0.273	80	55	0.1
4	Clear	18		6.98		12	5	0.08	0.234	80	55	0.1
5									0.097			
6									0.252			
7	Foggy	34		6.75		10	5	0.06	0.204	80	55	0.1
8	Clear	35					5		0.212	80	55	0.1
9	Clear	33		6.82		14	5	0.14	0.141	80	55	0.1
10	Foggy	18					5		0.165	80	55	0.1
11	Cloudy	25		6.76		17	5	0.11	0.045	80	55	0.1
12									0.045			
13									0.076			
14	Snow	33		6.89		9	5	0.13	0.071	80	55	0.1
15	Snow	32					5		0.045	80	55	0.1
16	Foggy	26		6.88		16	5	0.12	0.204	80	55	0.1
17	Foggy	16					5		0.114	80	55	0.1
18	Cloudy	10		6.93		16	5	0.08	0.05	80	55	0.1
19									0.053			
20									0.151			
21									0.195			
22	Foggy	39		6.77		20	5	0.12	0.197	80	55	0.1
23	Snow	34					5		0.245	80	55	0.1
24	Clear	30		6.73		5	5	0.04	0.295	80	55	0.1
25	Foggy	20					5		0.145	80	55	0.1
26									0.116			
27									0.098			
28	Rain	36					5		0.119	80	55	0.1

29 .Cloudy	34		6.73		11	5	0.06	0.154	80	55	0.1
30											
31											
AVG	27.95	ERR	6.824	ERR	13	5	0.085455	0.152207	80	55	0.1
MAX	39	ERR	6.98	ERR	20	5	0.14	0.295	80	55	0.1
MIN	10	ERR	6.73	ERR	5	5	0	0.045	80	55	0.1

City Of Plummer Month of

March 2000

Date	Weather	Temp (F)	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	PrtCldy	30					5		0.143	80	55	0.1
2	Clear	34		6.7		10	5	0.08	0.1	80	55	0.1
3	Clear	40					5		0.081	80	55	0.1
4									0.079			
5									0.204			
6	Cloudy	34		6.75		9	5	0.14	0.238	80	55	0.1
7	Cloudy	34					5		0.218	80	55	0.1
8	Rain	32		6.6		5	5	0.11	0.113	80	55	0.1
9	Foggy	33					5		0.07	80	55	0.1
10	Clear	35		6.74		9	5	0.13	0.05	80	55	0.1
11									0.065			
12									0.145			
13	Cloudy	25		6.75		10	5	0.03	0.065	80	55	0.1
14	PrtCldy	38					5		0.053	80	55	0.1
15	Clear	23		6.69		5	5	0.05	0.259	80	55	0.1
16	Cloudy	35					5		0.239	80	55	0.1
17	Clear	23		6.73		6	5	0.03	0.149	80	55	0.1
18									0.169			
19									0.169			
20	Foggy	20		6.7		10	5	0.07	0.127	80	55	0.1
21	Cloudy	28					5		0.074	80	55	0.1
22	Snow	30		6.71		11	5	0.08	0.05	80	55	0.1
23	Cloudy	32					5		0.061	80	55	0.1
24	Clear	27		6.74		12	5	0.08	0.147	80	55	0.1
25									0.189			
26									0.129			
27	Cloudy	28		6.78		5	5	0.04	0.098	80	55	0.1
28	Snow	32					5		0.098	80	55	0.1
29	Cloudy	28		6.69		10	5	0.07	0.077	80	55	0.1
30	PrtCldy	23					5		0.043	80	55	0.1
31	Clear	28		6.71		9	5	0.03	0.127	80	55	0.1
AVG	30.087		ERR	6.71462	ERR	8.53846	5	0.072308	0.123516	80	55	0.1
MAX	40		ERR	6.78	ERR	12	5	0.14	0.259	80	55	0.1
MIN	20		ERR	6.6	ERR	5	5	0.03	0.043	80	55	0.1

City Of Plummer Month of

April

2000

Date	Weather	Temp (F)	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1									0.059			
2									0.03			
3	Clear	30		6.71		10	5	11	0.035	80	55	0.1
4	PrtCldy	43					5		0.116	80	55	0.1
5	Clear	27		6.72		7	5	0.11	0.083	80	55	0.1
6	Snow	32					5		0.069	80	55	0.1
7	Clear	25		6.7		6	5	0.11	0.08	80	55	0.1
8									0.058			
9									0.048			
10	Clear	27		6.74		8	5	0.01	0.055	80	55	0.1
11	PrtCldy	25					5		0.09	80	55	0.1
12	PrtCldy	40		6.72		5	5	0.1	0.09	80	55	0.1
13	Rain	43					5		0.038	80	55	0.1
14	Rain	38					5		0.098	80	55	0.1
15									0.151			
16									0.152			
17	Foggy	40		6.71		10	5	0.3	0.311	80	55	0.1
18	Sunny	40					5		0.144	80	55	0.1
19	PrtCldy	42		6.73		9	5	0.3	0.088	80	55	0.1

20	Clear	34				5		0.054	80	55	0.1
21	Foggy	36	6.74		6	5	0.3	0.044	80	55	0.1
22								0.069			
23								0.061			
24	Clear	27	6.7		6	5	0.8	0.147	80	55	0.1
25	Cloudy	35				5		0.121	80	55	0.1
26	Foggy	30	6.73		5	5	0.1	0.054	80	55	0.1
27	Clear	36			5	5		0.074	80	55	0.1
28	Rain	30	6.73		8	5	0.1	0.092	80	55	0.1
29								0.122			
30								0.123			
31											
	AVG	34	ERR 6.72091	ERR 7.08333		5	1.202727	0.091867	80	55	0.1
	MAX	43	ERR 6.74	ERR 10		5	11	0.311	80	55	0.1
	MIN	25	ERR 6.7	ERR 5		5	0.01	0.03	80	55	0.1

City Of Plummer Month of

May

2000

Date	Weather	Temp (F)	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	PrtCldy	45		6.74			5	0.03	0.134	80	55	0.1
2	Rain	48					5		0.049	80	55	0.1
3	Rain	50					5		0.209	80	55	
4	Rain	38					5		0.076	80	55	
5	Foggy	40					5		0.035	80	55	
6									0.121			
7									0.125			
8	Clear	34					5		0.127	80	55	
9	Rain	42					5		0.121	80	55	
10	PrtCldy	37					5		0.19	80	55	
11	Snow	32					5		0.127	80	55	
12	Cloudy	36					5		0.133	80	55	
13									0.075			
14									0.02			
15	Clear	46					5		0.106	80	55	0.1
16	Clear	48		6.65		0.7	5	0.01	0.084	80	55	0.1
17	Cloudy	45					5		0.139	80	55	0.1
18	Clear	48					5		0.136	80	55	0.1
19	Rain	45		6.69		1	5		0.151	80	55	0.1
20									0.152	80	55	0.1
21									0.141	80	55	0.1
22	Clear	50					5		0.145	80	55	0.1
23	PrtCldy	48		6.74		0.9	5		0.143	80	55	0.1
24	Clear	50					5		0.132	80	55	0.1
25	PrtCldy	45		6.77			5		0.131	80	55	0.1
26	PrtCldy	45		6.79		1.3	5	0.08	0.127	80	55	0.1
27									0.13			
28									0.137			
29									0.158			
30	Foggy	46		6.7		0.5	5	0.08	0.142	80	55	0.1
31									0.13			
AVG		43.7143	ERR	6.72571	ERR	0.88	5	0.05	0.123419	80	55	0.1
MAX		50	ERR	6.79	ERR	1.3	5	0.08	0.209	80	55	0.1
MIN		32	ERR	6.65	ERR	0.5	5	0.01	0.02	80	55	0.1

City Of Plummer Month of

June

2000

Date	Weather	Temp (F)	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	PrtCldy	40							0.219	80	55	
2	Clear	50							0.081	80	55	
3									0.078			
4									0.067			
5	Cloudy	55							0.092	80	55	
6	Cloudy	50							0.106	80	55	
7	PrtCldy	58							0.065	80	55	
8	Cloudy	52							0.099	80	55	
9	Cloudy	45							0.111	80	55	
10									0.108			

11	.							0.107				
12	Rain	48						0.077	80	55		
13	Cloudy	46						0.101	80	55		
14	Rain	55						0.17	80	55		
15	Clear	52						0.042	80	55		
16	Clear	48						0.096	80	55		
17								0.115				
18								0.107				
19	Cloudy	48						0.097	80	55		
20	Clear	47						0.047	80	55		
21	Clear	55						0.047	80	55		
22	Clear	58						0.066	80	55		
23	Cloudy	48						0.064	80	55		
24								0.082				
25								0.086				
26	Clear	58				25		0.09	80	55		
27	Clear	58				25	1.16	0.091	80	55	0.315	
28	Clear	60				25	1.35	0.108	80	55	0.315	
29	Clear	60				25	1.05	0.086	80	55	0.315	
30	PrtCldy	58						0.051	80	55	0.315	
31												
AVG	52.2273		ERR	ERR	ERR	ERR	25	1.186667	0.091867	80	55	0.315
MAX	60		ERR	ERR	ERR	ERR	25	1.35	0.219	80	55	0.315
MIN	40		ERR	ERR	ERR	ERR	25	1.05	0.042	80	55	

City Of Plummer Month of

July

2000

Date	Weather	Temp (F)	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1									0.046			
2									0.049			
3	Cloudy	48					25	1.54	0.04	80	55	0.315
4							25		0.067	80	55	
5	Foggy	48					25	0.15	0.078	80	55	0.315
6	Cloudy	56					25		0.086	80	55	
7	Cloudy	58					25	1.26	0.064	80	55	0.315
8							25		0.059			
9							25		0.051			
10	Clear	50					25	1.75	0.056	80	55	0.315
11	Clear	56					25		0.06	80	55	
12	Clear	60					25	1.7	0.056	80	55	0.315
13	Clear	60					25		0.059	80	55	
14	Clear	61					25		0.055	80	55	0.315
15							25		0.055			
16							25		0.059			
17	Clear	60					25	1.1	0.048	80	55	0.315
18	Cloudy	62					25		0.06	80	55	
19	Clear	60					25	0.78	0.06	80	55	0.315
20	Clear	58					25	0.39	0.058	80	55	
21	Clear	50					25		0.06	80	55	0.315
22									0.057			
23									0.049			
24	Clear	48					25	0.75	0.053	80	55	0.315
25	Clear	50					25		0.055	80	55	
26	Clear	55					25		0.055	80	55	0.315
27	Clear	60					25	0.81	0.062	80	55	
28	Clear	50						0.87	0.061	80	55	0.315
29									0.066			
30									0.072			
31	Clear	60						0.26	0.075	80	55	0.315
AVG	55.5		ERR	ERR	ERR	ERR	25	0.946667	0.0595	80	55	0.315
MAX	62		ERR	ERR	ERR	ERR	25	1.75	0.086	80	55	0.315
MIN	48		ERR	ERR	ERR	ERR	25	0.15	0.04	80	55	

City Of Plummer Month of

Aug

2000

Date	Weather	Temp (F)	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	Clear	65					20		0.079	80	55	

2	Clear	56					20	0.76	0.056	80	55	0.315
3	Clear	56					20		0.055	80	55	
4	Clear	55					20	0.88	0.053	80	55	0.315
5									0.055			
6									0.062			
7	Clear	58					20	0.86	0.073	80	55	0.315
8	Clear	50					20		0.053	80	55	
9	Clear	50					20	0.53	0.049	80	55	0.315
10	Clear	62					20		0.047	80	55	
11	PrtCldy	82					20	0.53	0.049	80	55	0.315
12									0.047			
13									0.049			
14	Clear	50					20	0.26	0.05	80	55	0.315
15	PrtCldy	45					20		0.057	80	55	
16	Clear	58					20	0.86	0.052	80	55	0.315
17	Clear	40					20		0.048	80	55	
18	Clear	60					20	0.71	0.046	80	55	0.315
19									0.05			
20									0.045			
21	Clear	36					20	0.39	0.048	80	55	0.315
22	Clear	34					20		0.049	80	55	
23	Clear	40					20	0.73	0.055	80	55	0.315
24	Cloudy	68					20		0.066	80	55	
25	Cloudy	55					20	0.61	0.059	80	55	0.315
26									0.07			
27									0.097			
28	Clear	32					20	0.8	0.111	80	55	0.315
29	Clear	38					20		0.069	80	55	
30	Cloudy	52					20	1.32	0.056	80	55	0.315
31	Clear	36					20		0.059	80	55	
AVG	51.2174		ERR	ERR	ERR	ERR	20	0.710769	0.058516	80	55	0.315
MAX	82		ERR	ERR	ERR	ERR	20	1.32	0.111	80	55	0.315
MIN	32		ERR	ERR	ERR	ERR	20	0.26	0.045	80	55	

City Of Plummer Month of

Sept

2000

Date	Weather	Temp (F)	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	Cloudy	48					20	0.76	0.077	80	55	0.315
2									0.054			
3									0.053			
4									0.05			
5	Cloudy	47					20		0.055	80	55	
6	Cloudy	52					20	2.2	0.051	80	55	0.315
7	Foggy	47					20		0.052	80	55	
8	Cloudy	52					20	1.1	0.055	80	55	0.315
9									0.049			
10									0.05			
11	Cloudy	52							0.075	80	55	
12	Foggy	48							0.075	80	55	
13	Foggy	50							0.058	80	55	
14	PrtCldy	52							0.05	80	55	
15	Clear	54							0.052	80	55	
16									0.048			
17									0.046			
18	Cloudy	58							0.05	80	55	
19	PrtCldy	52							0.049	80	55	
20	PrtCldy	35							0.05	80	55	
21	Rain	45							0.053	80	55	
22	Clear	30							0.048	80	55	
23									0.046			
24									0.048			
25	Clear	30							0.053	80	55	
26	Clear	30							0.056	80	55	
27	Clear	34							0.051	80	55	
28	Clear	36							0.052	80	55	
29									0.053			
30												
31												
AVG	44.8421		ERR	ERR	ERR	ERR	20	1.353333	0.053759	80	55	0.315
MAX	58		ERR	ERR	ERR	ERR	20	2.2	0.077	80	55	0.315

MIN	30	ERR	ERR	ERR	ERR	20	0.76	0.046	80	55	0.315
-----	----	-----	-----	-----	-----	----	------	-------	----	----	-------

City Of Plummer Month of Oct 2000

Date	Weather	Temp (F)	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1									0.119			
2	PrtCldy	46							0.08	80	55	
3	Foggy	35							0.058	80	55	
4	Foggy	32							0.057	80	55	
5	Foggy	32							0.048	80	55	
6	Clear	32							0.051	80	55	
7									0.049			
8									0.047			
9	Clear	35							0.053	80	55	
10	PrtCldy	40							0.052	80	55	
11	PrtCldy	43							0.052	80	55	
12	PrtCldy	45							0.05	80	55	
13	Rain	42							0.048	80	55	
14									0.057	80	55	
15									0.048	80	55	
16	PrtCldy	40							0.05	80	55	
17	PrtCldy	40					20		0.049	80	55	
18	Rain	45					20	1.26	0.044	80	55	0.15
19	Clear	40					20	1.22	0.07	80	55	0.315
20	Cloudy	42					20	1.61	0.077	80	55	0.315
21									0.134	80	55	
22									0.103	80	55	
23	Foggy	32					20	0.28	0.077	80	55	0.315
24	Foggy	32					20		0.085	80	55	
25	Foggy	35					20	0.89	0.056	80	55	0.315
26	Foggy	38					20		0.049	80	55	
27	PrtCldy	42					20		0.052	80	55	0.315
28									0.054			
29									0.134			
30	Foggy	34					20	1.22	0.109	80	55	0.315
31	Cloudy	37					20	1.24	0.066	80	55	0.315
AVG		38.1364	ERR	ERR	ERR	ERR	20	1.102857	0.067032	80	55	0.294375
MAX		46	ERR	ERR	ERR	ERR	20	1.61	0.134	80	55	0.315
MIN		32	ERR	ERR	ERR	ERR	20	0.28	0.044	80	55	

City Of Plummer Month of Nov 2000

Date	Weather	Temp (F)	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	Foggy	33							0.056	80	55	
2	Foggy	30							0.056	80	55	
3	Foggy	28							0.054	80	55	
4									0.057			
5									0.081			
6	Foggy	34							0.071	80	55	
7	Foggy	27							0.062	80	55	
8	Snow	33							0.052	80	55	
9	Snow	32							0.056	80	55	
10	Cloudy	16							0.083	80	55	
11									0.067			
12									0.073			
13	Clear	14							0.059	80	55	
14	Clear	12							0.056	80	55	
15	Cloudy	20							0.059	80	55	
16	Cloudy	28							0.054	80	55	
17	Cloudy	25							0.059	80	55	
18									0.061			
19									0.066			
20	Foggy	15							0.073	80	55	
21	Foggy	18							0.067	80	55	
22	Foggy	15							0.065	80	55	
23									0.062			
24									0.066			
25									0.066			

26									0.071		
27	Rain	35							0.095	80	55
28	Foggy	24							0.072	80	55
29	Cloudy	30							0.056	80	55
30	Snow	30							0.074	80	55
31											
AVG	24.95		ERR	ERR	ERR	ERR	ERR	ERR	0.064967	80	55
MAX	35		ERR	ERR	ERR	ERR	ERR	ERR	0.095	80	55
MIN	12		ERR	ERR	ERR	ERR	ERR	ERR	0.052	80	55

City Of Plummer Month of

Dec

2000

Date	Weather	Temp (F)	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mix Hrs Pond 1	Mix Hrs Pond 2	Flow (MGD) Effluent
1	Cloudy	32					5		0.064	80	55	0.1
2									0.06			0.1
3									0.065			0.1
4	PrtCldy	30		7.29		7	5	0.77	0.064	80	55	0.1
5	Cloudy	28					5		0.069	80	55	0.1
6	Cloudy	28		7.14		7	5	0.37	0.066	80	55	0.1
7	Snow	28					5		0.062	80	55	0.1
8	Cloudy	27		7.23		7	5	0.33	0.055	80	55	0.1
9									0.053			
10									0.066			
11	Clear	19		7.32		5	5	0.17	0.083	80	55	0.1
12	Clear	10					5		0.078	80	55	0.1
13	Cloudy	14		7.39		10	5	0.33	0.054	80	55	0.1
14	Cloudy	17					5		0.078	80	55	0.1
15	Clear	18		7.5		4	5	0.27	0.078	80	55	0.1
16									0.075			
17									0.097			
18	Foggy	18		7.48		5	5	0.15	0.056	80	55	0.1
19	Snow	28					5		0.044	80	55	0.1
20	Foggy	18		7.33		12	5	0.3	0.06	80	55	0.1
21	Cloudy	22					5		0.083	80	55	0.1
22	Cloudy	30		7.17		7	5	0.33	0.065	80	55	0.1
23									0.077	80	55	0.1
24									0.106	80	55	0.1
25									0.141	80	55	0.1
26	PrtCldy	34					5		0.107	80	55	0.1
27	PrtCldy	36		7.23		9	5	0.32	0.093	80	55	0.1
28	Foggy	28					5		0.122	80	55	0.1
29	Foggy	29		7.15		10	5	0.29	0.116	80	55	0.1
30									0.098			
31									0.089			
AVG	24.7		ERR	7.29364	ERR	7.54545	5	0.33	0.078194	80	55	0.1
MAX	36		ERR	7.5	ERR	12	5	0.77	0.141	80	55	0.1
MIN	10		ERR	7.14	ERR	4	5	0.15	0.044	80	55	0.1
AVG	23.9381	ERR	ERR	ERR	7.29797	ERR	7.65734	ERR	0.094607			
MAX	36	ERR	ERR	ERR	7.5	ERR	12	ERR	0.311			
MIN	10	ERR	ERR	ERR	7.14	ERR	4	ERR	0.03			

City Of Plummer Month of Jan 2002

Date	Weather	Temp (F)	Temperature		PH		DO		Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing		Flow (MGD) Effluent
			Pond 1	Pond 2	Pond 1	Pond 2	Pond 1	Pond 2				Pond 1	Pond 2	
1											0.23			
2	Cloudy	28		4.3		6.69		2	5	0.44	0.25	55	80	0.1
3											0.28	55	80	0.1
4	Cloudy	32		5.7		6.72		3	5	0.36	0.03	55	80	0.1
5												55	80	0.1
6												55	80	0.1
7	Rainy	40									0.132	55	80	0.1
8	cloudy	42									0.147	55	80	0.1
9	Cloudy	35		4.6		6.68		3	5	0.04	0.378	55	80	0.1
10	Overcast	30									0.203	55	80	0.1
11	Cold	28		4.9		6.74		4	5	0.32	0.125	55	80	0.1
12												55	80	0.1
13												55	80	0.1
14	Cold	24		3.6		6.77		3	5	0.08	0.077	55	80	0.1
15	Cold	20										55	80	0.1
16	Cold	19		4.8		6.92		4	5	0.48	0.153	55	80	0.1
17	Snowy	24									0.043	55	80	0.1
18	Cold	20		4.7		6.87		2	5		0.04	55	80	0.1
19												55	80	0.1
20												55	80	0.1
21		34		3.7		6.88		3	5	0.35	0.047	55	80	0.1
22											0.05	55	80	0.1
23		30		3.4		6.77		3	5	0.16	0.042	55	80	0.1
24	Rainy	34									0.043	55	80	0.1
25	Rainy	36							5		0.135	55	80	0.1
26											0.082	55	80	0.1
27											0.406	55	80	0.1
28	cold	8		4.3		7.02		0.2	5	0.18	0.229	55	80	0.1
29		20									0.142	55	80	0.1
30	Snowy	24		5.2		7.04		13	5	0.13	0.082	55	80	0.1
31	Clean	34									0.085	55	80	0.1
AVG		28.1	ERR	4.47273	ERR	6.82727	ERR	3.65455	5	0.254	0.14296	55	80	0.1
MAX		42	ERR	5.7	ERR	7.04	ERR	13	5	0.48	0.406	55	80	0.1
MIN		8	ERR	3.4	ERR	6.68	ERR	0.2	5	0.04	0.03	55	80	0.1

City Of Plummer Month of Feb.

Date	Weather	Temp (F)	Temp.		PH		DO		Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
			Pond 1	Pond 2	Pond 1	Pond 2	Pond 1	Pond 2						
1	Sunny	34		4.1		6.72			7	0.16	0.078	55	80	0.1
2									7		0.072	55	80	0.1
3									7		0.072	55	80	0.1
4	Clear	28		3.4		7.07			7	0.4	0.069	55	80	0.1
5	Clear	24		3.4		7.07			7		0.067	55	80	0.1
6	Clear	24		3.6		7.03			5	0.24	0.069	55	80	0.1
7	Clear	22		3.6		7.03			5		0.068	55	80	0.1
8	Clear	22		3.5		7.02			5	0.16	0.131	55	80	0.1
9	Clear	22		3.5		7.02			5		0.204	55	80	0.1
10	Clear	22		3.5		7.02			5		0.16	55	80	0.1
11	Clear	24		3.6		7.05			5	0.17	0.148	55	80	0.1
12	Cold	8		3.6					5		0.142	55	80	0.1
13	Cold	12		4.3					5	0.17	0.086	55	80	0.1
14	Cold	123		4.1					5		0.097	55	80	0.1
15	Cold	12		4.3		7.05			5	0.17	0.086	55	80	0.1
16	Cold	12		4.3		7.05			5		0.082	55	80	0.1
17	Cold	12		4.3		7.05			5		0.079	55	80	0.1
18									7		0.092	55	80	0.1
19	Cold	32							7		0.14	55	80	0.1
20	Cold	29		4.8					7	0.08	0.245	55	80	0.1
21	Rainy	32							7		0.397	55	80	0.1
22	Rainy	44							7		0.192	55	80	0.1
23									7		0.192	55	80	0.1
24									7		0.275	55	80	0.1
25	Cold	6		3.3					7	0.01	0.035	55	80	0.1
26	Cold	12							7		0.135	55	80	0.1
27	Cold	16		2.9					7		0.092	55	80	0.1

28 Cold	20								7	0.092	55	80	0.1
29													
30													
31													
AVG	25.73913	ERR	3.78333	ERR	7.015	ERR	ERR	6.1428571	0.173333	0.12846	55	80	0.1
MAX	123	ERR	4.8	ERR	7.07	ERR	ERR	7	0.4	0.397	55	80	0.1
MIN	6	ERR	2.9	ERR	6.72	ERR	ERR	5	0.01	0.035	55	80	0.1

City Of Plummer Month of March

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
1	Cold	22		4.5		6.9		2	7	0.19	0.081	55	80	0.1
2									7	0.069		55	80	0.1
3									7	0.058		55	80	0.1
4	Cold	24		4.7		6.85		2	7	0.36	0.057	55	80	0.1
5	Cold	34							7	0.05	0.056	55	80	0.1
6	Snowy	14		3.7		7.01		3	7	0.18	0.08	55	80	0.1
7	Snowy	14		3.7		7.01		3	7	0.18	0.08	55	80	0.1
8	Snowy	14		3.7		7.01		3	7	0.18	0.08	55	80	0.1
9									5	0.073		55	80	0.1
10									5	0.064		55	80	0.1
11		34							5	0.132		55	80	0.1
12									5	0.159		55	80	0.2
13	Snowy	32		5		6.85		3	5	0.17	0.107	55	80	0.2
14									5	0.288		55	80	0.2
15	Snowy	28		6		7.04		2	5	0.23	0.105	55	80	0.2
16									5	0.174		55	80	0.2
17									5	0.136		55	80	0.1
18	Snowy	28		6		7.04		2	5	0.23	0.105	55	80	0.1
19	Cold	30							5	0.081		55	80	0.1
20	Snowy	30		6.9		6.94		2	5	0.25	0.155	55	80	0.2
21	Cold	12							5	0.316		55	80	0.2
22	Cold	28		5.3		7.02		2	5	0.21	0.213	55	80	0.2
23									5	0.253		55	80	0.2
24									5	0.279		55	80	0.2
25	Rainy	34		6.2		6.89		2	5	0.23	0.268	55	80	0.2
26	Foggy	36							5	0.176		55	80	0.2
27	Clear	34		6		6.98		2	5	0.23	0.198	55	80	0.2
28	Cloudy	36							5	0.144		55	80	0.2
29	Cool	34		8.3		6.75		3	5	0.28	0.117	55	80	0.2
30										0.082		55	80	0.2
31										0.073		55	80	0.2
AVG		27.26316	ERR	5.38462	ERR	6.94538	ERR	2.38462	5.5517241	0.212143	0.13739	55	80	0.1548387
MAX		36	ERR	8.3	ERR	7.04	ERR	3	7	0.36	0.316	55	80	0.2
MIN		12	ERR	3.7	ERR	6.75	ERR	2	5	0.05	0.056	55	80	0.1

City Of Plummer Month of April

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
1	Cool	37		8.1		6.75		2	5	0.14	0.096	55	80	0.2
2	Cool	34							5	0.068		55	80	0.2
3	Cold	30		7.3		6.98		2	5	0.19	0.058	55	80	0.15
4									5	0.05		55	80	0.1
5	Warm	39		7.4		6.96		2	5	0.17	0.044	55	80	0.1
6									5	0.045		55	80	0.1
7									5	0.045		55	80	0.1
8	Warm	40		7.3		6.97		2	5	0.16	0.045	55	80	0.1
9									5	0.045		55	80	0.1
10	Rainy	42		7.4		6.98		2	5	0.14	0.132	55	80	0.1
11										0.146		55	80	0.1
12	Cloudy	40		7.3		6.97		2	5	0.14	0.1321	55	80	0.2
13										0.157		55	80	0.2
14										0.159		55	80	0.2
15	Cloudy	38		11.5		6.95		5	5	0.33	0.196	55	80	0.2
16		36							5	0.1102		55	80	0.2
17	cool	36		10.1		6.98		3	5	0.29	0.122	55	80	0.2

18	Sunny	40						5		0.107	55	80	0.2	
19	Sunny	40		11.2		6.98		3	5	0.17	0.084	5	80	0.15
20										0.073	55	80	0.1	
21										0.061	55	80	0.1	
22	Cool	40		13.1		6.92		5	5	0.06	0.059	55	80	0.1
23										0.054	55	80	0.1	
24		34		11.7		6.88		3	5	0.26	0.052	55	80	0.1
25										0.049	55	80	0.1	
26		36		11.8		6.98		3	5	0.16	0.047	55	80	0.1
27										0.044	55	80	0.1	
28										0.011	55	80	0.1	
29	Clear	60		15.1		6.78		3	5	0.3	0.002	55	80	0.1
30	Cloudy	40									0.003	55	80	0.1
31														
AVG		38.94118	ERR	9.94615	ERR	6.92923	ERR	2.84615	5	0.193077	0.07654	53.333	80	0.1333333
MAX		60	ERR	15.1	ERR	6.98	ERR	5	5	0.33	0.196	55	80	0.2
MIN		30	ERR	7.3	ERR	6.75	ERR	2	5	0.06	0.002	5	80	0.1

City Of Plummer Month of May

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
1	Sunny	42		12.4		6.9		3	5	0.17	0.049	55	80	0.1
2									5		0.042	55	80	0.1
3	Sunny	42		13.9		6.89		5	5	0.24	0.042	55	80	0.1
4									5			55	80	0.1
5									5		0.041	55	80	0.1
6	Cold	30		13.4		6.9		4	5	0.18	0.051	55	80	0.1
7	Cold	30						2	5		0.42	55	80	0.1
8	Sunny	36						2	5	0.18	0.044	55	80	0.1
9	Sunny	32		11.3		6.9		2	5	0.17	0.038	55	80	0.1
10	Sunny	32		11.3		6.9		2	5	0.17	0.038	55	80	0.1
11									5		0.035	55	80	0.1
12									5		0.032	55	80	0.1
13	Sunny	36		11.4		6.91		3	5	0.21	0.036	55	80	0.1
14	Cloudy	34							5		0.034	55	80	0.1
15	Sunny	36		13.4		6.9		3	5	0.23	0.033	55	80	0.1
16									5		0.03	55	80	0.1
17	Rainy	42		15.6		6.8		1	5	0.04	0.029	55	80	0.1
18									5		0.0287	55	80	0.1
19									5		0.026	55	80	0.1
20	Cloudy	40		15.7		6.88		1	5	0.03	0.022	55	80	0.1
21	Cloudy	40							5		0.024	55	80	0.1
22	Cloudy	40		13.2		6.87		1	5	0.06	0.03	55	80	0.1
23	Sunny	42							5		0.202	55	80	0.1
24	Sunny	44		14		6.3		2	5	0.04	0.079	55	80	0.1
25									5		0.039	55	80	0.1
26									5		0.031	55	80	0.1
27									5		0.028	55	80	0.1
28									5		0.029	55	80	0.1
29	Cloudy	50							5		0.078	55	80	0.1
30									5		0.027	55	80	0.1
31				18.6		6.85		2	5	0.35	0.03	55	80	0.1
AVG		38.11765	ERR	13.6833	ERR	6.83333	ERR	2.35714	5	0.159231	0.05559	55	80	0.1
MAX		50	ERR	18.6	ERR	6.91	ERR	5	5	0.35	0.42	55	80	0.1
MIN		30	ERR	11.3	ERR	6.3	ERR	1	5	0.03	0.022	55	80	0.1

City Of Plummer Month of June

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
1											0.027	55	80	0.1
2											0.025	55	80	0.1
3											0.026	55	80	0.1
4											0.023	55	80	0.1
5											0.019	55	80	0.1
6	Cool	50		15.7		6.86		3			0.021	55	80	0.1
7	Cloudy	42									0.018	55	80	0.1

8											0.029	55	80	0.1
9											0.028	55	80	0.1
10	Cloudy	46									0.03	55	80	0.1
11	Cloudy	48										55	80	0.1
12	Warm	55									0.069	55	80	0.1
13											0.082	55	80	0.1
14	Warm	70									0.086	55	80	0.1
15											0.076	55	80	0.1
16											0.067	55	80	0.1
17		42									0.072	55	80	0.1
18											0.082	55	80	0.1
19											0.122	55	80	0.1
20	Warm	70	18.1		7		4				0.091	55	80	0.1
21											0.097	55	80	0.1
22											0.082	55	80	0.1
23											0.067	55	80	0.1
24	Hot										0.066	55	80	0.1
25	Hot										0.067	55	80	0.1
26	Hot										0.064	55	80	0.1
27	Hot										0.065	55	80	0.1
28												55	80	0.1
29												55	80	0.1
30														
31														
AVG		52.875	ERR	16.9	ERR	6.93	ERR	3.5	ERR	ERR	0.05773	55	80	0.1
MAX		70	ERR	18.1	ERR	7	ERR	4	ERR	ERR	0.122	55	80	0.1
MIN		42	ERR	15.7	ERR	6.86	ERR	3	ERR	ERR	0.018	55	80	0.1

City Of Plummer Month of July

Date	Weather	Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
1	Sunny								25	0.18	0.058			
2									25	0.16	0.06			
3									25	0.06	0.065			
4									25	0.05	0.067			
5									25	0.02	0.069			
6									25	0.17	0.071			
7									25	0.08	0.062			
8									25	0.06	0.062			
9									25	0.05	0.066			
10									25	0.08	0.067			
11									25	0.08	0.067			
12									25	0.08	0.068			
13									25	0.05	0.069			
14									25	0.04	0.067			
15									25	0.04	0.069			
16									25	0.03	0.061			
17									25	0.02	0.062			
18									25	0.02	0.062			
19									25	0.03	0.064			
20									25	0.04	0.06			
21									25	0.05	0.061			
22									25	0.06	0.07			
23									25	0.02	0.068			
24									25	0.02	0.063			
25									25	0.03	0.067			
26									25	0.01	0.065			
27									25	0.03	0.056			
28									25	0.06	0.06			
29									25	0.05	0.077			
30									25	0.02	0.096			
31										0.02	0.109			
AVG		ERR	ERR	ERR	ERR	ERR	ERR	ERR	25	0.055161	0.06735	ERR	ERR	ERR
MAX		ERR	ERR	ERR	ERR	ERR	ERR	ERR	25	0.18	0.109	ERR	ERR	ERR
MIN		ERR	ERR	ERR	ERR	ERR	ERR	ERR	25	0.01	0.056	ERR	ERR	ERR

Month of Jan

Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
									0.01	80	55	0.1
28		4.1		7.76		10	0.5	0.64	0.07	80	55	0.1
25							0.5		0.01	80	55	0.1
2							0.5		0.05	80	55	0.1
40		5.1		7.31		16		0.52	0.33	80	55	0.1
									0.44			
									0.271			
20		3.1		7.3		5	0.5	0.37	0.223	80	55	0.1
30							0.5		0.094	80	55	0.1
28		4		7.31		5	0.5	0.42	0.161	80	55	0.1
28							0.5		0.125	80	55	0.1
30		4.2		7.29		3	0.5	0.55	0.169	80	55	0.1
									0.189			
									0.184			
25		3.4		7.29		3	0.5	0.68	0.188	80	55	0.1
18							0.5		0.096	80	55	0.1
18		3.2		7.3		3	0.5	0.63	0.094	80	55	0.1
20							0.5		0.051	80	55	0.1
28		3.5		7.37		5	0.5	0.8	0.067	80	55	0.1
									0.067			
									0.073			
34		3.9		7.19		7	0.5	0.54	0.11	80	55	0.1
25							0.5		0.183	80	55	0.1
24		3.6		7.26		5	0.5	0.67	0.101	80	55	0.1
28							0.5		0.054	80	55	0.1
22		3.5		7.31		10	0.5	0.47	0.057	80	55	0.1
									0.084			
		3.3							0.01			
24				7.18		8	0.5	0.35	0.09	80	55	0.1
25							0.5		0.069	80	55	0.1
28		3.2		7.3		8	0.5	0.5	0.088	80	55	0.1
25	ERR	3.7	ERR	7.3208	ERR	6.7692	0.5	0.54923	0.1266	80	55	0.1
40	ERR	5.1	ERR	7.76	ERR	16	0.5	0.8	0.44	80	55	0.1
2	ERR	3.1	ERR	7.18	ERR	3	0.5	0.35	0.01	80	55	0.1

Month of Feb.

Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
25							0.05		0.101	80	55	0.1
30		3.8		7.27		4	0.05	0.47	0.05	80	55	0.1
									0.19			
									0.201			
34		3.6		7.33		3	0.05	0.011	0.229	80	55	0.1
25							0.05		0.202	80	55	0.1
14		3.1		7.41		4	0.05	0.012	0.134	80	55	0.1
8						7	0.05		0.084	80	55	0.1
18		3.3		7.34		8	0.05	0.012	0.059	80	55	0.1
									0.031			
									0.048			
15		3.7		7.31		8	0.05	0.011	0.066	80	55	0.1
22							0.05		0.092	80	55	0.1
18		4		7.16		12	0.05	0.028	0.099	80	55	0.1
26							0.05		0.091	80	55	0.1

20	3.5	7.15	5	0.05	0.048	0.048	80	55	0.1
						0.048			
						0.045			
						0.127			
18	3.4	7.15	0.03	0.05	0.028	0.138	80	55	0.1
32				0.05		0.098	80	55	0.1
36				0.05		0.116	80	55	0.1
30	4.4	7.08	3	0.05	0.068	0.213	80	55	0.1
						0.138			
						0.157			
10	5	7.14	10	0.05	0.07	0.165	80	55	0.1
12				0.05		0.115	80	55	0.1
10	2.7	7.15	8	0.05	0.074	0.09	80	55	0.1

21.21053	ERR	3.68182	ERR	7.2264	ERR	6.0025	0.05	0.07564	0.11339	80	55	0.1
36	ERR	5	ERR	7.41	ERR	12	0.05	0.47	0.229	80	55	0.1
8	ERR	2.7	ERR	7.08	ERR	0.03	0.05	0.011	0.031	80	55	0.1

Month of March

Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
15							0.05		0.095	80	55	0.1
34	4.9			7.14		3	0.05	0.023	0.342	80	55	0.1
									0.233			
									0.261			
38	6.3			7.13		3	0.05	0.05	0.291	80	55	0.1
30							0.05		0.197	80	55	0.1
28	5.3			7.15		3	0.05	0.053	0.182	80	55	0.1
25							0.05		0.203	80	55	0.1
35	5.5			7.13		9	0.05	0.044	0.132	80	55	0.1
									0.307			
									0.267			
34	5.3			7.12		20	0.05	0.032	0.332	80	55	0.1
40							0.05		0.202	80	55	0.1
28	5.5			7.09		8	0.05	0.032	0.188	80	55	0.1
25							0.05		0.06	80	55	0.1
32	6.2			7.03		10	0.05	0.021	0.082	80	55	0.1
									0.155			
									0.194			
40	7.5			6.95		13	0.05	0.019	0.252	80	55	0.1
28							0.05		0.18	80	55	0.1
25	6.8			6.94		0.04	0.05	0.017	0.095	80	55	0.1
28							0.05		0.042	80	55	0.1
26	7.5			6.88		0.04	0.05	0.017	0.082	80	55	0.1
									0.1287			
									0.121			
40	8.6			6.85		0.08	0.05	0.09	0.175	80	55	0.1
28							0.05		0.154	80	55	0.1
36	8.4			6.9		0.05	0.05	0.03	0.154	80	55	0.1
32						0	0.05		0.301	80	55	0.1
32	8.1			6.92		0.06	0.05	0.06	0.108	80	55	0.1
									0.052	80	55	0.1
30.86364	6.6077	ERR	ERR	7.0177	ERR	4.9479	0.05	0.03754	0.1796	80	55	0.1
40	8.6	ERR	ERR	7.15	ERR	20	0.05	0.09	0.342	80	55	0.1
15	4.9	ERR	ERR	6.85	ERR	0	0.05	0.017	0.042	80	55	0.1

Month of April

Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
									0.067	80	55	0.1
32		8.6		6.91		6	0.05	0.07	0.252	80	55	0.1
30							0.05		0.147	80	55	0.1
26		7.6		6.95		6	0.05	0.11	0.207	80	55	0.1
25							0.05		0.134	80	55	0.1
36		9		6.76		6	0.05	0.09	0.096	80	55	0.1
							0.05		0.223	80	55	0.1
							0.05		0.141	80	55	0.1
35		8.2		6.82		8	0.05	0.06	0.234	80	55	0.1
32							0.05		0.123	80	55	0.1
32		7.6		6.83			0.05	0.07	0.097	80	55	0.1
25							0.05		0.138	80	55	0.1
32		8.1		6.81		14	0.05	0.16	0.176	80	55	0.1
									0.352	80	55	0.1
									0.17	80	55	0.1
28		10		6.78		6	0.05	0.03	0.137	80	55	0.1
45							0.05		0.128	80	55	0.1
42		11.4		6.79		12	0.05	0.06	0.119	80	55	0.1
40							0.05		0.134	80	55	0.1
50		9.5		6.73		13	0.05	0.02	0.172	80	55	0.1
							0.05		0.131	80	55	0.1
							0.05		0.119	80	55	0.1
40		11.1		6.5		5	0.05	0.02	0.119	80	55	0.1
40							0.05		0.119	80	55	0.1
60		15.2		6.876		8	0.05	0.04	0.112	80	55	0.1
55							0.05		0.116	80	55	0.1
70		14.3		6.65		5	0.05	0.08	0.132	80	55	0.1
							0.05		0.133	80	55	0.1
40							0.05		0.217	80	55	0.1
40		11.3		6.74		1	0.05	0.02	0.262	80	55	0.1
										80	55	0.1
38.86364	ERR	10.1462	ERR	6.7805	ERR	7.5	0.05	0.06385	0.16	80	55	0.1
70	ERR	15.2	ERR	6.95	ERR	14	0.05	0.16	0.352	80	55	0.1
25	ERR	7.6	ERR	6.5	ERR	1	0.05	0.02	0.096	80	55	0.1

Month of May

Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
32							10		0.216	55	80	0.2
32		10.1		6.86		5	10	0.04	0.154	55	80	0.2
35							10		0.054	55	80	0.2
45		11.7		6.71		1	10	0.01	0.083	55	80	0.2
							10		0.155	55	80	0.2
							10		0.155	55	80	0.2
33		11.7		6.69		2	10	0.01	0.16	55	80	0.2
40							10		0.056	55	80	0.2
40		14.5		7.08		3	10	0.01	0.067	55	80	0.2
45							10		0.102	55	80	0.2
45		13.4		6.95		2	10	0	0.104	55	80	0.2
							10		0.103	55	80	0.2
							10		0.117	55	80	0.2

45	14.7	6.8	2	10	0.04	0.12	55	80	0.2			
40				10		0.115	55	80	0.2			
38	12.8	6.9	10	10	0.02	0.188	55	80	0.2			
40				10		0.252	55	80	0.2			
36	12.8	6.97	2	10	0.45	0.179	55	80	0.2			
				10		0.145	55	80	0.2			
				10		0.135	55	80	0.2			
42	12.7	6.99	2	10	0.02	0.125	55	80	0.2			
51				10		0.118	55	80	0.2			
585	16.4	6.89	2	10	0.05	0.11	55	80	0.2			
57				10		0.108	55	80	0.2			
61	18	6.71	6	10	0.05	0.097	55	80	0.2			
				10		0.082	55	80	0.2			
				10		0.075	55	80	0.2			
				10		0.074	55	80	0.2			
40	13.9	6.89	3	10	0.01	0.086	55	80	0.2			
44	13.9	6.96	3	10	0.19	0.079	55	80	0.2			
55				10		0.082	55	80				
67.31818	ERR	13.5846	ERR	6.8769	ERR	3.3077	10	0.06923	0.11923	55	80	0.2
585	ERR	18	ERR	7.08	ERR	10	10	0.45	0.252	55	80	0.2
32	ERR	10.1	ERR	6.69	ERR	1	10	0	0.054	55	80	0.2

Month of June

Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
62							10		0.079	55	80	
									0.081	55	80	
									0.073	55	80	
38							20	0.66	0.069	55	80	0.31
41							20		0.092	55	80	
50							20	0.08	0.106	55	80	0.32
52							20		0.098	55	80	
50								0.2	0.085	55	80	0.32
							20		0.08	55	80	
							20		0.095	55	80	
46							20	0.08	0.087	55	80	0.303
38							20		0.114	55	80	
42							20	0.19	0.108	55	80	0.338
48							20		0.095	55	80	
39							20	0.2	0.092	55	80	0.291
								0.086		55	80	
									0.079	55	80	
50							20	0.07	0.09	55	80	0.29
46							20		0.089	55	80	
50							20	0.22	0.095	55	80	0.333
56									0.079	55	80	
60							20	0.19	0.08	55	80	0.325
									0.067	55	80	
									0.065	55	80	
48							20	0.06	0.072	55	80	0.356
50							20		0.08	55	80	
58							20	0.08	0.082	55	80	0.328
58							20		0.182	55	80	
50							20	0.39	0.127	55	80	0.397
									0.096	55	80	
49.14286	ERR	ERR	ERR	ERR	ERR	ERR	19.52381	0.19277	0.09093	55	80	0.3259167

62	ERR	ERR	ERR	ERR	ERR	ERR	20	0.66	0.182	55	80	0.397
38	ERR	ERR	ERR	ERR	ERR	ERR	10	0.06	0.065	55	80	0.29

Month of July

Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
----------	--------------	--------------	-----------	-----------	-----------	-----------	-------------------	---------------	----------------	--------------	--------------	---------------------

55							20	1.78	0.089	55	80	
64							20	2.2	0.09	55	80	0.381
							20		0.087	55	80	0.33
							20		0.08	55	80	
62							20		0.085	55	80	
55							20	0.12	0.075	55	80	0.373
									0.107	55	80	
									0.073	55	80	
50							20	0.12	0.08	55	80	0.521
50							20		0.085	55	80	
54							20	0.1	0.082	55	80	
55							20		0.083	55	80	
51							20	0.12	0.087	55	80	0.481
									0.092	55	80	
									0.086	55	80	
44							20	0.12	0.079	55	80	0.333
54							20		0.09	55	80	
50							20	1.55	0.078	55	80	0.34
54							20		0.076	55	80	
50							20	0.32	0.071	55	80	0.311
									0.075	55	80	
									0.074	55	80	
52							20	0.41	0.09	55	80	0.364
60							20		0.105	55	80	
55							20	1.44	0.081	55	80	0.353
48							20		0.068	55	80	
49							20	0.14	0.072	55	80	0.344
									0.051	55	80	
									0.061	55	80	
40							20	0.04	0.051	55	80	0.249
50							20		0.072	55	80	

52.47619	ERR	ERR	ERR	ERR	ERR	ERR	20	0.65077	0.07953	55	80	0.365
64	ERR	ERR	ERR	ERR	ERR	ERR	20	2.2	0.107	55	80	0.521
40	ERR	ERR	ERR	ERR	ERR	ERR	20	0.04	0.051	55	80	0.249

Month of August

Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
----------	--------------	--------------	-----------	-----------	-----------	-----------	-------------------	---------------	----------------	--------------	--------------	---------------------

48							25	1.12	0.072	55	80	0.363
55							25		0.075	55	80	
53							25		0.074	55	80	
									0.073			
									0.075			
52							25	2.2	0.076	55	80	0.357
60							25		0.071	55	80	
48							25	1.6	0.068	55	80	0.347
55							25		0.07	55	80	
50							25		0.07	55	80	

72	25	0.081	55	80	
60	25	0.068	0.067	55	80
55	25	0.067	55	80	0.327
50	25	2.2	0.072	55	80
55	25	0.074	55	80	0.344
	25	0.071	55	80	
		0.071			
38		0.073			
48	25	0.08	55	80	
54	25	0.072	55	80	
52	25	0.076	55	80	
45	25	0.083	55	80	
	25	0.071	55	80	
		0.071	55	80	
50	25	0.07	55	80	
52	25	0.068	55	80	
45	25	0.046	55	80	
48	25	0.085	55	80	
60	25	0.08	55	80	

52.3913	ERR	ERR	ERR	ERR	ERR	ERR	25	1.4376	0.07248	55	80	0.3476
72	ERR	ERR	ERR	ERR	ERR	ERR	25	2.2	0.085	55	80	0.363
38	ERR	ERR	ERR	ERR	ERR	ERR	25	0.068	0.046	55	80	0.327

Month of Sept.

Temp (F)	Temp.	Temp.	PH	PH	DO	DO	Feed Rate	Residual	Influent	Mixing	Mixing	Flow (MGD)
	Pond 1	Pond 2	Pond 1	Pond 2	Pond 1	Pond 2	Lbs/day	mg/l	(MGD)	Hours	Hours	Effluent
									0.053	80	55	
									0.024	80	55	
									0.063			
42							5		0.073	80	55	
50							5		0.07	80	55	
40							5		0.073	80	55	
38							5		0.069	80	55	
									0.065			
									0.064			
38							5		0.063	80	55	
42							5		0.072	80	55	
43							5		0.067	80	55	
45							5		0.067	80	55	
45							5		0.067	80	55	
									0.077			
									0.066			
52							5		0.075	80	55	
50							5		0.067	80	55	
45							5		0.067	80	55	
35							5		0.068	80	55	
38							5		0.064	80	55	
									0.065	80	55	
									0.065			
45							5		0.073	80	55	
48							5		0.07	80	55	
50							5		0.074	80	55	
50							5		0.072	80	55	
45							5		0.078	80	55	
									0.08			
									0.074			

44.26316	ERR	ERR	ERR	ERR	ERR	ERR	5	ERR	0.0675	80	55	ERR
52	ERR	ERR	ERR	ERR	ERR	ERR	5	ERR	0.08	80	55	ERR
35	ERR	ERR	ERR	ERR	ERR	ERR	5	ERR	0.024	80	55	ERR

Month of October

Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
38							20	0.36	0.072	80	55	0.346
38							25		0.072	80	55	
32							25	2.2	0.073	80	55	0.2609
27							25		0.072	80	55	
30							25	0.76	0.07	80	55	0.327
									0.075			
									0.077			
48							25	0.78	0.088	80	55	0.329
36							25		0.069	80	55	
30							25	1.76	0.065	80	55	0.319
							25			80	55	
30							25		0.067	80	55	0.31
36							25	0.78	0.072	80	55	
40							25		0.078	80	55	
45							25	2.2	0.075	80	55	
42							25		0.066	80	55	
44							25	2.18	0.071	80	55	0.287
									0.065			
									0.064			
46							25	1.96	0.068	80	55	0.468
							25			80	55	
30							25	2.15	0.065	80	55	0.387
46							25		0.065	80	55	
32							25	2.2	0.073	80	55	0.451
40							25	0.24	0.072	80	55	0.312
42							25	0.24	0.125	80	55	0.346
47							25	0.24	0.132	80	55	0.843

38.04762	ERR	ERR	ERR	ERR	ERR	ERR	24.78261	1.28929	0.07564	80	55	0.3835308
48	ERR	ERR	ERR	ERR	ERR	ERR	25	2.2	0.132	80	55	0.843
27	ERR	ERR	ERR	ERR	ERR	ERR	20	0.24	0.064	80	55	0.2609

Month of Nov.

Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
40									0.242	55	80	
45							0.1		0.113	55	80	
44									0.069	55	80	
30									0.015	55	80	
32									0.015	55	80	
34									0.012	55	80	
28									0.011	55	80	

34	0.09	55	80
38	0.091	55	80
44	0.054	55	80
36	0.074	55	80
44	0.037	55	80
	0.021	55	80
	0.011	55	80
36	0.083	55	80
40	0.089	55	80
40	0.113	55	80
	0.161	55	80
	0.181	55	80
	0.159	55	80
	0.03	55	80
36	0.005	55	80
32	0.058	55	80
26	0.038	55	80
36	0.027	55	80
32	0.069	55	80

36.35	ERR	ERR	ERR	ERR	ERR	ERR	0.1	ERR	0.07185	55	80	ERR
45	ERR	ERR	ERR	ERR	ERR	ERR	0.1	ERR	0.242	55	80	ERR
26	ERR	ERR	ERR	ERR	ERR	ERR	0.1	ERR	0.005	55	80	ERR

Month of Dec.

Temp (F)	Temp. Pond 1	Temp. Pond 2	PH Pond 1	PH Pond 2	DO Pond 1	DO Pond 2	Feed Rate Lbs/day	Residual mg/l	Influent (MGD)	Mixing Hours	Mixing Hours	Flow (MGD) Effluent
									0.161	55	80	0.1
									0.166	55	80	0.1
36		4					5		0.079	55	80	0.1
34						4	5	0.21	0.174	55	80	0.1
30		4.4					5		0.74	55	80	0.1
30		2.7				4	5	0.17	0.84	55	80	0.1
27						14	5	0.28	0.77	55	80	0.1
							5	0.28	0.84	55	80	0.1
		3					5		0.09	55	80	0.1
26						4	5	0.27	0.22	55	80	0.1
29		2.6					5		0.22	55	80	0.1
26						3	5	0.23	0.188	55	80	0.1
36							5		0.157	55	80	0.1
34							5		0.122	55	80	0.3
							5		0.263	55	80	0.3
							5		0.153	55	80	0.3
38		3.7				4	5	0.08	0.272	55	80	0.3
24							5		0.151	55	80	0.3
30		2.8				14	5	0.01	0.079	55	80	0.3
34							1		0.099	55	80	0.3
30		3.5				4	1	0.28	0.08	55	80	0.3
							1		0.047	55	80	0.3
							1		0.058	55	80	0.3
20		3.8				15	1	0.16	0.067	55	80	0.3
							1		0.042	55	80	0.3
10		3.4				4	1	0.39	0.032	55	80	0.3
12							1.085		0.032	55	80	0.3
26		3.5				4	7	0.51	0.032	55	80	0.3
							7		0.031	55	80	0.3

							7		0.028	55	80	0.3
30		4				3	7	0.42	0.027	55	80	0.3
28.1	ERR	3.45	ERR	ERR	ERR	6.4167	4.175345	0.25308	0.20194	55	80	0.216129
38	ERR	4.4	ERR	ERR	ERR	15	7	0.51	0.84	55	80	0.3
10	ERR	2.6	ERR	ERR	ERR	3	1	0.01	0.027	55	80	0.1

APPENDIX III

**2002 Hydrogeological Report
(Wyatt Engineering)**

Groundwater Report for the City of Plummer, Proposed Wastewater Treatment Facility, Land Application Site.

Located in Sections 5, 6, 7 & 8, T46N, R4W, Benewah County, City of Plummer, State of Idaho.

USGS Hydrologic Unit: 17010304

Introduction

This research project was completed for the City of Plummer for the site of their proposed Wastewater Treatment Facility. The total site area is approximately 340 acres located in T46N, R4W, Sections 5, 6, 7 and 8. A much smaller portion of this area is being considered for the land application site (Target Area), and this lies within the northern half of section 8.

Research conducted included a USGS (United States Geological Service), IGS (Idaho Geological Service) and IWR (Idaho Water Resources) literature search, review of well logs in the area. Interviews with Idaho Department of Environmental Quality, and University of Idaho professor Gary Stevens were conducted to reveal any unpublished aquifer information.

Site Overview

Geography

The site is located in Northern Idaho, in the St. Joe River watershed. Plummer Creek bounds the area to the south and east, and flows north easterly approximately 5 miles to Chatcolet Lake. Chatcolet Lake is the furthest southern portion of the St. Joe River drainage and is connected surficially to Lake Coeur d'Alene. The site is generally flat lying with a gentle slope to the south and east, bounded to the north and west by hilly terrain. Refer to Figure 1, Topographic Map.

The area surrounding Plummer Creek is geologically mapped as the Miocene Priest Rapids Member of the Columbia River Basalt Group, with the surrounding creek bottom land mapped as Miocene and possibly Oligocene sediments. The hills in the northern and western portions of the site are mapped as the upper member of the Wallace Formation of the Pre Cambrian Belt Supergroup. The surficial geology in the middle elevations between the hilly uplands and the creek lowlands is the Pleistocene Palouse Formation, composed of loess soils. These soils exhibit high water storage capacities and some Holocene ash layers which may increase the water retention. The Target Area lies wholly within creek bottom lands mapped Miocene, Oligocene sediments. This formation is described as deeply weathered orange to yellow silt and clay, with pebbles and sand in some areas, overlying Columbia River Basalt (within the Target Area). The typical thickness is 30'. Refer to Figure 2, Geologic Map, Showing the Target Area.

Site Well Locations and Data

map

Watershed

Geology

Well logs from wells drilled in Sections 5, 6, 7 & 8 show static water levels ranging from 10' below ground surface (bgs) to 126' bgs. There are seven wells, five in section 7 and two in section 8 that are situated within the same geologic unit as the Target Area. The well locations, the Target Area and the geologic map unit are shown on Figure 2. *Where?*


Four of the well logs in section 7 describe between 20' and 32' of surficial soils including clay layers of 3' to 18' thick. The fifth well log describes 23' of surficial soils as "dirt, sand, dirt", and does not differentiate any clay layers. Static water levels for these wells range from 15' bgs to 80' bgs. The two well logs in section 8 describe 6' and 10' of surficial soils, which are noted as clay, and the static water levels are 10' bgs and 100' bgs.

Based on the information gleaned from the well logs within the Miocene Sediment Formation, groundwater should lie between 20' and 30' below ground surface, but could lie as shallow as 10' bgs. The surficial soils exhibit high water retention capacity, high clay content and/or clay layers or lenses. The soils exhibit occasional surface ponding under high moisture conditions.

Conclusions & Recommendations

Most of the wells in the general area exhibit shallow static water levels no matter the final depth of the drilled well. The static water level in one case is at the surface (Union Pacific Railroad). This data indicates a shallow water table, with little to indicate any subsurface confining layers. Most probably, the groundwater aquifer is directly, or at best, indirectly connected to the surface waters of Lake Chatcolet and Lake Coeur d'Alene. There is the possibility that a clay or ash layer in the Target Area may seal surface areas from the underlying groundwater.

The clay content, gentle slope and ponding effect of the soils could provide adequate protection to the underlying aquifers from the effect of land application of treated wastewater. The installation and monitoring of piezometers by the City of Plummer will provide sufficient data to define groundwater levels and seasonal variations.



APPENDIX IV

Wastewater Quality Data

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

A. BOOTH
BOX B
PLUMMER, ID 83851

Tracking Number: 10993-2830/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: PLUMMER IRRIGATION FIELD
Type of Sample: Wastewater, Final
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 09/07/93 Date Received in Lab: 09/07/93
Time Collected: 08:17 Time Received in Lab:

TEST CODE		RESULTS	COMPLETED
BDEC	FECAL COLIFORM (STORET # 31616)	4 /100 ML.	09/08/93

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER ATTN: BOOTH
BOX B
PLUMMER, ID 83851

Tracking Number: 10894-0154/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: 0022781
Matrix: WATER
Sample Location: WWTP IRRIG FIELD-EFFL
Type of Sample: Wastewater, Chlorinated
Sample Taken From: Sewage Treatment Plant - P
Collected by: BOOTH
Preservation: Not Given

Date Collected: 08/02/94 Date Received in Lab: 08/02/94
Time Collected: 08:36 Time Received in Lab: 10:17

TEST CODE		RESULTS	COMPLETED
BDFC	FECAL COLIFORM (STORET # 31616)	1000 /100 ML.	08/03/94

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10895-9800/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: IRRIGATION FIELD
Type of Sample: Wastewater
Sample Taken From: Sewage Treatment Plant - P
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 08/03/95 Date Received in Lab: 08/03/95
Time Collected: 13:30 Time Received in Lab:

TEST CODE		RESULTS	COMPLETED
BDFC	FECAL COLIFORM (STORET # 31616)	84 /100 ML.	08/04/95

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10996-2188/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: IRR. FIELD WATEWATER TREATMENT
Type of Sample: Wastewater, Chlorinated
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 09/03/96 Date Received in Lab: 09/03/96
Time Collected: 09:10 Time Received in Lab: 10:37

TEST CODE		RESULTS	COMPLETED
BDMF	TOTAL COLIFORM (STORET # 31501)	9000 /100 ML.	09/04/96
BDFC	FECAL COLIFORM (STORET # 31616)	310 /100 ML.	09/04/96

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10797-8875/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: IRRIGATION WWTP
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 07/15/97 Date Received in Lab: 07/15/97
Time Collected: 09:30 Time Received in Lab: 10:49

TEST CODE		RESULTS	COMPLETED
BDMF	TOTAL COLIFORM (STORET # 31501)	4000 /100 ML.	07/16/97
BDFC	FECAL COLIFORM (STORET # 31616)	210 /100 ML.	07/16/97

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
WATER QUALITY REPORT - CHEMICAL REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor: Mike Brodwater
Inorganic Chemistry Section: Peggy Albertson *PA*

CITY OF PLUMMER
CORKY BOOTH
P.O. BOX B
PLUMMER, ID 83851

Tracking Number: 10797-1161/
(Please Refer to this Tracking Number on any communications)

Survey Name: PLUMMER
Storet:
NPDES No.: 002781
Sample Location: PLUMMER IRRIGATION FIELD WWTP
Collected by: BOOTH
Purpose: Compliance
Taken From: Lagoon - G
Type of Sample: Wastewater, Chlorinated, Grab
Composite: No
Preservation: None, H2SO4, Cooled 4° C

Date Collected: 07/15/97 Date Received in Lab: 07/15/97
Time Collected: 09:30

STORET TEST PERFORMED

RESULTS

COMPLETED ANST

00310	BOD-5	28 (mg/l)	07/22/97	KH
00335	COD	72 (mg/l)	08/01/97	BO
00300	Filterable Residue	267 (mg/l)	07/21/97	KH
00530	Non-filterable Residue (105° C)	31 (mg/l)	07/21/97	KH
00610	Total Ammonia as N	0.298 (mg/l)	07/25/97	BL
00625	Total Kjeldahl Nitrogen as N	6.22 (mg/l)	07/25/97	SR
00630	Total NO2 + NO3 as N	7.08 (mg/l)	07/15/97	SP
00665	Total Phosphorus as P (Low Conc.)	2.5 (mg/l)	07/23/97	SP

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10797-9041/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: IRRIGATION FIELD WWTP
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 07/27/97 Date Received in Lab: 07/22/97
Time Collected: 08:10 Time Received in Lab: 09:42

TEST CODE		RESULTS	COMPLETED
BDMF	TOTAL COLIFORM (STORET # 31501)	27,000 /100 ML.	07/23/97

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
A F BOOTH
BOX B
PLUMMER, ID 83851

Tracking Number: 10797-9205/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: ID-22781
Matrix: WATER
Sample Location: WASTEWATER IRRIG FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 07/29/97 Date Received in Lab: 07/29/97
Time Collected: 10:14 Time Received in Lab: 11:31

TEST CODE		RESULTS	COMPLETED
BDMF	TOTAL COLIFORM (STORET # 31501)	1600 /100 ML.	07/30/97

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10897-9375/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WWTP IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 08/05/97 Date Received in Lab: 08/05/97
Time Collected: Time Received in Lab: 10:56

TEST CODE		RESULTS	COMPLETED
BDMF	TOTAL COLIFORM (STORET # 31501)	2 /100 ML.	08/06/97

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
WATER QUALITY REPORT - CHEMICAL REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor: Mike Brodwater
Inorganic Chemistry Section: Peggy Albertson PA

CITY OF PLUMMER
CORKY BOOTH
P.O. BOX B
PLUMMER, ID 83851

Tracking Number: 10897-1436/
(Please Refer to this Tracking Number on any communications)

Survey Name:
Storet:
NPDES No.:
Sample Location: WASTEWATER IRRIGATION FIELD
Collected by: BOOTH
Purpose:
Taken From: Lagoon - G
Type of Sample: Wastewater, Chlorinated, Grab
Composite: No
Preservation: H2SO4, Cooled 4° C

Date Collected: 08/12/97 Date Received in Lab: 08/12/97
Time Collected: 09:20

STORET TEST PERFORMED

RESULTS

COMPLETED ANST

00310	BOD-5	9 (mg/l)	08/19/97	KH
00335	COD	115 (mg/l)	08/22/97	BO
70300	Filterable Residue	334 (mg/l)	08/14/97	KH
00530	Non-filterable Residue (105° C)	37 (mg/l)	08/14/97	KH
00610	Total Ammonia as N	0.391 (mg/l)	08/14/97	BL
00625	Total Kjeldahl Nitrogen as N	3.49 (mg/l)	08/18/97	BL
00630	Total NO2 + NO3 as N	3.26 (mg/l)	08/20/97	SP
00665	Total Phosphorus as P (Low Conc.)	1.3 (mg/l)	08/13/97	SP

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
A F BOOTH
BOX B
PLUMMER, ID 83851

Tracking Number: 10897-9633/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: 0022781
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 08/12/97 Date Received in Lab: 08/12/97
Time Collected: 09:20 Time Received in Lab: 10:34

TEST
CODE

RESULTS

COMPLETED

BDMPN TOTAL COLIFORM BACTERIA
BDMPE FECAL COLIFORM BACTERIA

300 /100 ML.
<2 /100 ML

08/14/97
08/14/97

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 11097-0856/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 10/02/97 Date Received in Lab: 10/02/97
Time Collected: 07:15 Time Received in Lab: 10:00

TEST CODE	RESULTS	COMPLETED
BDFC	FECAL COLIFORM (STORET # 31616)	
	<1 /100 ML.	10/03/97

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 11097-1010/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 10/08/97 Date Received in Lab: 10/08/97
Time Collected: 09:15 Time Received in Lab: 10:25

TEST
CODE

RESULTS

COMPLETED

BDFC FECAL COLIFORM (STORET # 31616)

30 /100 ML.

10/09/97

NOTES:

CHLORINATED EFFLUENT SAMPLES REQUIRE A SPECIAL MEDIA WITH A SHORT
SHELF LIFE. PLEASE CONTACT THE LAB (769-1432) A DAY OR TWO
BEFORE SUBMITTING CHLORINATED EFFLUENT SAMPLES TO GIVE US TIME TO
PREPARE THE MEDIA.

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10600-9247/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: 0022781
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 06/28/00
Time Collected: 13:10

Date Received in Lab: 06/28/00
Time Received in Lab: 14:13

TEST CODE	RESULTS	COMPLETED
EMPE FECAL COLIFORM	<2 /100 ML	07/01/00

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
WATER QUALITY REPORT - CHEMICAL REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor: Mike Brodwater
Inorganic Chemistry Section: Peggy Albertson *PA*

CITY OF PLUMMER
CORKY BOOTH
P.O. BOX B
PLUMMER, ID 83851

Tracking Number: 10600-1079/
(Please Refer to this Tracking Number on any communications)

Survey Name:
Storet:
NPDES No.: 0022781
Sample Location: WW IRRIGATION FIELD
Submitted by: BOOTH
Purpose:
Taken From: Unknown - U
Type of Sample:
Composite: No
Preservation: Cooled 4° C

Date Collected: 06/28/00 Date Received in Lab: 06/28/00
Time Collected: 13:15

STORET TEST PERFORMED	RESULTS	COMPLETED	ANST
00310 BOD-5	10 (mg/l)	07/04/00	DN
00154 Non-filterable Residue (110° C)	47 (mg/l)	07/03/00	DN

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10700-9431/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 07/07/00 Date Received in Lab: 07/07/00
Time Collected: 13:00 Time Received in Lab: 13:56

TEST CODE		RESULTS	COMPLETED
EMPN	TOTAL COLIFORM	<2 /100 ML	07/10/00

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
WATER QUALITY REPORT - CHEMICAL REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor: Mike Brodwater
Inorganic Chemistry Section: Peggy Albertson *PA*

CITY OF PLUMMER
CORKY BOOTH
P.O. BOX B
PLUMMER, ID 83851

Tracking Number: 10700-1259/
(Please Refer to this Tracking Number on any communications)

Survey Name:
Storet:
NPDES No.: 0022781
Sample Location: WW IRRIGATION FIELD
Submitted by: BOOTH
Purpose:
Taken From: Lagoon - G
Type of Sample:
Composite: No
Preservation: Cooled 4° C

Date Collected: 07/19/00 Date Received in Lab: 07/19/00
Time Collected: 09:15

TORET TEST PERFORMED		RESULTS	COMPLETED	ANST
00310	BOD-5	20 (mg/l)	07/25/00	DN
0154	Non-filterable Residue (110° C)	62 (mg/l)	07/25/00	DN

NOTES:

Please contact the laboratory prior to submitting future BOD-5s to insure that there will be sufficient supplies for your sample to be analyzed. (208)666-6718. Thank you.

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10700-9689/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: 0072781
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 07/19/00 Date Received in Lab: 07/19/00
Time Collected: 09:20 Time Received in Lab: 11:07

TEST CODE		RESULTS	COMPLETED
EMPEN	TOTAL COLIFORM	>1600 /100 ML	07/22/00
EMPE	FECAL COLIFORM	4 /100 ML	07/22/00

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10700-9831/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 07/26/00 Date Received in Lab: 07/26/00
Time Collected: 07:50 Time Received in Lab: 08:59

TEST CODE		RESULTS	COMPLETED
EMP	TOTAL COLIFORM	2 /100 ML	07/29/00

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10800-9996/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: 0022781
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 08/02/00
Time Collected: 09:00

Date Received in Lab: 08/02/00
Time Received in Lab: 10:14

TEST
CODE

RESULTS

COMPLETED

EMPEN TOTAL COLIFORM

>1,600 /100 ML

08/04/00

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10800-0178/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: 0022781
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 08/09/00 Date Received in Lab: 08/09/00
Time Collected: 08:35 Time Received in Lab: 10:46

TEST CODE		RESULTS	COMPLETED
EMPEN	TOTAL COLIFORM	>1,600 /100 ML	08/11/00
EMPE	FECAL COLIFORM	900 /100 ML	08/11/00

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10800-0344/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: 0022781
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 08/16/00 Date Received in Lab: 08/16/00
Time Collected: 09:15 Time Received in Lab: 10:16

TEST CODE	RESULTS	COMPLETED
EMPEN TOTAL COLIFORM	>1,600 /100 ML	08/18/00

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10800-0557/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: 0022781
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 08/23/00
Time Collected: 08:55

Date Received in Lab: 08/23/00
Time Received in Lab: 10:01

TEST
CODE

RESULTS

COMPLETED

EMPEN TOTAL COLIFORM

300 /100 ML

08/26/00

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10800-0701/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: 0022781
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 08/30/00
Time Collected: 08:30

Date Received in Lab: 08/30/00
Time Received in Lab: 09:33

TEST CODE	RESULTS	COMPLETED
EMPEN TOTAL COLIFORM	>1,600 /100 ML	09/01/00

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10900-0845/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: 0022781
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 09/06/00
Time Collected: 08:05

Date Received in Lab: 09/06/00
Time Received in Lab: 09:40

TEST
CODE

EMPEN TOTAL COLIFORM
EMPE FECAL COLIFORM

RESULTS

7 /100 ML
<2 /100 ML

COMPLETED

09/10/00
09/10/00

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
WATER QUALITY REPORT - CHEMICAL REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor: Mike Brodwater
Inorganic Chemistry Section: Peggy Albertson

CITY OF PLUMMER
CORKY BOOTH
P.O. BOX B
PLUMMER, ID 83851

Tracking Number: 10900-1838/
(Please Refer to this Tracking Number on any communications)

Survey Name:
Storet:
NPDES No.: 0022781
Sample Location: W/W IRRIGATION FIELD
Submitted by: BOOTH
Purpose:
Taken From: Lagoon - G
Type of Sample:
Composite: No
Preservation: Cooled 4° C

Date Collected: 09/06/00 Date Received in Lab: 09/06/00
Time Collected: 08:05

STORET TEST PERFORMED

00310 BOD-5
00154 Non-filterable Residue (110° C)

RESULTS

32 (mg/l)
86 (mg/l)

COMPLETED ANST

09/12/00 DN
09/12/00 DN

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 11000-1877/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: 0022701
Matrix: WATER
Sample Location: IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: SCHULTZ
Preservation: Sodium Thiosulfate

Date Collected: 10/19/00 Date Received in Lab: 10/19/00
Time Collected: 09:00 Time Received in Lab: 09:58

TEST
CODE

RESULTS

COMPLETED

EMPEN TOTAL COLIFORM

300 /100 ML

10/22/00

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 11000-1984/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: 0022701
Matrix: WATER
Sample Location: IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: SCHULZ
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 10/25/00 Date Received in Lab: 10/25/00
Time Collected: 09:00 Time Received in Lab: 10:09

TEST
CODE

EMPEN TOTAL COLIFORM

RESULTS

500 /100 ML

COMPLETED

10/30/00

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
WATER QUALITY REPORT - CHEMICAL REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor: Mike Brodwater
Inorganic Chemistry Section: Peggy Albertson

CITY OF PLUMMER
CORKY BOOTH
P.O. BOX B
PLUMMER, ID 83851

Tracking Number: 11000-2386/
(Please Refer to this Tracking Number on any communications)

Survey Name:
Storet:
NPDES No.:
Sample Location: WW IRRIGATION FIELD
Submitted by: SCHULZ
Purpose:
Taken From: Sewage Treatment Plant - P
Type of Sample:
Composite: No
Preservation: Cooled 4° C

Date Collected: 10/25/00
Time Collected:

Date Received in Lab: 10/25/00

STORET TEST PERFORMED

00310 BOD-5
00530 Non-filterable Residue (105° C)

RESULTS

18 (mg/l)
49 (mg/l)

COMPLETED ANST

10/31/00 DN
10/27/00 DN

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 11000-2114/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number: 0022781
Matrix: WATER
Sample Location: IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 10/31/00
Time Collected: 09:25

Date Received in Lab: 10/31/00
Time Received in Lab: 11:13

TEST
CODE

RESULTS

COMPLETED

EMPEN TOTAL COLIFORM
EMPE FECAL COLIFORM

4 /100 ML
<2 /100 ML

11/03/00
11/03/00

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10601-5671/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WWTP IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 06/06/01
Time Collected: 08:20

Date Received in Lab: 06/06/01
Time Received in Lab: 09:59

TEST
CODE

RESULTS

COMPLETED

EMPE FECAL COLIFORM

300 /100 ML

06/09/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10601-5671/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WWTP IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 06/06/01
Time Collected: 08:20

Date Received in Lab: 06/06/01
Time Received in Lab: 09:59

TEST
CODE

RESULTS

COMPLETED

EMPE FECAL COLIFORM

300 /100 ML

06/09/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10601-5785/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WASTEWATER IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: HUBER
Preservation: Sodium Thiosulfate

Date Collected: 06/13/01 Date Received in Lab: 06/13/01
Time Collected: 07:49 Time Received in Lab: 08:56

TEST CODE		RESULTS	COMPLETED
EMPE	FECAL COLIFORM	30 /100 ML	06/16/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10601-5785/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WASTEWATER IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: HUBER
Preservation: Sodium Thiosulfate

Date Collected: 06/13/01
Time Collected: 07:49
Date Received in Lab: 06/13/01
Time Received in Lab: 08:56

TEST
CODE

EMPE FECAL COLIFORM

RESULTS

30 /100 ML

COMPLETED

06/16/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10601-5941/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: PLUMMER LAGOON
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: JANSON
Preservation: Sodium Thiosulfate

Date Collected: 06/20/01 Date Received in Lab: 06/20/01
Time Collected: 07:30 Time Received in Lab: 09:44

TEST CODE	RESULTS	COMPLETED
EMPE FECAL COLIFORM	80 /100 ML	06/23/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10601-5941/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: PLUMMER LAGOON
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: JANSON
Preservation: Sodium Thiosulfate

Date Collected: 06/20/01 Date Received in Lab: 06/20/01
Time Collected: 07:30 Time Received in Lab: 09:44

TEST CODE		RESULTS	COMPLETED
EMPE	FECAL COLIFORM	80 /100 ML	06/23/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10601-6110/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Final, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 06/27/01
Time Collected: 07:30

Date Received in Lab: 06/27/01
Time Received in Lab: 10:18

TEST CODE		RESULTS	COMPLETED
EMPE	FECAL COLIFORM	900 /100 ML	06/30/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10601-6110/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Final, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 06/27/01 Date Received in Lab: 06/27/01
Time Collected: 07:30 Time Received in Lab: 10:18

TEST CODE	RESULTS	COMPLETED
EMPE FECAL COLIFORM	900 /100 ML	06/30/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
WATER QUALITY REPORT - CHEMICAL REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor: Mike Brodwater
Inorganic Chemistry Section: Peggy Albertson

CITY OF PLUMMER
CORKY BOOTH
P.O. BOX B
PLUMMER, ID 83851

Tracking Number: 10601-0777/
(Please Refer to this Tracking Number on any communications)

Survey Name:
Storet:
NPDES No.: 002278-1
Sample Location: WW IRRIGATION FIELD
Submitted by: BOOTH
Purpose:
Taken From: Sewage Treatment Plant - P
Type of Sample:
Composite: No
Preservation: Cooled 4° C

Date Collected: 06/27/01 Date Received in Lab: 06/27/01
Time Collected: 07:45

STORET TEST PERFORMED

RESULTS

COMPLETED ANST

00310	BOD-5	16 (mg/l)	07/03/01	PH
00530	Non-filterable Residue (105° C)	26 (mg/l)	07/03/01	PH

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
WATER QUALITY REPORT - CHEMICAL REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor: Mike Brodwater
Inorganic Chemistry Section: Peggy Albertson

CITY OF PLUMMER
CORKY BOOTH
P.O. BOX B
PLUMMER, ID 83851

Tracking Number: 10601-0777/
(Please Refer to this Tracking Number on any communications)

Survey Name:

Storet:

NPDES No.: 002278-1

Sample Location: WW IRRIGATION FIELD

Submitted by: BOOTH

Purpose:

Taken From: Sewage Treatment Plant - P

Type of Sample:

Composite: No

Preservation: Cooled 4° C

Date Collected: 06/27/01

Date Received in Lab: 06/27/01

Time Collected: 07:45

STORET TEST PERFORMED

RESULTS

COMPLETED ANST

00310 BOD-5

16 (mg/l)

07/03/01

PH

00530 Non-filterable Residue (105° C)

26 (mg/l)

07/03/01

PH

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10701-6242/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: HUBER
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 07/03/01 Date Received in Lab: 07/03/01
Time Collected: 08:05 Time Received in Lab: 08:53

TEST CODE		RESULTS	COMPLETED
EMP	TOTAL COLIFORM	>1,600 /100 ML	07/06/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10701-6454/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: HUBER
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 07/11/01 Date Received in Lab: 07/11/01
Time Collected: 06:42 Time Received in Lab: 09:57

TEST CODE		RESULTS	COMPLETED
EMP	TOTAL COLIFORM	>1,600 /100 ML	07/13/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10701-6660/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: JANSON
Preservation: Sodium Thiosulfate

Date Collected: 07/18/01 Date Received in Lab: 07/18/01
Time Collected: 08:35 Time Received in Lab: 10:02

TEST CODE		RESULTS	COMPLETED
EMP	TOTAL COLIFORM	220 /100 ML	07/21/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10701-6660/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: JANSON
Preservation: Sodium Thiosulfate

Date Collected: 07/18/01 Date Received in Lab: 07/18/01
Time Collected: 08:35 Time Received in Lab: 10:02

TEST CODE		RESULTS	COMPLETED
EMP	TOTAL COLIFORM	220 /100 ML	07/21/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10701-6832/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: HUBER
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 07/25/01 Date Received in Lab: 07/25/01
Time Collected: 07:54 Time Received in Lab: 09:49

TEST CODE	RESULTS	COMPLETED
EMPE FECAL COLIFORM	50 /100 ML	07/28/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
WATER QUALITY REPORT - CHEMICAL REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor: Mike Brodwater
Inorganic Chemistry Section: Peggy Albertson

CITY OF PLUMMER
CORKY BOOTH
P.O. BOX B
PLUMMER, ID 83851

Tracking Number: 10701-0890/
(Please Refer to this Tracking Number on any communications)

Survey Name:
Stoiet:
NPDES No.: 0022781
Sample Location: WW IRRIGATION FIELD
Submitted by: BOOTH
Purpose:
Taken From: Lagoon - G
Type of Sample:
Composite: No
Preservation: Cooled 4° C

Date Collected: 07/25/01 Date Received in Lab: 07/25/01
Time Collected: 07:54

STOIE	TEST PERFORMED	RESULTS	COMPLETED	ANST
00310	BOD-5	17 (mg/l)	07/31/01	PH
00530	Non-filterable Residue (105° C)	61 (mg/l)	07/31/01	PH

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10801-7016/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 08/01/01 Date Received in Lab: 08/01/01
Time Collected: 08:45 Time Received in Lab: 09:53

TEST CODE		RESULTS	COMPLETED
EMP	TOTAL COLIFORM	1,600 /100 ML	08/04/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10801-7228/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 08/08/01 Date Received in Lab: 08/08/01
Time Collected: 08:00 Time Received in Lab: 10:02

TEST CODE	RESULTS	COMPLETED
EMPE FECAL COLIFORM	4 /100 ML	08/11/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
WATER QUALITY REPORT - CHEMICAL REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor: Mike Brodwater
Inorganic Chemistry Section: Peggy Albertson PA

CITY OF PLUMMER
CORKY BOOTH
P.O. BOX B
PLUMMER, ID 83851

Tracking Number: 10801-0949/
(Please Refer to this Tracking Number on any communications)

Survey Name:
Storet:
NPDES No.: 0022781
Sample Location: IRRIGATION FIELD
Submitted by: BOOTH
Purpose:
Taken From: Lagoon - G
Type of Sample:
Composite: No
Preservation: Cooled 4° C

Date Collected: 08/08/01 Date Received in Lab: 08/08/01
Time Collected:

STORET TEST PERFORMED

RESULTS

COMPLETED ANST

00310	BOD-5	28 (mg/l)	08/14/01	PH
00530	Non-filterable Residue (105° C)	76 (mg/l)	08/14/01	PH

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10801-7429/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 08/16/01 Date Received in Lab: 08/16/01
Time Collected: 08:20 Time Received in Lab: 10:24

TEST CODE		RESULTS	COMPLETED
EMPN	TOTAL COLIFORM	80 /100 ML	08/19/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 11001-8864/
(Please Refer to this Tracking Number on any communications)

Storet:

NPDES Number:

Matrix: WATER

Sample Location: PLUMMER IRRIGATION FIELD

Type of Sample: Wastewater, Chlorinated, Grab

Sample Taken From: Lagoon - G

Collected by: JANSON

Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 10/10/01

Date Received in Lab: 10/10/01

Time Collected: 08:55

Time Received in Lab: 10:17

TEST CODE	RESULTS	COMPLETED
EMPNN TOTAL COLIFORM	>1,600 /100 ML	10/13/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 11001-9139/
(Please Refer to this Tracking Number on any communications)

Storet:

NPDES Number:

Matrix: WATER

Sample Location: LAGOON IRRIGATION FIELD

Type of Sample: Wastewater, Chlorinated, Grab

Sample Taken From: Lagoon - G

Collected by: JANSON

Preservation: Sodium Thiosulfate

Date Collected: 10/24/01

Date Received in Lab: 10/24/01

Time Collected: 09:30

Time Received in Lab: 10:38

TEST CODE		RESULTS	COMPLETED
EMP	TOTAL COLIFORM	1,600 /100 ML	10/28/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
WATER QUALITY REPORT - CHEMICAL REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor: Mike Brodwater
Inorganic Chemistry Section: Peggy Albertson

CITY OF PLUMMER
CORKY BOOTH
P.O. BOX B
PLUMMER, ID 83851

Tracking Number: 11001-1727/
(Please Refer to this Tracking Number on any communications)

Survey Name:

Storet:

NPDES No.: 0022781

Sample Location: WW EFFLUENT

Submitted by: BOOTH

Purpose:

Taken From: Lagoon - G

Type of Sample:

Composite: No

Preservation: Cooled 4° C

Date Collected: 10/31/01

Date Received in Lab: 10/31/01

Time Collected: 07:30

STORET TEST PERFORMED

RESULTS

COMPLETED ANST

00310 BOD-5

10 (mg/l)

11/06/01 PH

0530 Non-filterable Residue (105° C)

52 (mg/l)

11/05/01 PH

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
WATER QUALITY REPORT - CHEMICAL REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor: Mike Brodwater
Inorganic Chemistry Section: Peggy Albertson

CITY OF PLUMMER
CORKY BOOTH
P.O. BOX B
PLUMMER, ID 83851

Tracking Number: 11001-1727/
(Please Refer to this Tracking Number on any communications)

Survey Name:
Storet:
NPDES No.: 0022781
Sample Location: WW EFFLUENT
Submitted by: BOOTH
Purpose:
Taken From: Lagoon - G
Type of Sample:
Composite: No
Preservation: Cooled 4° C

Date Collected: 10/31/01
Time Collected: 07:30

Date Received in Lab: 10/31/01

STORET TEST PERFORMED

00310 BOD-5
0530 Non-filterable Residue (105° C)

RESULTS

10 (mg/l)
52 (mg/l)

COMPLETED ANST

11/06/01 PH
11/05/01 PH

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
WATER QUALITY REPORT - CHEMICAL REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor: Mike Brodwater
Inorganic Chemistry Section: Peggy Albertson

CITY OF PLUMMER
CORKY BOOTH
P.O. BOX B
PLUMMER, ID 83851

Tracking Number: 11001-1727/
(Please Refer to this Tracking Number on any communications)

Survey Name:

Storet:

NPDES No.: 0022781

Sample Location: WW EFFLUENT

Submitted by: BOOTH

Purpose:

Taken From: Lagoon - G

Type of Sample:

Composite: No

Preservation: Cooled 4° C

Date Collected: 10/31/01

Date Received in Lab: 10/31/01

Time Collected: 07:30

STORET TEST PERFORMED

RESULTS

COMPLETED ANST

00310 BOD-5

10 (mg/l)

11/06/01

PH

0530 Non-filterable Residue (105° C)

52 (mg/l)

11/05/01

PH

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 11001-9285/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: BOOTH
Preservation: Sodium Thiosulfate

Date Collected: 10/31/01 Date Received in Lab: 10/31/01
Time Collected: 07:30 Time Received in Lab: 09:41

TEST CODE		RESULTS	COMPLETED
EMP	TOTAL COLIFORM	>1,600 /100 ML	11/03/01

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10602-3289/
(Please Refer to this Tracking Number on any communications)

Storet:

NPDES Number:

Matrix: WATER

Sample Location: WW IRRIGATION FIELD

Type of Sample: Wastewater, Chlorinated, Grab

Sample Taken From: Sewage Treatment Plant - P

Collected by: JANSON

Preservation: Sodium Thiosulfate

Date Collected: 06/05/02

Date Received in Lab: 06/05/02

Time Collected: 09:00

Time Received in Lab: 10:43

TEST CODE		RESULTS	COMPLETED
EMP	TOTAL COLIFORM	23 /100 ML	06/10/02
PE	FECAL COLIFORM	<2 /100 ML	06/10/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10602-3692/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW TREATMENT IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Lagoon - G
Collected by: JANSON
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 06/20/02
Time Collected: 08:30

Date Received in Lab: 06/20/02
Time Received in Lab: 09:37

TEST CODE		RESULTS	COMPLETED
EMPNI	TOTAL COLIFORM	>1,600 /100 ML	06/23/02
EMPEI	FECAL COLIFORM	130 /100 ML	06/23/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10602-3726/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 06/21/02 Date Received in Lab: 06/21/02
Time Collected: 09:30 Time Received in Lab: 10:45

TEST CODE		RESULTS	COMPLETED
EMP	TOTAL COLIFORM	>1,600 /100 ML	06/25/02
PE	FECAL COLIFORM	300 /100 ML	06/25/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10602-3835/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: IRRIGATION FLD/WWTP
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 06/26/02 Date Received in Lab: 06/26/02
Time Collected: 09:00 Time Received in Lab: 10:13

TEST CODE		RESULTS	COMPLETED
EMPN	TOTAL COLIFORM	>1,600 /100 ML	06/29/02
EMPE	FECAL COLIFORM	130 /100 ML	06/29/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10602-3911/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WW TREATMENT PLANT IRRIG FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate

Date Collected: 06/28/02 Date Received in Lab: 06/28/02
Time Collected: 08:45 Time Received in Lab: 10:01

TEST CODE		RESULTS	COMPLETED
EMPN	TOTAL COLIFORM	>1,600 /100 ML	06/30/02
EMPE	FECAL COLIFORM	300 /100 ML	06/30/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10702-4039/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 07/03/02
Time Collected: 09:30

Date Received in Lab: 07/03/02
Time Received in Lab: 10:30

TEST
CODE

RESULTS

COMPLETED

EMPNI TOTAL COLIFORM
EMPE FECAL COLIFORM

300 /100 ML
30 /100 ML

07/06/02
07/06/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10702-4090/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WWTP IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 07/05/02
Time Collected: 09:45

Date Received in Lab: 07/05/02
Time Received in Lab: 10:24

TEST
CODE

RESULTS

COMPLETED

EMPEN TOTAL COLIFORM
EMPE FECAL COLIFORM

LAB ERROR /100 ML
LAB ERROR /100 ML

07/09/02
07/09/02

NOTES:

LAB ID #ID00001

LABORATORY ERROR. WE APOLOGIZE FOR ANY INCONVENIENCE THIS MAY
CAUSE YOU. PLEASE RESUBMIT ANOTHER SAMPLE AT NO ADDITIONAL
CHARGE.

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10702-4149/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 07/09/02
Time Collected: 09:45

Date Received in Lab: 07/09/02
Time Received in Lab: 10:45

TEST
CODE

RESULTS

COMPLETED

EMPE FECAL COLIFORM
EMPEN TOTAL COLIFORM

<2 /100 ML
22 /100 ML

07/13/02
07/13/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10702-4202/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: POND 2 INFLOW
Type of Sample: Wastewater
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate

Date Collected: 07/09/02 Date Received in Lab: 07/09/02
Time Collected: 12:30 Time Received in Lab: 16:00

TEST
CODE

RESULTS

COMPLETED

EMPEN TOTAL COLIFORM
EMPE FECAL COLIFORM

>1,600 /100 ML
500 /100 ML

07/13/02
07/13/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10702-4203/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: CLS POND #1
Type of Sample: Wastewater
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate

Date Collected: 07/09/02 Date Received in Lab: 07/09/02
Time Collected: 13:30 Time Received in Lab: 16:00

TEST CODE		RESULTS	COMPLETED
EMP	TOTAL COLIFORM	500 /100 ML	07/13/02
EMPE	FECAL COLIFORM	50 /100 ML	07/13/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10702-4204/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: CLS POND #2
Type of Sample: Wastewater
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate

Date Collected: 07/09/02 Date Received in Lab: 07/09/02
Time Collected: 14:50 Time Received in Lab: 16:00

TEST CODE		RESULTS	COMPLETED
EMPEN	TOTAL COLIFORM	300 /100 ML	07/13/02
EMPE	FECAL COLIFORM	30 /100 ML	07/13/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10702-4294/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WWTP IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 07/14/02 Date Received in Lab: 07/12/02
Time Collected: 08:45 Time Received in Lab: 09:54

TEST CODE		RESULTS	COMPLETED
EMP	TOTAL COLIFORM	<2 /100 ML	07/14/02
EMPE	FECAL COLIFORM	<2 /100 ML	07/14/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10702-4318/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: IRRIGATION FIELD; WWTP
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 07/15/02 Date Received in Lab: 07/15/02
Time Collected: 09:30 Time Received in Lab: 10:40

TEST CODE		RESULTS	COMPLETED
EMPN	TOTAL COLIFORM	<2 /100 ML	07/17/02
EMPE	FECAL COLIFORM	<2 /100 ML	07/17/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10702-4460/
(Please Refer to this Tracking Number on any communications)

Storet: .
NPDES Number: .
Matrix: WATER
Sample Location: IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: .
Collected by: JANSON
Preservation: Sodium Thiosulfate

Date Collected: 07/19/02
Time Collected: 08:45

Date Received in Lab: 07/19/02
Time Received in Lab: 09:52

TEST
CODE

EMPN TOTAL COLIFORM
EMPE FECAL COLIFORM

RESULTS

500 /100 ML
17 /100 ML

COMPLETED

07/22/02
07/22/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10702-4499/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: IRRIGATION FIELD WWTP
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 07/22/02 Date Received in Lab: 07/22/02
Time Collected: 10:00 Time Received in Lab: 10:59

TEST
CODE

RESULTS

COMPLETED

EMPEN TOTAL COLIFORM
EMPE FECALE COLIFORM

1,600 /100 ML
280 /100 ML

07/26/02
07/26/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10702-4646/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: PLUMMER WWTP IRRIGATION
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 07/26/02 Date Received in Lab: 07/26/02
Time Collected: 09:15 Time Received in Lab: 10:06

TEST CODE		RESULTS	COMPLETED
EMPNI	TOTAL COLIFORM	2 /100 ML	07/30/02
EMPE	FECAL COLIFORM	<2 /100 ML	07/30/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10702-4685/
(Please Refer to this Tracking Number on any communications)

Storet:
NPDES Number:
Matrix: WATER
Sample Location: WWTP IRRIGATION FIELD
Type of Sample: Wastewater, Chlorinated, Grab
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 07/29/02
Time Collected: 09:00

Date Received in Lab: 07/29/02
Time Received in Lab: 10:01

TEST
CODE

RESULTS

COMPLETED

EMPNI TOTAL COLIFORM
EMPE FECAL COLIFORM

>1,600 /100 ML
170 /100 ML

07/31/02
07/31/02

NOTES:

LAB ID #ID00001

State of Idaho, Department of Health and Welfare
Bureau of Laboratories - Coeur d'Alene Branch Lab
2195 Ironwood Court, Coeur d'Alene, Idaho 83814
NON DRINKING WATER - BACTERIAL DENSITY REPORT

LAB: COEUR D'ALENE, Phone: (208) 769-1432
Branch Laboratory Supervisor, Bacteriology: Mike Brodwater

CITY OF PLUMMER
BOX B
PLUMMER, ID 83851

Tracking Number: 10802-4846/
(Please Refer to this Tracking Number on any communications)

Storet: 811
NPDES Number: 0
Matrix: WATER
Sample Location: IRRIGATION FIELD
Type of Sample: W Wastewater, Chlorinated, Grab
Sample Taken From: Sewage Treatment Plant - P
Collected by: JANSON
Preservation: Sodium Thiosulfate AND Cooled, 4° C

Date Collected: 08/02/02
Time Collected: 09:35

Date Received in Lab: 08/02/02
Time Received in Lab: 10:41

TEST
CODE

EMPNI TOTAL COLIFORM
EMPEI FECAL COLIFORM

RESULTS

4 /100 ML
<2 /100 ML

COMPLETED

08/05/02
08/05/02

NOTES:

LAB ID #ID00001

APPENDIX V

Calculations

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

Influent Flow Calculation:

from Influent average flow data, 1999 - 2002

	January	February	March	April	May	June	July	August	September	October	November	December
1139000 gpd	1139000 gpd	294000 gpd	333000 gpd	272000 gpd	251000 gpd	253000 gpd	174000 gpd	272000 gpd	161000 gpd	175000 gpd	261000 gpd	275000 gpd
4631010 cu ft/mo	1195362 cu ft/mo	1353930 cu ft/mo	1105913 cu ft/mo	1020530 cu ft/mo	1028661 cu ft/mo	707456.9 cu ft/mo	1105913 cu ft/mo	654602.8 cu ft/mo	711524.8 cu ft/mo	1081188 cu ft/mo	1118110 cu ft/mo	1307850 cu ft/mo

Run-off volume:
Hydrologic Soil Group:
SCS CN

Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sep.	Oct.	Nov.	Dec.	total	sum
98	98	92	89	89	89	89	89	89	92	98	98	98	98
0.204082	0.204082	0.869565	1.235955	1.235955	1.235955	1.235955	1.235955	1.235955	0.869565	0.204082	0.204082	0.204082	0.204082
frozen ground	frozen ground	saturated	gravel	gravel	gravel	gravel	gravel	gravel	saturated	frozen ground	frozen ground	frozen ground	frozen ground

From Western Regional Climate Center
average Bayview

Precipitation	50-year dry	50-year wet	Davg
2.86	2.86	4.75	4.75
2.27	0.39	5.92	5.92
2.06	0.47	5.23	5.23
1.75	0.63	4.12	4.12
2.06	0.66	5.57	5.57
1.82	0.86	4.23	4.23
1.02	0.05	1.95	1.95
1.08	0	3.29	3.29
1.21	0	3.14	3.14
2.07	0.47	4.6	4.6
2.92	1.81	7.94	7.94
3.22	1.86	7.75	7.75
24.33	20	43.72	43.72
24.34	8.4	56.49	56.49

Average of Sandpoint and Moscow, from Western Region Climate Center

Average of Sandpoint and Moscow, from Western Region Climate Center			
Monthly Evaporation:	Evaporative Index Parameters	Wind	Corr Factor
Jan	0.01	23	0.3908141
Feb	0.02	25	0.40386503
Mar	1.52	28	0.427801023
Apr	1.93	34	0.46555154
May	5.41	40	0.500823369
Jun	5.91	46	0.53813325
Jul	7.97	47	0.538722433
Aug	7.47	47	0.537609877
Sep	4.82	40	0.495157233
Oct	1.52	34	0.458544822
Nov	1.43	29	0.429680585
Dec	0.03	24	0.395966369
sum	38.04		

Existing Pond Volumes
Cell 1 - Anoxic Cell 1
depth area volume length width

Regression Output:

Regression Output:

Regression Output:

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

add									36.00
	Benewah County Area, Hydrologic type C	Lacy, Stony Loam	Infiltration Rate Calculation	SCS Permeability (K) 1980	2 inches/hour peak	0.6 inches/hour min.	0.000423333 cm/sec, peak	0.000141111 cm/sec, min.	0.000001 cm/sec, peak

Plummer Waste Water Treatment

Evaporative Lagoon Spreadsheet - No Equalization Basin

27-Sep-02

Prepared by Alan E. Gay
Wyatt Engineering

Worst Case Monthly Overflow:

Average Effluent Overflow:

Area contributing runoff:

Infiltration rate:

Average operating depth after second year:

Initial Conditions:

Influent Flow:

Assume Lagoon cells 1 initially full.

Lagoon Surface Area:

Month

Month Name Year

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

length

width

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

count:

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

0

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

Influent Flow Calculation:

from Influent average flow data, 1989 - 2002

	January	February	March	April	May	June	July	August	September	October	November	December
250000 gpd	1016464 cu ft/mo	833500.4 cu ft/mo	992088.8 cu ft/mo	744051.6 cu ft/mo	658668.6 cu ft/mo	668800.3 cu ft/mo	707456.9 cu ft/mo	744051.6 cu ft/mo	654602.8 cu ft/mo	711524.8 cu ft/mo	699327.2 cu ft/mo	756249.2 cu ft/mo
205000 gpd												
244000 gpd												
183000 gpd												
162000 gpd												
164000 gpd												
174000 gpd												
183000 gpd												
161000 gpd												
175000 gpd												
172000 gpd												
186000 gpd												
188250 gpd												

	July	August	September	October	November	December	January	February	March	April	May
0.054	0.054	0.007	0.006	0.011	-0.014	-0.017	-0.005	0.071	0.053	0.036	0.043
0.061	0.061	0.06	0.065	0.04	0.057	0.037	0.049	0.071	0.107	0.097	0.062
0.065	0.065	0.06	0.065	0.04	0.057	0.037	0.049	0.071	0.107	0.097	0.062
0.066	0.066	0.06	0.065	0.04	0.057	0.037	0.049	0.071	0.107	0.097	0.062

#NAME?

Run-off volumes:

Hydrologic Soil Group:
SCS CN

(based on hydrologic soil group c)
From Western Regional Climate Center
average Bayview

	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	total	sum
98 0.204082 frozen ground														
98 0.204082 frozen ground														
92 0.869565 saturated														
89 1.235955 gravel														
89 1.235955 gravel														
89 1.235955 gravel														
89 1.235955 gravel														
89 1.235955 gravel														
89 1.235955 gravel														
89 1.235955 gravel														
92 0.869565 saturated														
98 0.204082 frozen ground														

Average of Sandpoint and Moscow, from Western Regional Climate Center

	Monthly Evaporation:	Evaporative Index Parameters	Pan Evap	AvgTemp	Pressure	Dew Pt	wind	Corr Factor	Est. evap	Q 50-yr dry	Q 50-yr we	random precip	random runoff, Q
Jan	0.01	24.3	28.1896333	29	28.1896333	23	9.3	0.39088141	0.000459874	0.985653183	4.513579	2.820097	0.480828
Feb	0.02	29	28.1896333	37.8	28.1896333	25	9.7	0.405396503	9.04681E-05	0.220381138	5.681949	3.336079	0.871629
Mar	1.52	37.8	28.1896333	46.7	28.1896333	34	10.5	0.427801023	1.023233369	0.075208958	4.314127	1.225729	0.148997
Apr	1.93	46.7	28.1896333	54.5	28.1896333	40	9.9	0.466558154	1.284470315	0.090527537	2.935867	2.196098	0.768921
May	5.41	54.5	28.1896333	59.9	28.1896333	46	9.5	0.500823369	3.722068971	0.103356973	4.319761	2.595536	0.777788
Jun	5.91	59.9	28.1896333	67.4	28.1896333	47	8.7	0.536133325	4.071708635	0.203127521	3.039564	2.415519	0.892635
Jul	7.97	67.4	28.1896333	74.7	28.1896333	47	8.7	0.538722433	5.491778132	0.037433231	0.986859	0.715586	0.265114
Aug	7.47	65.6	28.1896333	65.6	28.1896333	47	8.5	0.537809877	5.149812762	0	2.163869	0.746441	0.27861
Sept	4.82	58.8	28.1896333	48.2	28.1896333	40	8.6	0.495157233	3.299897551	0	2.02884	1.935736	0.884846
Oct	1.52	47.5	28.1896333	47.5	28.1896333	34	8.8	0.458544822	1.011588101	0.034031443	3.390185	2.549538	0.725555
Nov	1.43	34.6	28.1896333	34.6	28.1896333	29	9.4	0.458544822	1.011588101	1.068296932	6.94082	1.418573	0.003413
Dec	0.03	28.5	28.1896333	28.5	28.1896333	24	9	0.429580585	0.9776451	1.635687237	7.510365	3.791806	0.799796
	38.04							0.000201117		4.453704154	47.86885	25.72694	17.39275407

Existing Pond Volumes
Cell 1 - Anoxic Cell 1
depth area

Regression Output:

Regression Output:

Regression Output:

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

27-Sep-02

Prepared by Alan E. Gay
Wyatt Engineering

[illegible]

Cell 2 - Aeration Cell 1, Additional Cell 1

[illegible]

Cell 3 - Aeration Cell 2

depth	area	volume	length	width	Regression Output:		
0	29365	0	167.8	175	Constant	29365	0 Constant
2	33622.6	62987.6	179.8	187	Sid Err of Y Est	14.40848	0.00402 Sid Err of Y Est
6	43001.8	216238.4	203.8	211	R Squared	0.99999	0.98994 R Squared
9	50792.2	356927.2	221.8	228	No. of Observations	5	No. of Observations
10	53533	409090	227.8	235	Degrees of Freedom	3	Degrees of Freedom
12	59230.6	521853.6	239.8	247			
100:	62192.13				X Coefficient(s)	2.30337E-05	X Coefficient(s)
	1.427734948				Sid Err of Coef.	9.44024E-10	Sid Err of Coef.
	9412.734483				to obtain area from depth:		to obtain area from volume:
					enter depth, multiply by		enter vol., multiply by
					add		add
					2479.275336	2.30337E-05	0.057332841
					29365.00	0.0000	3.66713E-06
							29365.00

Cell 4 & 5 - Equalization Basin

[illegible]

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

Benewah County Area, Hydrologic type C Cold, Silt Loam Infiltration Rate Calculation SCS Permeability (K) 1980 0.6 inches/hour peak 0.2 inches/hour min. 0.000423333 cm/sec. peak 0.000141111 cm/sec. min. Check With Freeze & Cherry for this soil type: 0.00001 cm/sec. peak 0.000000001 cm/sec. min. Utilize: 0.00001 cm/sec. Assume sealing with human waste, 1 order of magnitude reduction: 0.000001 cm/sec.	add	316344.00	add	0.0000	0.054 add	316344.00
Benewah County Area, Hydrologic type C Lacy, Stony Loam Infiltration Rate Calculation SCS Permeability (K) 1980 2 inches/hour peak 0.6 inches/hour min. 0.001411111 cm/sec. peak 0.000423333 cm/sec. min. Check With Freeze & Cherry for this soil type: 0.001 cm/sec. peak 0.00000001 cm/sec. min. Utilize: 0.000917222 cm/sec. Assume sealing with human waste, 1 order of magnitude reduction: 9.17222E-05 cm/sec.	add	316344.00	add	0.0000	0.054 add	316344.00

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

Adjusted Flow for Tribal Input: 50000 gpd
from Influent average flow data, 1999 - 2002

	January	February	March	April	May	June	July	August	September	October	November	December
1016464 cu ft/mo	833500.4 cu ft/mo	992068.8 cu ft/mo	744051.6 cu ft/mo	658668.6 cu ft/mo	668600.3 cu ft/mo	707459.9 cu ft/mo	744051.6 cu ft/mo	654602.8 cu ft/mo	711524.8 cu ft/mo	698327.2 cu ft/mo	756249.2 cu ft/mo	765397.3 cu ft/mo

(based on hydrologic soil group c)

Run-off volume:
Hydrologic Soil Group:
SCS CN

Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sep.	Oct.	Nov.	Dec.	total	sum
98 0.204082 frozen ground	92 0.204082 frozen ground	92 0.869565 saturated	89 1.235955 gravel	89 1.235955 gravel	89 1.235955 gravel	89 1.235955 gravel	89 1.235955 gravel	89 1.235955 gravel	89 1.235955 gravel	92 0.869565 saturated	98 0.204082 frozen ground		

From Western Regional Climate Center
average Bayview

Precipitation	50-year dry	50-yr wet	Qavg
2.86	1.2	4.75	2.628878309 in.
2.27	0.39	5.92	2.042218675 in.
2.06	0.47	5.23	1.290919094 in.
1.75	0.63	4.12	0.824618266 in.
2.06	0.66	5.57	1.077904482 in.
1.82	0.86	4.23	0.880717666 in.
1.02	0.05	1.95	0.29731403 in.
1.08	0	3.29	0.335258539 in.
1.21	0	3.14	0.421601013 in.
2.07	0.47	4.6	1.086266401 in.
2.92	1.81	7.94	2.085652383 in.
3.22	1.86	7.75	2.86741243 in.
24.33	20	43.72	
24.34	8.4	58.49	15.95876129

Average of Sandpoint and Moscow, from Western Regional Climate Center

Average of Sandpoint and Moscow, from Western Regional Climate Center									
Evaporative Index Parameters									
Average Annual Evaporation:		Pan Evap	Avg Temp	Pressure	Dew Pt	wind	Corr Factor	Est. evap	
Monthly Evaporation:									
Jan	0.00 inches	0.01	24.3	28.1896333	23	9.3	0.39088141	0.000459874	
Feb	0.00 inches	0.02	29	28.1896333	25	9.7	0.405366503	9.04661E-05	0.3
Mar	1.02 inches	1.52	37.8	28.1896333	28	10.5	0.427801023	1.023231369	0.5
Apr	1.29 inches	1.93	46.7	28.1896333	34	10.7	0.466558154	1.294470315	1.3
May	3.72 inches	5.41	54.5	28.1896333	40	9.9	0.500823369	3.722068871	5.27
Jun	4.07 inches	5.91	59.9	28.1896333	46	9.5	0.536133325	4.071708535	7.62
Jul	5.49 inches	7.97	67.4	28.1896333	47	8.7	0.538722433	5.491778132	8.71
Aug	5.15 inches	7.47	65.6	28.1896333	47	8.5	0.537809877	5.149812762	10.42
Sep	3.30 inches	4.82	58.8	28.1896333	40	8.6	0.495157233	3.298897551	9.29
Oct	1.01 inches	1.52	47.6	28.1896333	34	8.8	0.458544822	1.011886101	5.94
Nov	0.98 inches	1.43	34.6	28.1896333	29	9.4	0.429580585	0.9776451	2.3
Dec	0.00 inches	0.03	28.5	28.1896333	24	9	0.355663369	0.000201117	0.6
	26.04	38.04							0.3
									52.54

Existing Pond Volumes
Cell 1 - Anoxic Cell 1

depth area volume length width

Regression Output:

Regression Output:

Regression Output:

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

Adjusted Flow for Tribal Input: 50000 gpd

depth	0	79998	0	402	199	Constant	79998	Constant	0.054
	2	87354	167352	414	211	Std Err of Y Est	93.92	Std Err of Y Est	0.040364
	4	94998	349704	426	223	R Squared	1.00	R Squared	0.999404
	6	102930	547632	438	235	No. of Observations	5.00	No. of Observations	5
	8	111150	761712	450	247	Degrees of Freedom	3	Degrees of Freedom	3
top		133293		471	283	X Coefficient(s)	1.04813E-05	X Coefficient(s)	0.040857299
		761930.2232				Std Err of Coef.	1.35455E-07	Std Err of Coef.	0.000396573
						to obtain area from depth:		to obtain area from volume:	
						enter depth, multiply by	3894	enter vol., multiply by	0.040857299
						add	79998.00	add	79998.00

Cell 1 & 2 - Aeration Cell 2

depth	0	29365	0	167.8	175	Constant	29365	Constant	0.034974
	2	33622.6	62987.5	179.8	187	Std Err of Y Est	94.94187	Std Err of Y Est	0.999552
	4	38168.2	134778.4	191.8	199	R Squared	0.999817	R Squared	0.999552
	6	43001.8	215948.4	203.8	211	No. of Observations	5	No. of Observations	5
	8	48123.4	307073.6	215.8	223	Degrees of Freedom	3	Degrees of Freedom	3
	10	53533	408730	227.8	235				
	12	58230.6	521493.6	239.8	247				
top		73863		261	283	X Coefficient(s)	2.28359E-05	X Coefficient(s)	0.057117026
		521320.6791				Std Err of Coef.	1.25791E-07	Std Err of Coef.	0.00020634
						to obtain area from depth:		to obtain area from volume:	
						enter depth, multiply by	2488.8	enter vol., multiply by	0.057117026
						add	29365.00	add	29365.00

Cell 3 - Sand Filter-Cell 1, Add Cell 1, Cell 2, Add Cell 2

depth	0	4984	0	178	28	Constant	4984	Constant	0.00402
	1	6256	5620	184	34	Std Err of Y Est	14.40846	Std Err of Y Est	0.00402
	2	7600	12548	190	40	R Squared	0.999999	R Squared	0.999994
	3	9016	20856	196	46	No. of Observations	5	No. of Observations	5
	4	10504	30616	202	52	Degrees of Freedom	3	Degrees of Freedom	3
	7	15400	68472	220	70				
top:		16170				X Coefficient(s)	9.73647E-05	X Coefficient(s)	0.146592572
		0.371212121				Std Err of Coef.	9.44024E-10	Std Err of Coef.	3.66713E-06
		9412.734483				to obtain area from depth:		to obtain area from volume:	
						enter depth, multiply by	9.73647E-05	enter vol., multiply by	0.146592572
						add	0.0000	add	4984.00

Cell 4 & 5 - Equalization Basin

depth	0	328329	0	573	573	Constant	328329	Constant	0.065678
	2	335241	663570	579	579	Std Err of Y Est	19.44222	Std Err of Y Est	0.065678
	4	342225	1341036	585	585	R Squared	0.999837	R Squared	0.998706
	6	349281	2032542	591	591	No. of Observations	5	No. of Observations	5
	9	360000	3096464	600	600	Degrees of Freedom	3	Degrees of Freedom	3
top:		16170				X Coefficient(s)	2.90529E-06	X Coefficient(s)	0.010226037
		0.371212121				Std Err of Coef.	1.51412E-06	Std Err of Coef.	0.000814853
		9412.734483				to obtain area from depth:		to obtain area from volume:	
						enter depth, multiply by	3519.442623	enter vol., multiply by	0.010226037

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

Adjusted Flow for Tribal Input: 50000 gpd				
add		328329.00	add	
Benewah County Area, Hydrologic type C				
Lacy, Silty Loam				
Infiltration Rate Calculation				
SCS Permeability ("K") 1980				
0.6 inches/hour peak				
0.2 inches/hour min.				
0.000423333 cm/sec, peak				
0.000141111 cm/sec, min.				
Check With Freeze & Cherry for this soil type:				
0.00001 cm/sec, peak				
0.000000001 cm/sec, min.				
Utilize:				
0.00001 cm/sec.				
Assume sealing with human waste, 1 order of magnitude reduction:				
0.000001 cm/sec.				
Benewah County Area, Hydrologic type C				
Lacy, Silty Loam				
Infiltration Rate Calculation				
SCS Permeability ("K") 1980				
2 inches/hour peak				
0.6 inches/hour min.				
0.001411111 cm/sec, peak				
0.000423333 cm/sec, min.				
Check With Freeze & Cherry for this soil type:				
0.001 cm/sec, peak				
0.0000001 cm/sec, min.				
Utilize:				
0.000517222 cm/sec.				
Assume sealing with human waste, 1 order of magnitude reduction:				
9.17222E-05 cm/sec.				
0.0000	add	328329.00	0.054	add
				328329.00

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

Plummer Lagoon Spreadsheet - Equalization Basin

Worst Case Monthly Overflow:

Average Effluent Overflow:

Area contributing runoff:

Infiltration rate:

Average operating depth after second year:

Initial Conditions:

Influent Flow:

Assume Lagoon cells 1 initially full.

Lagoon Surface Area:

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

Month

length
width
600
600
8.264463 acres

0 cfd/day

0 gallons/day

0 cfd/day

0 gpm

0 cfs

count:

Average flow balance:

198816.3 gallons/day

1.00E-10

169777.4 square feet

765397.3 cuft/mo

Assume System begins operation Jan. 1

Initial

Pond Vol.

Pond Surf.

Evap Vol.

Exfiltr. Vol.

Depth/pond4

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

length
width
600
600
8.264463 acres

0 cfd/day

0 gallons/day

0 cfd/day

0 gpm

0 cfs

count:

Average flow balance:

198816.3 gallons/day

1.00E-10

169777.4 square feet

765397.3 cuft/mo

Assume System begins operation Jan. 1

Initial

Pond Vol.

Pond Surf.

Evap Vol.

Exfiltr. Vol.

Depth/pond4

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

length
width
600
600
8.264463 acres

0 cfd/day

0 gallons/day

0 cfd/day

0 gpm

0 cfs

count:

Average flow balance:

198816.3 gallons/day

1.00E-10

169777.4 square feet

765397.3 cuft/mo

Assume System begins operation Jan. 1

Initial

Pond Vol.

Pond Surf.

Evap Vol.

Exfiltr. Vol.

Depth/pond4

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

length
width
600
600
8.264463 acres

0 cfd/day

0 gallons/day

0 cfd/day

0 gpm

0 cfs

count:

Average flow balance:

198816.3 gallons/day

1.00E-10

169777.4 square feet

765397.3 cuft/mo

Assume System begins operation Jan. 1

Initial

Pond Vol.

Pond Surf.

Evap Vol.

Exfiltr. Vol.

Depth/pond4

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

length
width
600
600
8.264463 acres

0 cfd/day

0 gallons/day

0 cfd/day

0 gpm

0 cfs

count:

Average flow balance:

198816.3 gallons/day

1.00E-10

169777.4 square feet

765397.3 cuft/mo

Assume System begins operation Jan. 1

Initial

Pond Vol.

Pond Surf.

Evap Vol.

Exfiltr. Vol.

Depth/pond4

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

length
width
600
600
8.264463 acres

0 cfd/day

0 gallons/day

0 cfd/day

0 gpm

0 cfs

count:

Average flow balance:

198816.3 gallons/day

1.00E-10

169777.4 square feet

765397.3 cuft/mo

Assume System begins operation Jan. 1

Initial

Pond Vol.

Pond Surf.

Evap Vol.

Exfiltr. Vol.

Depth/pond4

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

Max depth

length
width
600
600
8.264463 acres

0 cfd/day

0 gallons/day

0 cfd/day

0 gpm

0 cfs

count:

Average flow balance:

198816.3 gallons/day

1.00E-10

169777.4 square feet

765397.3 cuft/mo

Assume System begins operation Jan. 1

Initial

Pond Vol.

Pond Surf.

Evap Vol.

Exfiltr. Vol.

Depth/pond4

Max depth

Max depth

Max depth

Max depth

Max depth

Plummer Waste Water Treatment

Evaporative Lagoon Spreadsheet - Equalization Basin

27-Sep-02

Prepared by Alan E. Gay

Wyatt Engineering

length width 600 600

8.264463 acres

August	3	32	0	0	0	5.15	744051.60	1579952	516433.7	221628.1	44.5272	0	0.660299265	0.6602993	0
September	3	33	1.29279	58798.3	1499.25	3.30	654602.77	2102331	521775.6	143483.8	44.9877	0	2.177961243	2.1779612	0
October	3	34	2.398579	109091.5	4275.17	1.01	711524.75	2660365	527482.1	44470.52	45.4798	0	3.799208631	3.7992086	0
November	3	35	3.498863	159134.3	8246.39	0.98	699327.18	3332265	534352.9	43533.96	46.0722	0	5.751272936	5.7512729	0
December	3	36	6.650256	302465.1	20060.1	0.00	756249.16	3964958	540822.9	9.064051	46.63	0	7.589430804	7.5894308	0
January	4	37	5.559551	252857.9	16651.2	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0	0
February	4	38	0	0	0	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0	0
March	4	39	3.756416	170848.2	9019.59	1.02	992068.80	761712	111150	9477.681	9.58341	0	0	0	0
April	4	40	2.633222	119763.5	4917.91	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0	0
May	4	41	4.769885	216942.6	11113.5	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0	0
June	4	42	1.539344	70012	2066.37	4.07	668800.34	1265759	169304.7	57446.61	14.5975	0	0	0	0
July	4	43	0.746151	33936.23	448.982	5.49	707458.90	996344.9	153916.5	70439.62	13.2708	0	0	0	0
August	4	44	0	0	0	5.15	744051.60	1667736	517331.4	222013.3	44.6046	0	0.915336035	0.915336	0
September	4	45	0.391129	17789.23	46.9766	3.30	654602.77	2189730	522669.3	143729.6	45.0648	0	2.431878555	2.4318786	0
October	4	46	1.683727	76578.78	2415.97	1.01	711524.75	2705056	527939.1	44509.05	45.5192	0	3.929049198	3.9290492	0
November	4	47	4.560501	207419.4	11454.1	0.98	699327.18	3342545	534458.1	43542.53	46.0812	0	5.781141168	5.7811412	0
December	4	48	3.41003	155094	9939.48	0.00	756249.16	4026723	541454.5	9.074636	46.6845	0	7.768875638	7.7688756	0
January	5	49	2.401904	109242.7	6799.61	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0	0
February	5	50	0	0	0	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0	0
March	5	51	0.385254	17522.01	129.287	1.02	992068.80	761712	111150	9477.681	9.58341	0	0	0	0
April	5	52	0.169813	7723.402	16.1689	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0	0
May	5	53	1.865785	84859.09	2871.53	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0	0
June	5	54	3.169307	144145.5	6425.08	4.07	668800.34	1125434	161289.7	54727.06	13.9065	0	0	0	0
July	5	55	0.188579	8576.895	9.12949	5.49	707458.90	937232	150540.2	68894.44	12.9796	0	0	0	0
August	5	56	0	0	0	5.15	744051.60	1584369	516478.9	221647.5	44.5311	0	0.673131943	0.6731319	0
September	5	57	1.101973	50119.64	1093.42	3.30	654602.77	2106729	521820.6	143496.2	44.9916	0	2.190737593	2.1907376	0
October	5	58	1.591162	72368.78	2190.52	1.01	711524.75	2655665	527434	44466.47	45.4768	0	3.785555962	3.785556	0
November	5	59	2.707197	123128	5900.66	0.98	699327.18	3288762	533908.1	43497.72	46.0338	0	5.624885496	5.6248855	0
December	5	60	1.791292	81471.01	4905	0.00	756249.16	3883140	539886.2	9.050028	46.5579	0	7.351724849	7.3517248	0
January	6	61	2.157878	98144	6041.44	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0	0
February	6	62	2.969433	135054.9	8566.08	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0	0
March	6	63	1.760018	80048.65	3205.3	1.02	992068.80	761712	111150	9477.681	9.58341	0	0	0	0
April	6	64	3.000014	136445.8	5944.18	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0	0
May	6	65	4.286199	194943.7	9676.22	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0	0
June	6	66	1.023409	46546.41	936.867	4.07	668800.34	1242323	167966.1	56992.41	14.4821	0	0	0	0
July	6	67	0	0	0	5.49	707458.90	948768	151199.1	69195.98	13.0365	0	0	0	0
August	6	68	1.596091	72592.96	2202.41	5.15	744051.60	1587018	516506	221659.1	44.5334	0	0.68082629	0.6808263	0
September	6	69	0	0	0	3.30	654602.77	2184161	522612.4	143713.9	45.0599	0	2.415700362	2.4157004	0
October	6	70	0	0	0	1.01	711524.75	2681667	527699.9	44488.89	45.4985	0	3.861097186	3.8610972	0
November	6	71	3.635529	165350.1	8656.19	0.98	699327.18	3240182	533411.3	43457.24	45.991	0	5.483745202	5.4837452	0
December	6	72	4.417768	200927.7	13084.5	0.00	756249.16	3879578	539949.8	9.049418	46.5547	0	7.34137536	7.3413754	0
January	7	73	3.799162	172792.4	11153.4	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0	0
February	7	74	2.649484	120503.1	7569.76	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0	0
March	7	75	0.91809	41756.3	1073.73	1.02	992068.80	761712	111150	9477.681	9.58341	0	0	0	0

Evaporative Lagoon Spreadsheet - Equalization Basin

Prepared by Alan E. Gay

Wyatt Engineering

April	7	76	0.513875	23371.91	148.086	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0
May	7	77	2.894962	131667.8	5647.91	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0
June	7	78	3.974399	172714.1	8239.52	4.07	666800.34	1175019	164121.9	55688.04	14.1507	0	0	0
July	7	79	1.435299	65279.87	1821.98	5.49	707458.90	1016239	155028.8	70959.64	13.3687	0	0	0
August	7	80	0.552743	25139.7	189.496	5.15	744051.60	1719827	517894.1	222421.9	44.6505	0	1.066673935	1.0666739
September	7	81	0.488151	22201.95	123.001	3.30	654602.77	2266921	523458.7	143946.7	45.1329	0	2.856140824	2.8561408
October	7	82	4.013714	192550.6	8873.02	1.01	711524.75	2786518	528772.1	44579.28	45.591	0	4.165721727	4.1657217
November	7	83	1.633721	74304.43	2862.38	0.98	699327.18	3536367	536440.1	43704	46.2521	0	6.344247799	6.3442478
December	7	84	4.442982	202074.5	13163.2	0.00	756249.16	4078876	541985.8	9.06354	46.7303	0	7.919813696	7.9198137
January	8	85	3.270538	148749.7	9504.52	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0
February	8	86	4.632188	210679.9	13754.1	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0
March	8	87	0.759869	34560.14	738.052	1.02	992068.80	761712	111150	9477.681	9.58341	0	0	0
April	8	88	2.978638	135473.6	5893.76	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0
May	8	89	1.711595	77846.29	2484.71	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0
June	8	90	2.173172	98839.58	3670.51	4.07	666800.34	1118034	160867.1	54583.65	13.87	0	0	0
July	8	91	0.317948	14460.84	11.9878	5.49	707458.90	881915.3	147380.7	67448.49	12.7072	0	0	0
August	8	92	0.401913	18279.69	53.8584	5.15	744051.60	1536306	515988.2	221436.9	44.4887	0	0.533725478	0.5337255
September	8	93	0.396625	18175.63	52.3634	3.30	654602.77	2077290	521519.5	143413.4	44.9657	0	2.10520731	2.1052073
October	8	94	3.74848	62530.44	1693.27	1.01	711524.75	2593324	526796.5	44412.72	45.4206	0	3.604435126	3.6044351
November	8	95	2.984604	135744.9	6716.2	0.98	699327.18	3216129	533165.3	43437.21	45.9698	0	5.413864014	5.413864
December	8	96	3.633163	185242.5	10635.5	0.00	756249.16	3824000	539381.4	9.039893	46.5057	0	7.179904685	7.1799047
January	9	97	5.317144	241832.8	15893.7	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0
February	9	98	2.475195	112576.1	7027.5	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0
March	9	99	2.073131	94289.54	4076.02	1.02	992068.80	761712	111150	9477.681	9.58341	0	0	0
April	9	100	0.077719	3534.777	84.2596	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0
May	9	101	0.53859	24496.02	173.945	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0
June	9	102	1.031317	48906.09	952.311	4.07	666800.34	1062373	157687.9	53504.92	13.5959	0	0	0
July	9	103	0	0	0	5.49	707458.90	772681.6	141141.5	64593.17	12.1693	0	0	0
August	9	104	1.17604	53488.31	1246.94	5.15	744051.60	1415535	514752.4	220906.5	44.3822	0	0.182619255	0.1826193
September	9	105	1.734135	78871.45	2540.58	3.30	654602.77	1993371	520661.4	143177.4	44.8917	0	1.861399708	1.8613997
October	9	106	1.051344	47816.93	991.744	1.01	711524.75	2572825	526586.9	44395.05	45.4026	0	3.544881232	3.5448812
November	9	107	0.506788	23049.57	288.319	0.98	699327.18	3180243	532798.4	43407.31	45.9381	0	5.309605469	5.3096055
December	9	108	1.032742	46970.9	2573.95	0.00	756249.16	3669020	537796.6	9.013331	46.3691	0	6.729645659	6.7296457
January	10	109	2.603661	118419	7427.16	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0
February	10	110	0	0	0	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0
March	10	111	3.882819	176597.3	9400.41	1.02	992068.80	761712	111150	9477.681	9.58341	0	0	0
April	10	112	2.146669	97634.18	3600.36	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0
May	10	113	3.689394	168690.3	7886.34	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0
June	10	114	0	0	0	4.07	666800.34	1212460	166260.4	55413.65	14.335	0	0	0
July	10	115	1.070795	48701.61	1030.48	5.49	707458.90	872000.4	146814.3	67189.32	12.6584	0	0	0
August	10	116	1.958585	89079.79	3109.17	5.15	744051.60	1561989	516250	221549.2	44.5113	0	0.608111361	0.6081114
September	10	117	2.209015	100469.8	3765.71	3.30	654602.77	2176636	522535.4	143669.2	45.0533	0	2.393637991	2.393638
October	10	118	3.164728	143937.3	6412.02	1.01	711524.75	2778398	528689.1	44572.28	45.5838	0	4.142130633	4.1421306
November	10	119	1.914847	87090.54	3632.59	0.98	699327.18	3487179	535937.1	43663.02	46.2087	0	6.201344222	6.2013442

Plummer Waste Water Treatment

Evaporative Lagoon Spreadsheet - Equalization Basin

27-Sep-02

Prepared by Alan E. Gay

Wyatt Engineering

length width 600 600
8.264463 acres

December	10	120	2.924055	132991	8424.71	0.00	756249.16	4043086	541621.8	9.077441	46.6989	0	7.816414323	7.8164143	0
January	11	121	4.30055	195596.4	12718.4	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0	0
February	11	122	0.66104	30065.22	1460.1	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0	0
March	11	123	2.382355	108353.6	4957.67	1.02	992068.80	761712	111150	9.477.681	9.58341	0	0	0	0
April	11	124	2.143333	97482.46	3591.55	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0	0
May	11	125	3.942856	179327.9	8665.05	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0	0
June	11	126	3.084692	140297.1	6184.21	4.07	666800.34	1225696	167016.4	56670.18	14.4002	0	0	0	0
July	11	127	0.936596	42597.99	772.347	5.49	707458.90	1031461	155922.3	71357.55	13.4437	0	0	0	0
August	11	128	0.311548	14189.63	9.96525	5.15	744051.60	1710920	517773	222202.8	44.6426	0	1.040796499	1.0407965	0
September	11	129	0.619946	28196.19	270.236	3.30	654602.77	2246903	523254	143890.4	45.1152	0	2.597984148	2.5979841	0
October	11	130	0.704961	32062.85	387.104	1.01	711524.75	2772699	528630.8	44567.37	45.5788	0	4.125571405	4.1255714	0
November	11	131	4.165918	189473.1	10256.1	0.98	699327.18	3363585	534673.2	43560.05	46.0998	0	5.842267666	5.8422677	0
December	11	132	2.387994	108610.1	6756.36	0.00	756249.16	4028601	541473.7	9.074958	46.6861	0	7.774331244	7.7743312	0
January	12	133	1.840432	83706	5057.12	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0	0
February	12	134	1.733004	78820.02	4724.68	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0	0
March	12	135	2.544027	115706.7	5425.15	1.02	992068.80	761712	111150	9.477.681	9.58341	0	0	0	0
April	12	136	1.040366	47317.63	970.071	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0	0
May	12	137	3.283765	149351.3	8752.4	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0	0
June	12	138	0.769416	34994.35	485.319	4.07	666800.34	1193807	165195	56052.15	14.2432	0	0	0	0
July	12	139	1.510978	68721.89	1999.07	5.49	707458.90	889188.6	147796.1	67638.61	12.743	0	0.717721321	0.7177213	0
August	12	140	0.833432	28809.56	287.732	5.15	744051.60	1599717	516635.8	221714.8	44.5446	0	2.319667285	2.3196673	0
September	12	141	1.708895	77723.5	2478.04	3.30	654602.77	2151107	522274.4	143621	45.0307	0	3.998342894	3.9983429	0
October	12	142	2.143283	97480.21	3591.42	1.01	711524.75	2728907	528183	44529.61	45.5402	0	5.91451477	5.9145148	0
November	12	143	1.49811	68136.6	2500.87	0.98	699327.18	3388453	534927.5	43580.77	46.1217	0	7.471469406	7.4714694	0
December	12	144	2.489281	113216.8	7071.32	0.00	756249.16	3924356	540407.7	9.057092	46.5942	0	0	0	0
January	13	145	3.434647	156213.7	10016.3	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0	0
February	13	146	1.855327	84383.46	5103.24	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0	0
March	13	147	1.946055	88509.91	3719.53	1.02	992068.80	761712	111150	9.477.681	9.58341	0	0	0	0
April	13	148	0.891023	31428.91	386.909	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0	0
May	13	149	1.595304	72557.16	2200.51	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0	0
June	13	150	2.362424	107447.1	4177.27	4.07	666800.34	1112461	160548.7	54475.64	13.8426	0	0	0	0
July	13	151	0	0	0	5.49	707458.90	885564.3	147589.1	67543.87	12.7252	0	0.502001913	0.5020019	0
August	13	152	0.995829	45292.03	883.585	5.15	744051.60	1525467	515876.5	221389	44.4791	0	2.154512232	2.1545122	0
September	13	153	1.734303	78879.08	2541	3.30	654602.77	2094260	521693.1	143461.1	44.9806	0	3.83719263	3.8371926	0
October	13	154	3.174811	144395.8	6440.78	1.01	711524.75	2673439	527615.8	44481.79	45.4913	0	5.898085237	5.8980852	0
November	13	155	3.437424	156340	8062.55	0.98	699327.18	3382798	534869.7	43576.06	46.1167	0	7.727468102	7.7274681	0
December	13	156	0.905093	41165.18	2187.58	0.00	756249.16	4012471	541308.7	9.072194	46.6719	0	0	0	0
January	14	157	5.16975	235129.1	15433.2	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0	0
February	14	158	1.796615	81713.14	4921.48	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0	0
March	14	159	1.967583	90398.69	3835.6	1.02	992068.80	761712	111150	9.477.681	9.58341	0	0	0	0
April	14	160	1.242896	56529.04	1389.98	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0	0
May	14	161	2.188902	99555.01	3712.24	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0	0
June	14	162	3.328887	151403.5	6881.89	4.07	666800.34	1140971	162177.1	55028.17	13.983	0	0	0	0
July	14	163	1.161272	52816.62	1215.9	5.49	707458.90	980182.2	151851	69494.35	13.0927	0	0	0	0

Plummer Waste Water Treatment

Evaporative Lagoon Spreadsheet - Equalization Basin

27-Sep-02

Prepared by Alan E. Gay
Wyatt Engineering

length width 600 600
8.264463 acres

August	14	164	0.58521	26616.37	227.123	5.15	744051.60	1652166	517172.2	221945	44.5908	0	0.870100881	0.8701009	0
September	14	165	1.462536	66518.65	1885.29	3.30	654602.77	2201072	522785.3	143761.5	45.0748	0	2.464830057	2.4648301	0
October	14	166	2.192727	99729	3722.4	1.01	711524.75	2766933	528571.8	44562.4	45.5737	0	4.108821896	4.1088219	0
November	14	167	4.696284	213595.1	11867.6	0.98	699327.18	3428826	53540.4	43614.41	46.1573	0	6.03181235	6.0318123	0
December	14	168	2.520396	114631.9	7168.1	0.00	756249.16	4119521	542403.4	9.090541	46.7663	0	8.038481133	8.0384811	0
January	15	169	3.731997	169737.6	10943.8	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0	0
February	15	170	6.128482	278733.9	18429.2	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0	0
March	15	171	0.356708	16223.69	99.3434	1.02	992068.80	761712	111150	9477.681	9.58341	0	0	0	0
April	15	172	0.080138	3644.809	81.6858	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0	0
May	15	173	4.02273	182960.6	8899.51	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0	0
June	15	174	3.545694	161264.3	7507.3	4.07	666800.34	1229564	167237.3	56745.12	14.4193	0	0	0	0
July	15	175	0.953243	43355.14	803.153	5.49	707458.90	1057544	157412	72039.33	13.5721	0	0	0	0
August	15	176	0.458007	20830.95	96.1132	5.15	744051.60	1737108	518040.8	222317.8	44.6657	0	1.116881947	1.1168819	0
September	15	177	0	0	0	3.30	654602.77	2279724	523589.6	143982.7	45.1441	0	2.693338971	2.6933339	0
October	15	178	0.921354	41904.75	744.466	1.01	711524.75	2776961	526674.4	44571.04	45.5826	0	4.137954811	4.1379548	0
November	15	179	5.118393	232793.3	13156.4	0.98	699327.18	3378043	534821.1	43572.1	46.1125	0	5.864272187	5.8642722	0
December	15	180	2.338828	106373.9	6603.53	0.00	756249.16	4089268	542094.1	9.085356	46.7396	0	7.950584822	7.9505848	0
January	16	181	0.868758	40422.22	2138.37	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0	0
February	16	182	1.483892	67489.96	3955.66	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0	0
March	16	183	4.501213	204722.9	11273.7	1.02	992068.80	761712	111150	9477.681	9.58341	0	0	0	0
April	16	184	3.120868	141942.4	6287.07	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0	0
May	16	185	0.913203	41534.03	729.686	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0	0
June	16	186	2.849882	120521.2	4964	4.07	666800.34	1079967	158692.8	53845.9	13.6826	0	0	0	0
July	16	187	0.210522	9574.889	3.50798	5.49	707458.90	867561	146560.8	67073.27	12.6365	0	0	0	0
August	16	188	0	0	0	5.15	744051.60	1517512	515795.2	221354.1	44.4721	0	0.478892717	0.4788927	0
September	16	189	1.038248	47221.31	965.906	3.30	654602.77	2040185	521139.9	143309	44.9329	0	1.99735096	1.997351	0
October	16	190	1.809575	82302.59	2729.3	1.01	711524.75	2586263	526724.3	44406.64	45.4144	0	3.583922365	3.5839224	0
November	16	191	3.848233	175024.3	9296.13	0.98	699327.18	3229892	533306.1	43448.67	45.9819	0	5.453851802	5.4538518	0
December	16	192	2.071174	94200.55	5772.34	0.00	756249.16	3879611	539950.1	9.049424	46.5548	0	7.341472389	7.3414724	0
January	17	193	4.886771	222258.8	14549.2	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0	0
February	17	194	2.538346	115448.3	7223.94	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0	0
March	17	195	0	0	0	1.02	992068.80	761712	111150	9477.681	9.58341	0	0	0	0
April	17	196	0.708416	32219.98	392.169	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0	0
May	17	197	2.29639	104443.8	3999.34	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0	0
June	17	198	0.77303	35158.75	491.051	4.07	666800.34	1146146	162472.8	55128.47	14.0085	0	0	0	0
July	17	199	1.908277	86791.73	2979.92	5.49	707458.90	842622.1	145136.3	86421.38	12.5137	0	0	0	0
August	17	200	0.874151	39757.91	660.18	5.15	744051.60	1573419	516366.9	221599.4	44.5214	0	0.641316939	0.6413169	0
September	17	201	1.01149	46004.29	913.727	3.30	654602.77	2136245	522122.4	143579.2	45.0176	0	2.276488467	2.2764885	0
October	17	202	3.42009	155551.6	7144.34	1.01	711524.75	2680803	527691.1	44488.14	45.4978	0	3.858567291	3.8585673	0
November	17	203	0.490221	22296.1	263.972	0.98	699327.18	3402015	535086.2	43592.07	46.1337	0	5.953916161	5.9539162	0
December	17	204	3.713272	168886	10885.4	0.00	756249.16	3898929	540054.6	9.051175	46.5638	0	7.371159198	7.3711592	0
January	18	205	1.598213	72689.48	4308.21	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0	0
February	18	206	0.088928	4044.603	28.7174	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0	0
March	18	207	0.383497	17442.1	127.353	1.02	992068.80	761712	111150	9477.681	9.58341	0	0	0	0

Plummer Waste Water Treatment

Evaporative Lagoon Spreadsheet - Equalization Basin

27-Sep-02

Prepared by Alan E. Gay

Wyatt Engineering

length width 600 600

8.264463 acres

April	18	208	2.021554	91943.74	3272.26	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0
May	18	209	1.849714	84128.17	2830.73	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0
June	18	210	1.611137	73277.26	2238.79	4.07	668800.34	1124662	161245.6	54712.1	13.9027	0	0	0
July	18	211	2.757742	125426.8	5283.65	5.49	707458.90	861420.7	146210.1	66912.77	12.6063	0	0	0
August	18	212	1.608259	73146.37	2231.82	5.15	744051.60	1632645	516972.6	221859.3	44.5736	0	0.813385262	0.8133853
September	18	213	0.81006	36842.94	551.064	3.30	654602.77	2230171	523082.9	143843.3	45.1005	0	2.549370722	2.5493707
October	18	214	4.059469	184631.6	9007.52	1.01	711524.75	2784940	528551.5	44560.68	45.572	0	4.103031927	4.1030319
November	18	215	3.734537	169853.1	8953.76	0.98	699327.18	3517023	536242.3	43687.89	46.2351	0	6.28804879	6.2880488
December	18	216	2.703612	122964.9	7738.24	0.00	756249.16	4160989	542827.5	9.097648	46.8028	0	8.158955353	8.1589554
January	19	217	0	0	0	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0
February	19	218	4.7922	217957.5	14253.8	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0
March	19	219	2.720985	123755.1	5940.99	1.02	992068.80	761712	111150	9477.681	9.58341	0	0	0
April	19	220	2.55205	116071.6	4694.19	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0
May	19	221	0	0	0	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0
June	19	222	0.468654	21315.18	105.291	4.07	668800.34	1037703	156278.8	53026.81	13.4744	0	0	0
July	19	223	0	0	0	5.49	707458.90	761712	111150	50867.59	9.58341	0	0.19063379	0.1906338
August	19	224	3.313862	150720.1	6838.74	5.15	744051.60	1418294	514780.6	220918.6	44.3846	0	2.168111442	2.1681114
September	19	225	1.675064	76184.77	2394.68	3.30	654602.77	2098941	521740.9	143474.3	44.9847	0	3.842500765	3.8425008
October	19	226	1.38164	62839.35	1698.72	1.01	711524.75	2675266	527634.4	44483.37	45.4929	0	5.6526666	5.6526666
November	19	227	3.41148	155160	7984.99	0.98	699327.18	3298324	534005.9	43505.68	46.0422	0	7.478600656	7.4786007
December	19	228	3.060469	139195.4	8849.73	0.00	756249.16	3926811	540432.8	9.057513	46.5964	0	0	0
January	20	229	1.270135	57767.9	3298.65	0.00	1016463.93	761712	111150	4.259586	9.58341	0	0	0
February	20	230	4.547418	206824.4	13489.3	0.00	833500.42	761712	111150	0.837942	9.58341	0	0	0
March	20	231	2.838643	129106.4	6286.07	1.02	992068.80	761712	111150	9477.681	9.58341	0	0	0
April	20	232	1.489767	68847.54	1902.18	1.29	744051.60	761712	111150	11990.03	9.58341	0	0	0
May	20	233	2.160526	98264.45	3637.01	3.72	658668.63	761712	111150	34475.66	9.58341	0	0	0
June	20	234	2.632475	119729.5	4915.85	4.07	668800.34	1139605	162099.1	55001.7	13.9763	0	0	0
July	20	235	2.420274	110078.2	4334.07	5.49	707458.90	925202.8	149853.1	68580	12.9204	0	0.946553405	0.9465534
August	20	236	0.351408	15982.64	25.3566	5.15	744051.60	1678481	517441.3	222060.5	44.614	0	2.509466752	2.5094668
September	20	237	0	0	0	3.30	654602.77	2216436	522942.4	143804.7	45.0893	0	3.954599816	3.9545998
October	20	238	0.124249	5651.052	42.489	1.01	711524.75	2713850	528029	44516.63	45.5289	0	5.59370852	5.5937085
November	20	239	4.423592	201192.6	11037.8	0.98	699327.18	3278031	533798.3	43488.78	46.0243	0	7.56229901	7.562299
December	20	240	1.981308	89203.67	5431.61	0.00	756249.16	3955620	540727.4	12622050	6044.29	0	0	0
totals:			481.2063	2186087	1059724	520.861	183695361.6			631102.5	302.215	0	0	0
average annual totals:			24.06031	1094304	52866.2	26.04305	9184768.079 (in.)			average: peak:	average: peak:	average: peak:	average: peak:	count:

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

Influent Flow Calculation:

from Influent average flow data, 1999 - 2002

	January	February	March	April	May	June	July	August	September	October	November	December
250000 gpd	250000 gpd	205000 gpd	244000 gpd	163000 gpd	162000 gpd	164000 gpd	174000 gpd	183000 gpd	161000 gpd	175000 gpd	172000 gpd	186000 gpd
1016484 cu ft/mo	833500.4 cu ft/mo	992088.8 cu ft/mo	744051.6 cu ft/mo	658688.6 cu ft/mo	668003.3 cu ft/mo	707458.9 cu ft/mo	744051.6 cu ft/mo	654602.8 cu ft/mo	711524.8 cu ft/mo	699327.2 cu ft/mo	756249.2 cu ft/mo	765397.3 cu ft/mo

(based on hydrologic soil group c)

Run-off volume:
Hydrologic Soil Group:
SCS CN

	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sep.	Oct.	Nov.	Dec.	total	sum
98 0.204082 frozen ground	98 0.204082 frozen ground	92 0.869565 saturated	89 1.235955 gravel	89 1.235955 gravel	89 1.235955 gravel	89 1.235955 gravel	89 1.235955 gravel	89 1.235955 gravel	89 1.235955 gravel	92 0.869565 saturated	98 0.204082 frozen ground			

From Western Regional Climate Center
average Bayview

Precipitation	50-year dry	50-year wet	Qavg
2.86	1.2	4.75	2.628878309 in.
2.27	0.39	5.92	2.042218875 in.
2.06	0.47	5.23	1.290919094 in.
1.75	0.63	4.12	0.824618266 in.
2.06	0.66	5.57	1.077904482 in.
1.82	0.88	4.23	0.880717666 in.
1.02	0.05	1.95	0.297314003 in.
1.08	0	3.29	0.335268539 in.
1.21	0	3.14	0.421601013 in.
2.07	0.47	4.6	1.086265401 in.
2.92	1.81	7.94	2.065652383 in.
3.22	1.86	7.75	2.98741243 in.
24.33	20	43.72	15.95876129
24.34	8.4	58.49	

Average of Sandpoint and Moscow, from Western Regional Climate Center

Average Annual Evaporation:				Evaporative Index Parameters				Average of Sandpoint and Moscow, from Western Regional Climate Center				Regression Output:			
Monthly Evaporation:	Pan Evap	Avg Temp	Pressure	Dew Pt	Wind	Corr Factor	Est evap	Q 50-yr dry	Q 50-yr wet	Q 50-yr we precip	random	random	random	random	random
Jan 0.00 inches	0.01	24.3	28.1896333	23	9.3	0.39088141	0.000459874	0.985653183	4.513679	2.965953	0.550789	0.509477	0.509477	0.509477	0.509477
Feb 0.00 inches	0.02	29	28.1896333	25	9.7	0.405386503	9.04681E-05	0.220381138	5.681949	3.743335	0.941487				2.734365008
Mar 1.02 inches	1.52	37.8	28.1896333	28	10.5	0.427801023	1.023231369	0.075206958	4.314127	1.524922	0.250456				3.509098341
Apr 1.29 inches	1.93	46.7	28.1896333	34	10.7	0.465558154	1.294470315	0.090527537	2.935867	2.141884	0.757972				0.821360646
May 3.72 inches	5.41	54.5	28.1896333	40	9.9	0.500823369	3.722068971	0.035356973	4.319761	1.392359	0.170099				1.146883036
Jun 4.07 inches	5.91	59.9	28.1896333	46	9.5	0.536133325	4.071708535	0.203127521	3.039564	0.677485	0.008651				0.550752302
Jul 5.49 inches	7.97	67.4	28.1896333	47	8.7	0.538722433	5.491778132	0.037433231	0.986659	0.888337	0.393015				0.11119609
Aug 5.15 inches	7.47	65.6	28.1896333	47	8.5	0.537809877	5.149812762	0.034031443	3.390185	1.010134	0.007146				0.218990854
Sep 3.30 inches	4.82	58.8	28.1896333	40	8.6	0.495157233	3.299997551	0.034031443	3.390185	1.010134	0.007146				0.308917424
Oct 1.01 inches	1.52	47.6	28.1896333	34	8.8	0.458544822	1.011686101	1.068296932	6.94082	2.833999	0.439427				0.314402182
Nov 0.98 inches	1.43	34.6	28.1896333	29	9.4	0.429580585	0.9776451	1.635687237	7.510365	4.580839	0.977317				0.017094187
Dec 0.00 inches	0.03	28.5	28.1896333	24	9	0.395966369	0.000201117	0.034031443	3.390185	1.010134	0.007146				2.004746561
26.04	38.04							4.453704154	47.86885	22.94509					4.344720301
															16.08285065

Existing Pond Volumes
Cell 1 - Mechanical Plant
depth area volume length width

Regression Output:

Regression Output:

Regression Output:

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

Benewah County Area, Hydrologic type C Cald, Silt Loam Infiltration Rate Calculation SCS Permeability (K) 1980 0.6 inches/hour peak 0.2 inches/hour min. 0.000423333 cm/sec, peak 0.000141111 cm/sec, min. Check With Freeze & Cherry for this soil type: 0.00001 cm/sec, peak 0.000000001 cm/sec, min. Utilize: 0.00001 cm/sec. Assume sealing with human waste, 1 order of magnitude reduction: 0.000001 cm/sec.	add	0.00	add	0.0000	0.054	add	0.00
Benewah County Area, Hydrologic type C Lacy, Stony Loam Infiltration Rate Calculation SCS Permeability (K) 1980 2 inches/hour peak 0.6 inches/hour min. 0.001411111 cm/sec, peak 0.000423333 cm/sec, min. Check With Freeze & Cherry for this soil type: 0.001 cm/sec, peak 0.0000001 cm/sec, min. Utilize: 0.000917222 cm/sec. Assume sealing with human waste, 1 order of magnitude reduction: 9.17222E-05 cm/sec.	add	0.00	add	0.0000	0.054	add	0.00

Plummer Waste Water Treatment

Evaporative Lagoon Spreadsheet - Equalization Basin

27-Sep-02

Prepared by Alan E. Gay

Wyatt Engineering

Worst Case Monthly Overflow:

Average Effluent Overflow:

Area contributing runoff:

Infiltration rate:

Average operating depth after second year:

Initial Conditions:

Influent Flow:

Assume Lagoon cells 1 initially full.

Lagoon Surface Area:

0 cfd/day

0 gallons/day

0 cuf/mo

6.64 acres

1.00E-09 cm/s =

140750 gpd =

18000000 sq.ft.

=

=

=

feet

18000000 square feet

572269.2 cuf/mo

Assume System begins operation Jan. 1

Initial

Pond vol.

Pond Surf. (sq. ft.)

Evap Vol. (cuf/mo)

Exflit. Vol. (cuf/mo)

Effl. Vol. (cuf/mo)

Depth/pond4 (ft.)

Max depth

8.6E-05 ft/month, with a an impermeable geomembrane liner

4.560987

Ponds 1 -2 surface:

18814.3 cfd/day =

Pond Vol: 71568792

Initial

Pond vol.

Pond Surf. (sq. ft.)

Evap Vol. (cuf/mo)

Exflit. Vol. (cuf/mo)

Effl. Vol. (cuf/mo)

Depth/pond4 (ft.)

Max depth

18000000 square feet

572269.2 cuf/mo

Assume System begins operation Jan. 1

Initial

Pond vol.

Pond Surf. (sq. ft.)

Evap Vol. (cuf/mo)

Exflit. Vol. (cuf/mo)

Effl. Vol. (cuf/mo)

Depth/pond4 (ft.)

Max depth

count:

Average flow balance:

131983.3 gallons/day

1.00E-10

Month Name Year	Month	Rainfall (in/mo.)	Rain Vol. (cuf/mo)	Run-off/V. (cuf/mo)	Evap Rate (in/mo.)	Influent (cuf/mo)	Pond vol. (cuf)	Pond Surf. (sq. ft.)	Evap Vol. (cuf/mo)	Exflit. Vol. (cuf/mo)	Effl. Vol. (cuf/mo)	Depth/pond4 (ft.)	Max depth
January	1	1.379124	2068886	27981	0.00	813171.14	35784396	17892288	685.6836	1542.68	0	0	0
February	1	2.756508	4134762	60863.5	0.00	752183.31	71568792	18000000	135.6991	1551.97	0	0	0
March	1	3.1719441	2579161	23832.2	1.02	788776.01	76514913	18000000	1534847	1551.97	0	0.27643933	0.2764393
April	1	4.3133371	4700057	48693.3	1.29	540758.81	78370283	18000000	1941705	1551.97	0	0.380136209	0.3801362
May	1	5.2985146	4477719	45454.8	3.72	455375.84	81716536	18000000	5883103	1551.97	0	0.56715864	0.5671586
June	1	6.583001	874502	1728.8	4.07	463507.55	81110429	18000000	6107563	1551.97	0	0.533283287	0.5332833
July	1	7.559458	839186.7	1517.62	5.49	504166.11	76341052	18000000	8237667	1551.97	0	0.266722231	0.2667222
August	1	8.077064	115595.3	654.345	5.15	540758.81	71568792	18000000	7724719	1551.97	0	0	0
September	1	9.077064	115595.3	654.345	3.30	451309.99	71568792	18000000	4949846	1551.97	0	0	0
October	1	10.2184949	3277424	28508.6	1.01	508231.97	71568792	18000000	1517529	1551.97	0	0	0
November	1	11.4768471	7152707	93091.9	0.98	496034.40	73863875	18000000	1466468	1551.97	0	0.128272499	0.1282725
December	1	12.3268468	4902703	73148.4	0.00	552956.38	80137689	18000000	301.6753	1551.97	0	0.478916734	0.4789167
January	2	13.2064537	3096806	44296.5	0.00	813171.14	85664643	18000000	689.8115	1551.97	0	0.787818887	0.7878189
February	2	14.306695	4600426	68310.9	0.00	752183.31	89616674	18000000	135.6991	1551.97	0	1.008698426	1.0086984
March	2	15.0501531	752296.3	2160.33	1.02	788776.01	95035906	18000000	1534847	1551.97	0	1.311580002	1.31158
April	2	16.3701122	5551683	61292.9	1.29	540758.81	95042740	18000000	1941705	1551.97	0	1.311961934	1.3119619
May	2	17.0	0	0	3.72	455375.84	99253217	18000000	5883103	1551.97	0	1.547286066	1.5472861
June	2	18.793169	1189753	4030.91	4.07	463507.55	94123938	18000000	6107563	1551.97	0	1.260609975	1.26061
July	2	19.1489707	2234561	15009.5	5.49	504166.11	89672115	18000000	7724719	1551.97	0	1.011797016	1.011797
August	2	20.628644	942966.5	2167.74	5.15	540758.81	84186632	18000000	8237667	1551.97	0	0.705212689	0.7052127
September	2	21.194569	2918536	23689.1	3.30	451309.99	77946254	18000000	4949846	1551.97	0	0.356437163	0.3564372
October	2	22.4282444	6423666	74434.9	1.01	508231.97	76388390	18000000	1517529	1551.97	0	0.269367964	0.269368
November	2	23.2837167	4255751	48378.1	0.98	496034.40	81875642	18000000	1466468	1551.97	0	0.57605117	0.5760512
December	2	24.3581655	5372482	80670.5	0.00	552956.38	85207786	18000000	301.6753	1551.97	0	0.762285115	0.7622851
January	3	25.2641417	3962125	58104.3	0.00	813171.14	91212041	18000000	689.8115	1551.97	0	1.097863713	1.0978637
February	3	26.1215662	1823492	24119.3	0.00	752183.31	96043200	18000000	135.6991	1551.97	0	1.367877799	1.3678778
March	3	27.1500335	2250503	19305.4	1.02	788776.01	98641308	18000000	1534847	1551.97	0	1.513086349	1.5130863
April	3	28.1937637	2906456	23529.6	1.29	540758.81	1E+08	18000000	1941705	1551.97	0	1.598161484	1.5981615
May	3	29.0	0	0	3.72	455375.84	1.02E+08	18000000	5883103	1551.97	0	1.683532936	1.6835329
June	3	30.1877683	2816525	22348	4.07	463507.55	96561700	18000000	6107563	1551.97	0	1.396856845	1.3968568
July	3	31.3391045	5086567	54376.9	5.49	504166.11	93754966	18000000	8237667	1551.97	0	1.239988119	1.2399881

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

Influent Flow Calculation:

from Influent average flow data, 1999 - 2002

	January	February	March	April	May	June	July	August	September	October	November	December
200000 gpd	185000 gpd	194000 gpd	133000 gpd	112000 gpd	114000 gpd	124000 gpd	133000 gpd	111000 gpd	125000 gpd	122000 gpd	136000 gpd	140750 gpd
813171.1 cu ft/mo	752183.3 cu ft/mo	788776 cu ft/mo	540758.8 cu ft/mo	453375.8 cu ft/mo	463507.6 cu ft/mo	504166.1 cu ft/mo	540758.8 cu ft/mo	451310 cu ft/mo	508232 cu ft/mo	496034.4 cu ft/mo	552956.4 cu ft/mo	572289.2 cu ft/mo

Run-off volume:
Hydrologic Soil Group:

SCS CN

(based on hydrologic soil group c)

C description

98 0.204082 frozen ground

98 0.204082 frozen ground

92 0.869585 saturated

89 1.235955 gravel

89 1.235955 gravel

89 1.235955 gravel

89 1.235955 gravel

89 1.235955 gravel

89 1.235955 gravel

92 0.869585 saturated

98 0.204082 frozen ground

total

sum

From Western Regional Climate Center

average Bayview

Precipitation

50-year dry

50-yr wet

Qavg

1.2

4.75

0.39

5.92

0.47

5.23

0.63

4.12

0.68

5.57

0.86

4.23

0.05

1.95

0

3.29

0

3.14

0.47

4.6

1.81

7.94

1.86

7.75

20

43.72

24.33

24.34

8.4

58.48

15.95876129

from Western Regional Climate Center

0.768045

random

random

Q 50-yr dry

Q 50-yr we

precip

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

random

Existing Pond Volumes
Cell 1 - Mechanical Plant

Regression Output:

Regression Output:

Regression Output:

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

0	17784576	0	5976	2976 Constant	17784576 Constant	0.054
1	17838324	17811450	5982	2982 Std Err of Y Est	93.92 Std Err of Y Est	0.040364
2	17892144	35876684	5988	2988 R Squared	1.00 R Squared	0.999404
3	17946036	53595774	5984	2984 No. of Observations	5 No. of Observations	5
4	18000000	71568792	6000	3000 Degrees of Freedom	3 Degrees of Freedom	3
top	18279756		6021	3036 X Coefficient(s)	X Coefficient(s)	0.003010023
	761930.2232			Std Err of Coef.	Std Err of Coef.	0.000396573
				to obtain area from depth:	to obtain area from volume:	
				enter depth, multiply by	enter vol., multiply by	
				add	add	
						17784576.00

Cell 2 - Equalization Basin

depth	area	volume	length	width	Regression Output:
0	0	0	0	0	0 Constant
0	0	0	0	0	Std Err of Y Est
0	0	0	0	0	R Squared
0	0	0	0	0	No. of Observations
0	0	0	0	0	Degrees of Freedom
0	0	0	0	0	
0	0	0	0	0	
top	9396	261			X Coefficient(s)
	521320.6791				Std Err of Coef.
					to obtain area from depth:
					enter depth, multiply by
					add
					0.00
					#NUM!
					33.15513776
					#NUM!
					1.25791E-07
					X Coefficient(s)
					Std Err of Coef.
					to obtain area from volume:
					enter vol., multiply by
					add
					0.0000
					#NUM!
					1.25791E-07
					X Coefficient(s)
					Std Err of Coef.
					to obtain area from volume:
					enter vol., multiply by
					add
					0.0000
					#NUM!
					1.25791E-07

Cell 3 -

depth	area	volume	length	width	Regression Output:
0	0	0	0	0	0 Constant
0	0	0	0	0	Std Err of Y Est
0	0	0	0	0	R Squared
0	0	0	0	0	No. of Observations
0	0	0	0	0	Degrees of Freedom
0	0	0	0	0	
top:	0				X Coefficient(s)
	9412.734483				Std Err of Coef.
					to obtain area from depth:
					enter depth, multiply by
					add
					5.03165175
					#NUM!
					9.44024E-10
					X Coefficient(s)
					Std Err of Coef.
					to obtain area from volume:
					enter vol., multiply by
					add
					3.66713E-08
					#NUM!
					3.66713E-08

Cell 4 & 5

depth	area	volume	length	width	Regression Output:
0	0	0	0	0	0 Constant
0	0	0	0	0	Std Err of Y Est
0	0	0	0	0	R Squared
0	0	0	0	0	No. of Observations
0	0	0	0	0	Degrees of Freedom
					X Coefficient(s)
					Std Err of Coef.
					to obtain area from depth:
					enter depth, multiply by
					add
					6.14817048
					#NUM!
					1.51412E-06
					X Coefficient(s)
					Std Err of Coef.
					to obtain area from volume:
					enter vol., multiply by
					add
					0.000814853
					#NUM!
					0.000814853

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

Benewah County Area, Hydrologic type C
Cold, Silt Loam
Infiltration Rate Calculation
SCS Permeability (K') 1980
0.6 inches/hour peak
0.2 inches/hour min.
0.000423333 cm/sec, peak
0.000141111 cm/sec, min.
Check With Freeze & Cherry for this soil type
0.00001 cm/sec, peak
0.000000001 cm/sec, min.
Utilize:
0.000001 cm/sec.
Assume sealing with human waste, 1 order
0.000001 cm/sec.

add

Benewah County Area, Hydrologic type C
Lacy, Stony Loam
Infiltration Rate Calculation
SCS Permeability (K') 1980
2 inches/hour peak
0.6 inches/hour min.
0.001411111 cm/sec, peak
0.000423333 cm/sec, min.
Check With Freeze & Cherry for this soil type
0.001 cm/sec, peak
0.0000001 cm/sec, min.
Utilize:
0.000917222 cm/sec.
Assume sealing with human waste, 1 order
9.17222E-05 cm/sec.

ଅପର

```
add
0.054
```

00000

0.00

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

Influent Flow Calculation:

from Influent average flow data, 1999 - 2002

	January	February	March	April	May	June	July	August	September	October	November	December
250000 gpd	1016464 cu ft/mo	833500.4 cu ft/mo	992068.8 cu ft/mo	744051.6 cu ft/mo	658668.6 cu ft/mo	668800.3 cu ft/mo	707458.9 cu ft/mo	744051.6 cu ft/mo	654602.8 cu ft/mo	711524.8 cu ft/mo	699327.2 cu ft/mo	756249.2 cu ft/mo
206000 gpd												
244000 gpd												
183000 gpd												
162000 gpd												
164000 gpd												
174000 gpd												
183000 gpd												
161000 gpd												
175000 gpd												
172000 gpd												
186000 gpd												
188250 gpd												

Run-off volume: (based on hydrologic soil group c)

Hydrologic Soil Group:

SCS CN

	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sep.	Oct.	Nov.	Dec.	total	sum
98 0.204082 frozen ground														
98 0.204082 frozen ground														
92 0.869565 saturated														
89 1.235955 gravel														
89 1.235955 gravel														
89 1.235955 gravel														
89 1.235955 gravel														
89 1.235955 gravel														
89 1.235955 gravel														
92 0.869565 saturated														
98 0.204082 frozen ground														

From Western Regional Climate Center

average Bayview

	Precipitation	50-year dry	50-yr wet	Qavg
	2.86	1.2	4.75	
	2.27	0.39	5.92	
	2.06	0.47	5.23	
	1.75	0.63	4.12	
	2.06	0.66	5.57	
	1.82	0.86	4.23	
	1.02	0.05	1.95	
	1.08	0	3.29	
	1.21	0	3.14	
	2.07	0.47	4.6	
	2.92	1.81	7.94	
	3.22	1.86	7.75	
	24.33	20	43.72	
	24.34	8.4	58.49	

Average of Sandpoint and Moscow, from Western Regional Climate Center

Evaporative Index Parameters

	Monthly Evaporation:	Pan Evap	Avg Temp	Pressure	Dew Pt	wind	Corr Factor	Est. evap
Jan	0.01	24.3	28.1896333	23	9.3	0.39088141	0.000459874	
Feb	0.02	29	28.1896333	25	9.7	0.405386503	9.04681E-05	
Mar	1.52	37.8	28.1896333	28	10.5	0.427801023	1.073231369	
Apr	1.93	46.7	28.1896333	34	10.7	0.466553154	1.294470315	
May	5.41	54.5	28.1896333	40	9.9	0.500823369	3.722068871	
Jun	5.91	59.9	28.1896333	46	9.5	0.536133325	4.071708535	
Jul	7.97	67.4	28.1896333	47	8.7	0.588722433	5.491778132	
Aug	7.47	65.6	28.1896333	47	8.5	0.537609877	5.148812762	
Sep	4.82	58.8	28.1896333	40	8.6	0.485157233	3.298997551	
Oct	1.52	47.6	28.1896333	34	8.8	0.458544822	1.011686101	
Nov	1.43	34.6	28.1896333	29	9.4	0.429880585	0.9776451	
Dec	0.03	28.5	28.1896333	24	9	0.395966369	0.00020117	
	38.04							

Existing Pond Volumes
Cell 1 - Mechanical Plant
depth area volume length width

Regression Output:

Regression Output:

Regression Output:

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

	0	-792	0	24	-33 Constant	-792 Constant	0.054
	2	-756	-1548	36	-21 Std Err of Y Est	93.92 Std Err of Y Est	0 Constant
	8	1080	-576	72	15 R Squared	1.00 R Squared	0.040364 Std Err of Y Est
	10	2268	2772	84	27 No. of Observations	5.00 No. of Observations	0.999404 R Squared
	12	3744	6784	96	39 Degrees of Freedom	3 Degrees of Freedom	5 No. of Observations
top	8775			117	75 X Coefficient(s)	X Coefficient(s)	3 Degrees of Freedom
					Std Err of Coef.	Std Err of Coef.	X Coefficient(s)
					to obtain area from depth:	to obtain area from volume:	Std Err of Coef.
					enter depth, multiply by	enter vol., multiply by	enter vol., multiply by
					add	add	add
	761930.2232				366.1791045	0.00932371	0.419388869
					32.79894971	1.35455E-07	0.000396573
					366.1791045	0.00932371	0.419388869
					-792.00	0.0000	-792.00

Cell 2 -Leaky Welland	depth	area	volume	length	width	Regression Output:
	0	262544	0	538	488 Constant	262544 Constant
	0.25	264085.25	65628.66	539.5	489.5 Std Err of Y Est	94.94187 Std Err of Y Est
	0.5	265631	132043.2	541	491 R Squared	0.999817 R Squared
	0.75	267181.25	199644.7	542.5	492.5 No. of Observations	5 No. of Observations
	1	268736	265634.4	544	494 Degrees of Freedom	3 Degrees of Freedom
	1.5	271859	400783.1	547	497	
	2	275000	537497.9	550	500	
top	139896			261	536 X Coefficient(s)	X Coefficient(s)
					Std Err of Coef.	Std Err of Coef.
					to obtain area from depth:	to obtain area from volume:
					enter depth, multiply by	enter vol., multiply by
					add	add
	521320.6791				6228.107784	3.72067E-06
					33.15513776	1.25791E-07
					6228.107784	3.72067E-06
					262544.00	0.0000

Cell 3 -	depth	area	volume	length	width	Regression Output:
	0	0	0	0	0 Constant	#NUM! Constant
	0	0	0	0	0 Std Err of Y Est	0.00402 Std Err of Y Est
	0	0	0	0	0 R Squared	0.999994 R Squared
	0	0	0	0	0 No. of Observations	5 No. of Observations
	0	0	0	0	0 Degrees of Freedom	3 Degrees of Freedom
	0	0	0	0		
top:	0				X Coefficient(s)	X Coefficient(s)
					Std Err of Coef.	Std Err of Coef.
					to obtain area from depth:	to obtain area from volume:
					enter depth, multiply by	enter vol., multiply by
					add	add
	9412.734483				9.44024E-10	3.86713E-06
					#NUM!	#NUM!
					#NUM!	#NUM!
					#NUM!	#NUM!

Cell 4 & 5	depth	area	volume	length	width	Regression Output:
	0	0	0	0	0 Constant	area fr. vol Regression Output:
	0	0	0	0	0 Std Err of Y Est	0 Constant
	0	0	0	0	0 R Squared	0.085676 Std Err of Y Est
	0	0	0	0	0 No. of Observations	0.998706 R Squared
	0	0	0	0	0 Degrees of Freedom	5 No. of Observations
	0	0	0	0		3 Degrees of Freedom
					X Coefficient(s)	X Coefficient(s)
					Std Err of Coef.	Std Err of Coef.
					to obtain area from depth:	to obtain area from volume:
					enter depth, multiply by	enter vol., multiply by
					add	add
					5.03165175	3.86713E-06
					#NUM!	#NUM!
					#NUM!	#NUM!
					#NUM!	#NUM!

Cell 4 & 5	depth	area	volume	length	width	Regression Output:
	0	0	0	0	0 Constant	area fr. vol Regression Output:
	0	0	0	0	0 Std Err of Y Est	0 Constant
	0	0	0	0	0 R Squared	0.085676 Std Err of Y Est
	0	0	0	0	0 No. of Observations	0.998706 R Squared
	0	0	0	0	0 Degrees of Freedom	5 No. of Observations
					X Coefficient(s)	X Coefficient(s)
					Std Err of Coef.	Std Err of Coef.
					to obtain area from depth:	to obtain area from volume:
					enter depth, multiply by	enter vol., multiply by
					add	add
					5.03165175	3.86713E-06
					#NUM!	#NUM!
					#NUM!	#NUM!
					#NUM!	#NUM!

Cell 4 & 5	depth	area	volume	length	width	Regression Output:
	0	0	0	0	0 Constant	area fr. vol Regression Output:
	0	0	0	0	0 Std Err of Y Est	0 Constant
	0	0	0	0	0 R Squared	0.085676 Std Err of Y Est
	0	0	0	0	0 No. of Observations	0.998706 R Squared
	0	0	0	0	0 Degrees of Freedom	5 No. of Observations
					X Coefficient(s)	X Coefficient(s)
					Std Err of Coef.	Std Err of Coef.
					to obtain area from depth:	to obtain area from volume:
					enter depth, multiply by	enter vol., multiply by
					add	add
					5.03165175	3.86713E-06
					#NUM!	#NUM!
					#NUM!	#NUM!
					#NUM!	#NUM!

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

	add	0.00	add	0.0000	0.054	add	0.00
Benewah County Area, Hydrologic type C							
Cold, Silt Loam							
Infiltration Rate Calculation							
SCS Permeability (K) 1980							
0.6 inches/hour peak							
0.2 inches/hour min.							
0.000423333 cm/sec, peak							
0.000141111 cm/sec, min.							
Check With Freeze & Cherry for this soil type:							
0.00001 cm/sec, peak							
0.000000001 cm/sec, min.							
Utilize:							
0.00001 cm/sec.							
Assume sealing with human waste, 1 order of magnitude reduction:							
0.000001 cm/sec.							
Benewah County Area, Hydrologic type C							
Lacy, Stony Loam							
Infiltration Rate Calculation							
SCS Permeability (K) 1980							
2 inches/hour peak							
0.6 inches/hour min.							
0.001411111 cm/sec, peak							
0.000423333 cm/sec, min.							
Check With Freeze & Cherry for this soil type:							
0.001 cm/sec, peak							
0.0000001 cm/sec, min.							
Utilize:							
0.000917222 cm/sec.							
Assume sealing with human waste, 1 order of magnitude reduction:							
9.17222E-05 cm/sec.							

Plummer Waste Water Treatment

Evaporative Lagoon Spreadsheet - Equalization Basin

27-Sep-02

Prepared by Alan E. Gay

Wyatt Engineering

Worst Case Monthly Overflow:

Average Effluent Overflow:

Area contributing runoff:

Infiltration rate:

Average operating depth after second year:

Initial Conditions:

Influent Flow:

Assume Lagoon cells 1 initially full.

Lagoon Surface Area:

length 400 width 350
3.213958 acres

0 cfd/day

0 gallons/day

1.00E-09 cm/s =

8.6E-05 ft/month, with a an impermeable geomembrane liner

Ponds 1-2 surface:

4.38704

Pond Vol:

8784

188250 gpd =

25163.7 cfd/day =

143744 sq.ft.

130568 square feet

765397.3 cuft/mo

Assume System begins operation Jan. 1

Initial

count:

Average flow balance:

187979 gallons/day

1.00E-10

Month	Month Name	Year	Rainfall (in/mo.)	Rain Vol. (cuft/mo.)	Run-off Vol. (cuft/mo.)	Evap Rate (in/mo.)	Evap Vol. (cuft/mo.)	Influent (cuft/mo.)	Pond vol. (cuft)	Pond Surf. (sq.ft.)	Evap Vol. (cuft/mo.)	Exflit Vol. (cuft/mo.)	Effl. Vol. (cuft/mo.)	Depth/pond4 (ft.)	Max depth
1	January	1	4.173413	49991.92	-11231.2	0.00	0.00	1016463.93	4392	1049.956	0.040237	0.09053	0	0	0
2	February	1	2.230028	26712.76	-5711.06	0.00	0.00	833500.42	296272.5	116095.6	0.875226	10.0098	0	2.376395544	2.3763955
3	March	1	1.707331	20451.55	-2790.66	1.02	1.02	992068.80	387419.8	119245.7	10167.99	10.2814	0	3.129823517	3.1298235
4	April	1	2.520634	30193.83	-4200.22	1.29	1.29	744051.60	623627.2	127409	13743.93	10.9853	0	5.082326568	5.0823266
5	May	1	0.52199	6252.743	-142.552	3.72	3.72	658668.63	616573.5	127165.2	39443.15	10.9642	0	5.0240202	5.0240202
6	June	1	2.148939	25741.43	-3287.24	4.07	4.07	666800.34	478554.2	122395.3	41529.83	10.553	0	3.883145344	3.8831453
7	July	1	0.743402	8904.963	-405.396	5.49	5.49	707458.90	362924.3	118399.1	54185.14	10.2084	0	2.927342846	2.9273428
8	August	1	0.912047	10925.1	-663.213	5.15	5.15	744051.60	261343.4	114898.5	49304.51	9.90574	0	2.087669847	2.0876698
9	September	1	2.510563	30073.2	-4175.07	3.30	3.30	654602.77	202988.5	112872.1	31038.85	9.73188	0	1.603387582	1.6033876
10	October	1	1.07546	12882.58	-947.814	1.01	1.01	711524.75	89106.83	108936	9184.083	9.39251	0	0.663952788	0.6639528
11	November	1	2.814371	33712.41	-5684.81	0.98	0.98	699327.18	40028.87	107239.8	8736.874	9.24627	0	0.258271775	0.2582718
12	December	1	2.977704	35668.93	-7831.55	0.00	0.00	756249.16	8784	3744	0.062748	0.32281	0	0	0
1	January	2	2.261787	27093.2	-5800.98	0.00	0.00	1016463.93	29526.15	106876.9	4.095827	9.21497	0	0.171455744	0.1714557
2	February	2	3.563331	42683.95	-9495.77	0.00	0.00	833500.42	303925	116380.1	0.87722	10.0326	0	2.439651127	2.4396511
3	March	2	3.155096	37793.85	-6582.17	1.02	1.02	992068.80	407258.7	119931.3	10226.46	10.3405	0	3.293812956	3.293813
4	April	2	0.885573	10807.99	-620.084	1.29	1.29	744051.60	658584.4	128580.9	13868.19	11.0846	0	5.35784379	5.3578438
5	May	2	4.307762	51801.25	-8878.1	3.72	3.72	658668.63	633774.6	127759.7	39627.54	11.0155	0	5.168205429	5.1682054
6	June	2	0.160671	1924.628	-18.573	4.07	4.07	666800.34	532183.8	124248.7	42158.72	10.7128	0	4.328450666	4.3284507
7	July	2	0.275024	3294.427	-174823	5.49	5.49	707458.90	395376.8	119520.7	54898.42	10.3051	0	3.195596409	3.1955964
8	August	2	5.465412	65468.35	-12032.1	5.15	5.15	744051.60	288075.6	115812.3	49700.99	9.98539	0	2.308639406	2.3086394
9	September	2	3.46478	41503.45	-6629.67	3.30	3.30	654602.77	272508.5	115274.3	31699.46	9.9301	0	2.179960794	2.1799608
10	October	2	3.461036	41458.59	-6619.82	1.01	1.01	711524.75	166931.6	111625.6	9410.838	9.62441	0	1.307256889	1.3072569
11	November	2	2.891155	34632.18	-5870.64	0.98	0.98	699327.18	140530.7	110713.2	9019.849	9.54574	0	1.089025338	1.0890253
12	December	2	4.997005	59857.45	-13575.6	0.00	0.00	756249.16	96246.04	109182.7	1829874	9.41378	0	0.722965907	0.7229659
1	January	3	3.394523	40661.86	-9015.86	0.00	0.00	1016463.93	135421.8	110536.6	4.236079	9.53052	0	1.046794683	1.0467947
2	February	3	4.222743	50582.83	-11371.6	0.00	0.00	833500.42	420174	120377.7	0.907508	10.379	0	3.400571308	3.4005713
3	March	3	0.892653	10692.79	-927.569	1.02	1.02	992068.80	529530.4	124157	10586.78	10.7049	0	4.304517144	4.3045171
4	April	3	4.060771	48642.63	-8213.93	1.29	1.29	744051.60	757422.9	132033	14242.73	11.3839	0	6.188288967	6.188289
5	May	3	1.052479	12607.29	-906.033	3.72	3.72	658668.63	764305.1	132270.9	41026.77	11.4045	0	6.245177365	6.2451774
6	June	3	2.243094	26869.28	-3515.31	4.07	4.07	666800.34	630292.8	127639.4	43309.2	11.0051	0	5.137424628	5.1374246
7	July	3	0.067094	803.6997	-87.6078	5.49	5.49	707458.90	513782.9	123612.8	56571.17	10.658	0	4.17434762	4.1743476

Plummer Waste Water Treatment

27-Sep-02
Prepared by Alan E. Gay
Wyatt Engineering

Benewah County Area, Hydrologic type C Cold, Silt Loam Infiltration Rate Calculation SCS Permeability (K) 1980 0.6 inches/hour peak 0.2 inches/hour min. 0.000423333 cm/sec, peak 0.000141111 cm/sec, min. Check With Freeze & Cherry for this soil type: 0.00001 cm/sec, peak 0.000000001 cm/sec, min. Utilize: 0.00001 cm/sec. Assume sealing with human waste, 1 order of magnitude reduction: 0.000001 cm/sec.	add	0.00	add	0.0000	0.054	add	0.00
Benewah County Area, Hydrologic type C Lacy Stony Loam Infiltration Rate Calculation SCS Permeability (K) 1980 2 inches/hour peak 0.6 inches/hour min. 0.001411111 cm/sec, peak 0.000423333 cm/sec, min. Check With Freeze & Cherry for this soil type: 0.001 cm/sec, peak 0.00000001 cm/sec, min. Utilize: 0.000917222 cm/sec. Assume sealing with human waste, 1 order of magnitude reduction: 9.1722E-05 cm/sec.	add	0.00	add	0.0000	0.054	add	0.00

Plummer Water Usage as Basis for ERU count

08/30/02

Compiled by AEG from 2000 City of Plummer Data

Gallons/residential Service: 5300 per month

User	water use gallons/mo	equiv. ERU	
	12500	2.358490566	1
	25750	4.858490566	1
	4826	1	1
	167	1	1
	19670	3.711320755	1
		1	1
	28267	5.333396226	1
	2555	1	1
	70	1	1
	667	1	1
	1000	1	1
	1956	1	1
	43773	8.259056604	1
	2910	1	1
	2248	1	1
	21400	4.037735849	1
	4333	1	1
	51000	9.622641509	1
	4000	1	1
	34000	6.41509434	1
	1665	1	1
	108000	20.37735849	1
	2950	1	1
	3833	1	1
	1000	1	1
	30000	5.660377358	1
		1	1
		1	1
	500	1	1
	500	1	1
	4000	1	1
	1000	1	1
	1000	1	1
	50	1	1
	50	1	1
	500	1	1
	12000	2.264150943	1
	4800	1	1
	1000	1	1
	1500	1	1
		1	1
		1	1
	10670	2.013207547	1
	23000	4.339622642	1
	18000	3.396226415	1
	3000	1	1
	740	1	1
	28000	5.283018868	1
	1000	1	1
		1	1
	3000	1	1
	3500	1	1
	1150	1	1
commercial ERUs		126	53
Residences:		345	100
total:		471	445 current total ERUs

Plummer ERU count/wastewater flow projection
08/30/02

08/30/02

Compiled by AEG from 1980 through 2000 Census Data

Year	Population	household: ERUs	Benewah County	Ratios	Ratio Rate of Change
1980	610	191	8292	3499	0.054631
1990	796	277	7937	3731	0.007659
2000	990	336 (345)	9171	3580	0.074243
2002	1040	345			0.107949
2008	1206	400			0.093855
2028	1977	656	516 projection		
			846 projection		

[illegible]

Average flows(MGD)	January	February	March	April	May	June	July	August	September	October	November	December	Peak Average Annual (MGD)
2000	0.19	0.15	0.12	0.092	0.123	0.092	0.0595	0.0585	0.0537	0.067	0.064	0.078	0.19 actual
2002	0.1429	0.128	0.137	0.0765	0.0566	0.0577	0.0674	0.0759	0.055	0.068	0.065	0.060	0.14 actual
2008	0.151	0.137	0.146	0.085	0.064	0.066	0.076	0.084	0.063	0.077	0.074	0.098	0.15 projection
2028	0.200	0.185	0.194	0.133	0.112	0.114	0.124	0.133	0.111	0.125	0.122	0.136	0.20 projection

Year

January	2.94	4.75	96	1.2	97	0.99	28/1992	13	9	1	0	7.5	31.5	90
February	3.15	5.92	96	0.39	90	1.17	23/1999	12	9	2	0	1.4	8	99
March	2.45	5.23	50	0.47	90	1.95	16/1950	11	8	1	0	0.6	5	89
April	2.08	4.12	97	0.63	51	1.49	24/1996	10	7	1	0	0	0	89
May	2.78	5.57	98	0.66	92	1.2	20/1994	10	7	2	0	0.3	3.5	100
June	1.9	4.23	50	0.86	89	1.44	Apr-90	8	5	1	0	0	0	89
July	0.72	1.95	97	0.05	99	1.02	14/1993	3	2	0	0	0	0	89
August	0.89	3.29	89	0	88	1.43	24/1989	4	2	0	0	0	0	88
r	0.93	3.14	95	0	90	1.07	28/1995	4	3	0	0	0	0	88
October	2.9	4.6	50	0.47	88	1.55	27/1994	10	7	2	0	0	0	88
November	4.26	7.94	96	1.81	90	1.45	Jan-94	17	13	2	0	0	0	89
December	4.24	7.75	96	1.86	97	1.2	May-89	16	11	3	0	4.2	10	88
Annual	29.23	43.72	96	26.85	97	1.95	19500316	119	84	15	2	14.1	14.5	99
Winter	10.33	15.65	96	7.19	98	1.2	19891205	41	30	6	0	13.2	8.5	99
Spring	7.31	10.63	97	3.27	92	1.95	19500316	32	23	3	1	0.8	5	89
Summer	3.5	5.36	90	2.08	98	1.44	19900604	15	9	2	0	0	0	89
Fall	8.09	13.83	96	5.55	90	1.55	19941027	31	23	4	1	0	0	89

IDAHO Pan Evaporation Data

MOSCOW UNIV OF IDAHO | 1893-2000 |

SANDPOINT EXPERMNT STN | 1910-2000 |

Blended average:

annual		
0.00	47.11	47.11
0.00	28.79	28.79
0.00		37.95

Plummer Creek (01-CJ020010)

Plummer Creek (01-CJ020010)								
STL ID	2571	2657	2741	2804	2915	3068	3277	3399
CLIENT ID	0300	0300	0300	0300	0300	0300	0300	0300
SAMPLE DATE		03/15/99	4/1/1999	4/15/1999	5/10/1999	6/2/1999	7/6/1999	10/1/1999
ANALYSIS PARAMETERS		METHOD		UNITS				
PHYSICAL PROPERTIES								
Total Dissolved Solids	EPA 160.1	mg/L						
Total Suspended Solids	EPA 160.2	mg/L						
Turbidity	EPA 180.1	NTU						
Hardness as CaCO3	EPA 200.7	mg/L						
INORGANIC NON-METALLICS								
Chloride, Cl	EPA 300.0	mg/L						
Fluoride, F	EPA 300.0	mg/L						
Nitrate as N	EPA 300.0	mg/L						
Nitrite as N	EPA 300.0	mg/L						
Total Phosphorous	EPA 200.7	mg/L						
ortho-Phosphate as P	EPA 300.0	mg/L						
Sulfate	EPA 300.0	mg/L						
TKN	EPA 351.4	mg/L						

SAMPLE DATE

04/03/00 04/25/00 05/05/00 05/18/00 6/27/2000 9/27/2000

SAMPLE DATE		
ANALYSIS PARAMETER METHOD UNITS		
PHYSICAL PROPERTIES		
Total Dissolved Solids	EPA 160.1	mg/L
Total Suspended Solids	EPA 160.2	mg/L
Turbidity	EPA 180.1	NTU
Hardness as CaCO3	EPA 200.7	mg/L
INORGANIC NON-METALLICS		
Chloride, Cl	EPA 300.0	mg/L
Fluoride, F	EPA 300.0	mg/L
Nitrate as N	EPA 300.0	mg/L

Nitrite as N	EPA 300.0	mg/L	<0.010	<0.010	<0.010	<0.010	<0.010
Total Phosphorous	EPA 200.7	mg/L	0.030	0.065	0.018	0.058	0.032
ortho-Phosphate as P	EPA 300.0	mg/L	<0.006	0.030	0.022	<0.006	0.032
Sulfate	EPA 300.0	mg/L	2.45	3.20	2.58	2.84	6.62
TKN	EPA 351.4	mg/L	0.127	0.171	0.351	0.112	0.110

ANALYSIS	DATE	TIME	LOCATION	ANALYST
3/22/2001	4/11/2001	5/10/2001	5/23/2001	

ANALYSIS	DATE	TIME	LOCATION	ANALYST
3/22/2001	4/11/2001	5/10/2001	5/23/2001	

Total Dissolve	7	EPA 160.1	mg/L
Total Suspensi	2	EPA 160.2	mg/L
Turbidity	0.02	EPA 180.1	NTU
Hardness as i	0.33	EPA 200.7	mg/L

INORGANIC NON-METALLICS

Chloride, Cl	0.02	EPA 300.0	mg/L	4.10	4.71	3.95	5.56
Fluoride, F	0.02	EPA 300.0	mg/L	0.175	0.284	0.239	0.033
Nitrate as N	0.005	EPA 300.0	mg/L	1.78	1.34	0.350	0.130
Nitrite as N	0.01	EPA 300.0	mg/L	<0.010	<0.010	<0.010	<0.010
Total Phosphi	0.005	EPA 200.7	mg/L	0.073	0.073	0.072	0.055
ortho-Phosph	0.01	EPA 300.0	mg/L	0.064	0.032	0.048	0.036
Sulfate	0.03	EPA 300.0	mg/L	4.36	4.16	4.05	4.13
TKN	0.02	EPA 351.2	mg/L	0.560	0.560	0.323	0.659

Supplemental to Plummer Creek Data
Phosphorus Discharges from Plummer Wastewater Treatment Facility
September 27, 2002
Prepared by Alan E. Gay, P.E.
Wyatt Engineering, Inc.

The following phosphorus loads are estimates. The 1999 through 2001 estimates are based on a per capita loading of 0.007 pounds per day, a population of 990 people in Plummer, and the recorded flows for the November through May period. I also estimated that the effective phosphorus removal through the plant averages 50%, based on settlement and filtration.

	Jan-99	Feb-99	Mar-99	Apr-99	May-99	Nov-99	Dec-99
Estimated TP load (lbs/day)	6.93	6.93	6.93	6.93	6.93	6.93	6.93
Estimated TP effluent (lbs/day)	3.465	3.465	3.465	3.465	3.465	3.465	3.465
Recorded avg. Plant Flow (mgd)	0.1477	0.19975	0.14229	0.154067	0.124839	0.115033	0.219133
Estimated Plant Discharge Conc. (mg/L)	2.812534	2.079656	2.919463	2.696309	3.327584	3.611225	1.895701
Recorded Creek Flow @ Mouth (cfs)	89.916	NA	54	26.45983	14.7335	NA	NA
dilution ratio, Creek:Plant	393.4865	#VALUE!	245.274	111.0074	76.2834	#VALUE!	#VALUE!
Recorded TP, Mouth, mg/L:	NA	NA	0.039	0.017	0.035	NA	NA
Calculated Creek Load, lbs/day:	#VALUE!	#VALUE!	11.353	2.354	2.780	#VALUE!	#VALUE!
Estimated non-plant TP, lbs/day:	#VALUE!	#VALUE!	7.888	-1.111	-0.685	#VALUE!	#VALUE!
Estimated non-plant TP, mg/L:	#VALUE!	#VALUE!	0.027	-0.008	-0.009	#VALUE!	#VALUE!

	Jan-00	Feb-00	Mar-00	Apr-00	May-00	Nov-00	Dec-00
Estimated TP load (lbs/day)	6.93	6.93	6.93	6.93	6.93	6.93	6.93
Estimated TP effluent (lbs/day)	3.465	3.465	3.465	3.465	3.465	3.465	3.465
Recorded avg. Plant Flow (mgd)	0.199258	0.152207	0.123516	0.091867	0.123419	0.064967	0.078194
Estimated Plant Discharge Conc. (mg/L)	2.08479	2.729254	3.363215	4.521894	3.365852	6.394222	5.312603
Recorded Creek Flow @ Mouth (cfs)	NA	NA	NA	14.38	14.7335	NA	NA
dilution ratio, Creek:Plant	#VALUE!	#VALUE!	#VALUE!	101.1753	77.16068	#VALUE!	#VALUE!
Recorded TP, Mouth, mg/L:	NA	NA	NA	0.048	0.038	NA	NA
Calculated Creek Load, lbs/day:	#VALUE!	#VALUE!	#VALUE!	3.683	3.018	#VALUE!	#VALUE!
Estimated non-plant TP, lbs/day:	#VALUE!	#VALUE!	#VALUE!	0.218	-0.447	#VALUE!	#VALUE!
Estimated non-plant TP, mg/L:	#VALUE!	#VALUE!	#VALUE!	0.003	-0.006	#VALUE!	#VALUE!

Note: May flow in creek is estimated

	Jan-01	Feb-01	Mar-01	Apr-01	May-01	Nov-01	Dec-01
Estimated TP load (lbs/day)	6.93	6.93	6.93	6.93	6.93	6.93	6.93
Estimated TP effluent (lbs/day)	3.465	3.465	3.465	3.465	3.465	3.465	3.465
Recorded avg. Plant Flow (mgd)	0.1266	0.113393	0.179603	0.16	0.119226	0.071846	0.201935
Estimated Plant Discharge Conc. (mg/L)	3.28129	3.66347	2.312939	2.596321	3.48424	5.781956	2.057149
Recorded Creek Flow @ Mouth (cfs)	NA	NA	26.89	66.4825	6.52	NA	NA
dilution ratio, Creek:Plant	#VALUE!	#VALUE!	96.77208	268.572	35.34685	#VALUE!	#VALUE!
Recorded TP, Mouth, mg/L:	NA	NA	0.064	0.073	0.064	NA	NA
Calculated Creek Load, lbs/day:	#VALUE!	#VALUE!	9.278	26.165	2.232	#VALUE!	#VALUE!
Estimated non-plant TP, lbs/day:	#VALUE!	#VALUE!	5.813	22.700	-1.233	#VALUE!	#VALUE!
Estimated non-plant TP, mg/L:	#VALUE!	#VALUE!	0.040	0.063	-0.035	#VALUE!	#VALUE!

Projected Loadings, Design (2028)

	1/1	2/1	3/1	4/1	5/1	11/1	12/1
Estimated TP load (lbs/day)	13.839	13.839	13.839	13.839	13.839	13.839	13.839
Estimated TP effluent (lbs/day)	0.345975	0.345975	0.345975	0.27678	0.207585	0.207585	0.27678
Projected avg. Plant Flow (mgd)	0.200	0.185	0.194	0.133	0.112	0.122	0.136
Estimated Plant Discharge Conc. (mg/L)	0.207907	0.224688	0.214243	0.249299	0.221802	0.204118	0.243607
Estimated Creek Flow @ Mouth (cfs)	15	52	30.00	25	4	2	100
dilution ratio, Creek:Plant	48.59758	182.0696	100.1572	121.4017	23.04241	10.60261	474.5191
Estimated TP, Mouth, mg/L:	0.004	0.001	0.036	0.024	0.010	0.019	0.001
Calculated Creek Load, lbs/day:	0.346	0.346	5.764	3.242	0.208	0.208	0.277
Estimated non-plant TP, lbs/day:	0.000	0.000	5.418	2.965	0.000	0.000	0.000
Estimated non-plant TP, mg/L:	0.000	0.000	0.034	0.022	0.000	0.000	0.000

Phosphorus removal based on using biological nutrient removal to achieve 1 mg/L (90% removal) followed by alum addition to achieve 0.5 mg/L (50% reduction) and filtration to remove most of the remaining TP to 0.25 mg/L or less (50%+ reduction) for a total reduction of 97.5% or better. We will achieve this with either a new mechanical treatment plant or a retrofit of the existing facility.

Plummer Wastewater Treatment Facility
 September 27, 2002
 Process Calculations
 Wyatt Engineering, Inc.
 Prepared by Alan E. Gay, P.E.

Process Description

The goal of the process modification for the existing plant scenarios is to achieve water quality objectives while retaining the use of the existing facility. The process will include biological nutrient removal. The BNR process will be sized to include appropriately sized basins for anoxic, aerobic and anearobic biological treatment of wastewater in order to remove phosphorus during stream discharge periods and nitrogen during land application periods and for leaky wetland and mound discharge options. Enhanced pre-treatment will be used, with the addition of a longer head-works that can accommodate either a comminutor or a automated self-cleaning bar screen. The new headworks will have the necessary hydraulic capacity for the design flows.

The first and/or second cells will be divided by means of move-able baffle curtains into the various chambers necessary for maintaining the appropriate bacterial colonies. These curtains are manufactured by ____ and _____. The return will be modified to allow multiple discharge points to the various chambers to facilitate return to the appropriate chamber depending upon the selected configuration. In addition, the operator will be assisted by a process logic system to aid in adjusting the appropriate valves depending upon the treatment necessary.

Discharge to Plummer Creek, if this is selected, will be flow paced.

Settlement

Use Stokes Law to size the required area of the settlement cell of the new lined pretreatment portion of the plant:

$$v_s = d^2 \cdot g \cdot (r_p - r_v) / (18 \cdot \mu)$$

where:

v_s = settlement velocity
 d = particle diameter
 g = acceleration due to gravity
 r_p = density of particle
 r_v = density of fluid
 μ = dynamic viscosity of fluid

Assuming a worst case temperature of 5 deg. C, the dynamic viscosity of the water (assumed equivalent to Plummer's wastewater) is 1.519 centipoise, or 0.001021 lbs/ft-sec

Assume the particle diameter for removal is 0.05 mm = 0.000164 feet

Assume the particle specific gravity is 1.2 so the density is 74.88 lb/ft³

Therefore: $v_s = 0.000588$ ft/sec.

And minimal area is $Q/A = 380.3257$ gpd/ft²

$Q_{peak} = 477000$ gpd, non-tribal

$A = 1254.188$ ft²

Use a FS of 2: 2508.376 ft², say 2500 ft²

Use a maximum depth of 8 ft., 3:1 side slopes.

Width: 247 feet

length: 10.12146 feet

actual depth: 3.373819 feet

Incorporate the settlement cell into the Anoxic Cell

Anoxic Biological Treatment

Phosphorus Removal

Use Monod Model $s = D \cdot K_s / (\mu - D)$

where

s = concentration of nutrient
 D = dilution rate = F/V = Feed rate/volume = days⁻¹
 K_s = half saturation coefficient = 1 mg/L
 μ = maximum growth rate coefficient = 1.5 mg/L/Day

Influent P: 10 mg/L

Effluent P: 0.25 mg/L

Required retention time: 0.735043 days

$Q_{peak} = 477000$ gpd, non-tribal

$V_{min.} = 46867.45$ ft³

Use first 70 feet of first cell

Volume: 50336 ft³

Nitrogen Removal

Use Monod Model $s = D \cdot K_s / (\mu - D)$

where

s = concentration of nutrient
 D = dilution rate = F/V = Feed rate/volume = days⁻¹
 K_s = half saturation coefficient = 5 mg/L
 μ = maximum growth rate coefficient = 1.5 1/Day

Influent TKN (N): 50 mg/L

Effluent NO₂ (N): 1 mg/L

Required retention time: 0.734694 days

$Q_{peak} = 477000$ gpd, non-tribal

$V_{min.} = 46845.21$ ft³

Aerobic Treatment

BOD removal: $Le/Lo = 1/(1+kt)$, $t = (Lo/Le-1)/kT$
 $kT = k20^{\theta(T-20)}$

where:

Le = effluent BOD, mg/L
 Lo = influent BOD, mg/L

k = BOD removal constant, per day
t = detention time, days
theta = temperature coefficient

Le: 20
Lo: 237
k20: 0.5 (conservative estimate)
theta: 1.035
T: 4 deg. C
kT: 0.29
therefore, t = 37.63 days
Lagoon Vol.: 7525499 gallons at 4 deg. C
1005948 cubic feet
12 working depth
175 bottom width
83829.03 sq. ft. average area
211 average width
247 top width (3:1 side slopes)
427.1518 top length

Le: 20
Lo: 237
k20: 0.5 (conservative estimate)
theta: 1.035
T: 30 deg. C
kT: 0.71
therefore, t = 15.38 days
Lagoon Vol.: gallons at 30 deg. C

Oxygen Required/day = lb of BOD removed per day (coefficient = 1.0):
concentration BOD removed: 217 mg/L 91.56% reduction For 30 deg. C
Influent Flow: 200000.00 gal/day BOD removal = 381.0127 lbs/day
Influent BOD Load: 395.4 lbs/day = 15.87553 lbs/hour
lbs removed/day: 362.0051 lbs/day
Oxygen required/day = 362.0051 lbs/day; say 400 lbs/day
Oxygen required/hour = 16.66667 lbs/hr

Oxygen transfer, conventional surface aerators:

$$R = R_o \frac{(B \cdot C_s - C_t)}{9.2 \cdot 1.02^{(T-20)} \cdot \alpha}$$

where:

R = actual rate of oxygen transfer, lb of O2/hp-hr
Ro = rate of O2 transfer of manufacturer's unit under standard conditions, lb of O2/hp-hr
B = oxygen saturation coefficient of wastewater
Cs = oxygen concentration at saturation, mg/L
Ct = oxygen concentration existing in liquid, mg/L
T = temperature of lagoon liquid, deg. C
alpha = oxygen transfer coefficient
9.2 = saturation of oxygen concentration in pure water at 20 deg. C, mg/L

Try Ro of 2.5 lbs O2/hp-hr
B 0.8
alpha 0.9
Cs 13.1 at 4 deg. C
Ct 2

Try Ro of 2.5 lbs O2/hp-hr
B 0.8
alpha 0.9
Cs 7.6 at 30 deg. C
Ct 2

Therefore R: 1.51

Therefore I 1.22

power required: 11.03 hp
Use 2 7.5 hp surface aerators

power reqd 13.05184 hp

Anaerobic Cell

Utilize second cell for anaerobic treatment, keep well mixed with propellor mixer(s)

minimum volume = 0.3 * aerated basin volume (10-state standards)

Volume: 301784.5 cubic feet
2257650 gallons
12 working depth
175 bottom width
25148.71 sq. ft. average area
211 average width
247 top width (3:1 side slopes)
149.046 top length

Plummer Wastewater Treatment Facility

September 27, 2002

Process Calculations

Wyatt Engineering, Inc.

Prepared by Alan E. Gay, P.E.

Process Description

The goal of the process modification for the existing plant scenarios is to achieve water quality objectives while retaining the use of the existing facility. The process will include biological nutrient removal. The BNR process will be sized to include appropriately sized basins for anoxic, aerobic and anearobic biological treatment of wastewater in order to remove phosphorus during stream discharge periods and nitrogen during land application periods and for leaky wetland and mound discharge options. Enhanced pre-treatment will be used, with the addition of a longer head-works that can accommodate either a comminutor or a automated self-cleaning bar screen. The new headworks will have the necessary hydraulic capacity for the design flows.

The first and/or second cells will be divided by means of move-able baffle curtains into the various chambers necessary for maintaining the appropriate bacterial colonies. These curtains are manufactured by _____ and _____. The return will be modified to allow multiple discharge points to the various chambers to facilitate return to the appropriate chamber depending upon the selected configuration. In addition, the operator will be assisted by a process logic system to aid in adjusting the appropriate valves depending upon the treatment necessary.

Discharge to Plummer Creek, if this is selected, will be flow paced.

Settlement

Use Stokes Law to size the required area of the settlement cell of the new lined pretreatment portion of the plant:

$$v_s = d^2 \cdot g \cdot (r_p - r_v) / (18 \cdot \mu)$$

where:

v_s = settlement velocity
 d = particle diameter
 g = acceleration due to gravity
 r_p = density of particle
 r_v = density of fluid
 μ = dynamic viscosity of fluid

Assuming a worst case temperature of 5 deg. C, the dynamic viscosity of the water (assumed equivalent to Plummer's wastewater) is 1.519 centipoise, or 0.001021 lbs/R-sec

Assume the particle diameter for removal is 0.05 mm = 0.000164 feet

Assume the particle specific gravity is 1.2 so the density is 74.88 lb/ft3

Therefore: $v_s = 0.000588$ ft/sec.

And minimal area is $Q/A = 380.3257$ gpd/ft2

$Q_{peak} = 477000$ gpd, non-tribal

$A = 1254.188$ ft2

Use a FS of 2: 2508.376 ft2, say 2500 ft2

Use a maximum depth of 8 ft., 3:1 side slopes.

Width: 247 feet

length: 10.12146 feet

actual depth: 3.373819 feet

Incorporate the settlement cell into the Anoxic Cell

Anoxic Biological Treatment

Phosphorus Removal

Use Monod Model $s = D \cdot K_s / (\mu - D)$

where

s = concentration of nutrient
 D = dilution rate = F/V = Feed rate/volume = days⁻¹
 K_s = half saturation coefficient = 1 mg/L
 μ = maximum growth rate coefficient = 1.5 mg/L/Day

Influent P: 10 mg/L

Effluent P: 1 mg/L

Required retention time: 0.740741 days

$Q_{peak} = 527000$ gpd, tribal

$V_{min} = 52181.58$ ft3

Use first 70 feet of first cell

Volume: 50336 ft3

Nitrogen Removal

Use Monod Model $s = D \cdot K_s / (\mu - D)$

where

s = concentration of nutrient
 D = dilution rate = F/V = Feed rate/volume = days⁻¹
 K_s = half saturation coefficient = 5 mg/L
 μ = maximum growth rate coefficient = 1.5 1/Day

Influent TKN (N): 50 mg/L

Effluent NO2 (N): 1 mg/L

Required retention time: 0.734694 days

$Q_{peak} = 527000$ gpd, tribal

$V_{min} = 51755.6$ ft3

Aerobic Treatment

BOD removal: $Le/L_0 = 1/(1+kt)$, $t = (L_0/Le-1)/kT$
 $kT = k20 \cdot \theta^{(T-20)}$

where:

Le = effluent BOD, mg/L
 L_0 = influent BOD, mg/L

k = BOD removal constant, per day
t = detention time, days
theta = temperature coefficient

Le: 60
Lo: 237
k20: 0.5 (conservative estimate)
theta: 1.035
T: 4 deg. C
kT: 0.29
therefore, t = 10.23 days
Lagoon Vol.: 2557629 gallons at 4 deg. C
341883.4 cubic feet
8 working depth
199 bottom width
42735.42 sq. ft. average area
223 average width
247 top width (3:1 side slopes)
213.0557 top length

Le: 20
Lo: 237
k20: 0.5 (conservative estimate)
theta: 1.035
T: 30 deg. C
kT: 0.71
therefore, t = 15.38 days
Lagoon Vol.: gallons at 30 deg. C

Oxygen Required/day = lb of BOD removed per day (coefficient = 1.0):
concentration BOD removed: 177 mg/L 74.68% reduction
Influent Flow: 250000.00 gal/day
Influent BOD Load: 494.2 lbs/day
lbs removed/day: 369.095 lbs/day
Oxygen required/day = 369.095 lbs/day; say 400 lbs/day
Oxygen required/hour = 16.66667 lbs/hr

For 30 deg. C
BOD removal = 434.0565 lbs/day
= 18.08569 lbs/hour

Oxygen transfer, conventional surface aerators:

$$R = Ro \cdot (B \cdot Cs - Ct) / 9.2 \cdot 1.02^{(T-20)} \cdot \alpha$$

where:

R = actual rate of oxygen transfer, lb of O₂/hp-hr
Ro = rate of O₂ transfer of manufacturer's unit under standard conditions, lb of O₂/hp-hr
B = oxygen saturation coefficient of wastewater
Cs = oxygen concentration at saturation, mg/L
Ct = oxygen concentration existing in liquid, mg/L
T = temperature of lagoon liquid, deg. C
alpha = oxygen transfer coefficient
9.2 = saturation of oxygen concentration in pure water at 20 deg. C, mg/L

Try Ro of 2.5 lbs O₂/hp-hr
B 0.8
alpha 0.9
Cs 13.1 at 4 deg. C
Ct 2

Try Ro of 2.5 lbs O₂/hp-hr
B 0.8
alpha 0.9
Cs 7.6 at 30 deg. C
Ct 2

Therefore R: 1.51

Therefore I 1.22

power required: 11.03 hp
Use 2 7.5 hp surface aerators

power reqd 14.86889 hp

Anaerobic Cell

Utilize second cell for anaerobic treatment, keep will mixed with propellor mixer(s)

minimum volume = 0.3 * aerated basin volume (10-state standards)

Volume: 102565 cubic feet
767288.8 gallons
11.5 working depth
178 bottom width
8918.696 sq. ft. average area
212.5 average width
247 top width (3:1 side slopes)
70.86916 top length

Plummer Wastewater Treatment Facility

September 27, 2002

Process Calculations

Wyatt Engineering, Inc.

Prepared by Alan E. Gay, P.E.

Process Description

The goal of the process modification for the existing plant scenarios is to achieve water quality objectives while retaining the use of the existing facility. The process will include biological nutrient removal. The BNR process will be sized to include appropriately sized basins for anoxic, aerobic and anearobic biological treatment of wastewater in order to remove phosphorus during stream discharge periods and nitrogen during land application periods and for leaky wetland and mound discharge options. Enhanced pre-treatment will be used, with the addition of a longer head-works that can accommodate either a comminutor or a automated self-cleaning bar screen. The new headworks will have the necessary hydraulic capacity for the design flows.

The first and/or second cells will be divided by means of move-able baffle curtains into the various chambers necessary for maintaining the appropriate bacterial colonies. These curtains are manufactured by _____ and _____. The return will be modified to allow multiple discharge points to the various chambers to facilitate return to the appropriate chamber depending upon the selected configuration. In addition, the operator will be assisted by a process logic system to aid in adjusting the appropriate valves depending upon the treatment necessary.

Discharge to Plummer Creek, if this is selected, will be flow paced.

Settlement

Use Stokes Law to size the required area of the settlement cell of the new lined pretreatment portion of the plant:

$$v_s = \frac{d^2 \cdot g \cdot (r_p - r_v)}{18 \cdot \mu}$$

where:

v_s = settlement velocity
 d = particle diameter
 g = acceleration due to gravity
 r_p = density of particle
 r_v = density of fluid
 μ = dynamic viscosity of fluid

Assuming a worst case temperature of 5 deg. C, the dynamic viscosity of the water (assumed equivalent to Plummer's wastewater) is 1.519 centipoise, or 0.001021 lbs/ft-sec

Assume the particle diameter for removal is 0.05 mm = 0.000164 feet

Assume the particle specific gravity is 1.2 so the density is 74.88 lb/ft³

Therefore: v_s = 0.000588 ft/sec.

And minimal area is Q/A = 380.3257 gpd/ft²

Q_{peak} = 477000 gpd, non-tribal

A = 1254.188 ft²

Use a FS of 2: 2508.376 ft², say 2500 ft²

Use a maximum depth of 8 ft., 3:1 side slopes.

Width: 247 feet

length: 10.12146 feet

actual depth: 3.373819 feet

Incorporate the settlement cell into the Anoxic Cell

Anoxic Biological Treatment

Phosphorus Removal

Use Monod Model $s = D \cdot K_s / (\mu - D)$

where

s = concentration of nutrient
 D = dilution rate = F/V = Feed rate/volume = days⁻¹
 K_s = half saturation coefficient = 1 mg/L
 μ = maximum growth rate coefficient = 1.5 mg/L/Day

Influent P: 10 mg/L

Effluent P: 1 mg/L

Required retention time: 0.740741 days

Q_{peak} = 527000 gpd, tribal

$V_{min.}$ = 52181.58 ft³

Use first 70 feet of first cell

Volume: 50336 ft³

Nitrogen Removal

Use Monod Model $s = D \cdot K_s / (\mu - D)$

where

s = concentration of nutrient
 D = dilution rate = F/V = Feed rate/volume = days⁻¹
 K_s = half saturation coefficient = 5 mg/L
 μ = maximum growth rate coefficient = 1.5 1/Day

Influent TKN (N): 50 mg/L

Effluent NO₂ (N): 1 mg/L

Required retention time: 0.734694 days

Q_{peak} = 527000 gpd, tribal

$V_{min.}$ = 51755.6 ft³

Aerobic Treatment

BOD removal: $L_e/L_o = 1/(1+kt)$, $t = (L_o/L_e - 1)/kT$
 $KT = kT_0 \cdot \theta^{(T-20)}$

where:

L_e = effluent BOD, mg/L
 L_o = influent BOD, mg/L

k = BOD removal constant, per day
t = detention time, days
theta = temperature coefficient

Le: 60
Lo: 237
k20: 0.5 (conservative estimate)
theta: 1.035
T: 4 deg. C
kT: 0.29
therefore, t = 10.23 days
Lagoon Vol.: 2557629 gallons at 4 deg. C
341883.4 cubic feet
8 working depth
199 bottom width
42735.42 sq. ft. average area
223 average width
247 top width (3:1 side slopes)
213.0557 top length

Le: 20
Lo: 237
k20: 0.5 (conservative estimate)
theta: 1.035
T: 30 deg. C
kT: 0.71
therefore, t = 15.38 days
Lagoon Vol.: gallons at 30 deg. C

Oxygen Required/day = lb of BOD removed per day (coefficient = 1.0):
concentration BOD removed: 177 mg/L 74.68% reduction
Influent Flow: 250000.00 gal/day
Influent BOD Load: 494.2 lbs/day
lbs removed/day: 369.095 lbs/day
Oxygen required/day = 369.095 lbs/day; say 400 lbs/day
Oxygen required/hour = 16.6667 lbs/hr
Oxygen transfer, conventional surface aerators:
 $R = R_o \cdot (B^*C_s - C_t) / 9.2 \cdot 1.02^{(T-20)^{\alpha}}$
where:

R = actual rate of oxygen transfer, lb of O2/hp-hr
R_o = rate of O2 transfer of manufacturer's unit under standard conditions, lb of O2/hp-hr
B = oxygen saturation coefficient of wastewater
C_s = oxygen concentration at saturation, mg/L
C_t = oxygen concentration existing in liquid, mg/L
T = temperature of lagoon liquid, deg. C
alpha = oxygen transfer coefficient
9.2 = saturation of oxygen concentration in pure water at 20 deg. C, mg/L

Try R_o of 2.5 lbs O2/hp-hr
B 0.8
alpha 0.9
C_s 13.1 at 4 deg. C
C_t 2

Try R_o of 2.5 lbs O2/hp-hr
B 0.8
alpha 0.9
C_s 7.6 at 30 deg. C
C_t 2

Therefore R: 1.51

Therefore I 1.22

power required: 11.03 hp
Use 2 7.5 hp surface aerators

power reqd 14.86889 hp

Anaerobic Cell

Utilize second cell for anaerobic treatment, keep well mixed with propellor mixer(s)
minimum volume = 0.3 * aerated basin volume (10-state standards)
Volume: 102565 cubic feet

767288.8 gallons
11.5 working depth
178 bottom width
8918.696 sq. ft. average area
212.5 average width
247 top width (3:1 side slopes)
70.86916 top length

COD 50 lbs/acre/day
N 150 lbs/acre/day
P 27 lbs/acre/day

COD 50 lbs/acre/day
N 2 lbs/acre/day
P 1 lbs/acre/day

acres	lbs/day	flow cu. ft/day	Allowable conc. COD (mg/L)	BOD (mg/L)	N (mg/L)	P (mg/L)
20	1000	57702.78	277.7273	185.1516	11.10909	5.554547
40	40	69673.29	230.0113	153.3408	9.20045	4.600225
20	20	69944.26	229.1202	152.7468	9.164807	4.582404
		60938.93	262.9787	175.3191	10.51915	5.259574
		57844.39	277.0474	184.6983	11.0819	5.540949
		56005.11	286.1461	190.764	11.44584	5.722921
		43782.75	366.0263	244.0176	14.64105	7.320527
		56451.28	283.8848	189.2564	11.35538	5.677691
		46679.73	343.3105	228.8737	13.73242	6.86621
		46809.26	343.8295	229.2197	13.75318	6.87658
		59895.76	267.5589	178.3726	10.70235	5.351177
		61276.63	261.5294	174.353	10.46118	5.230589

WYATT ENGINEERING, INC.

A Subsidiary of



Memorandum

DATE: 9/11/02

W.O. #: 685900

TO: Alan Gay

cc: John Manion

FROM: Tracy Johnson

SUBJECT: Plummer Cost Estimates: Disposal Systems

Alan,

I have provided rough cost estimates for the following wastewater disposal methods (in lieu of surface water discharge). These estimates are based on construction experience, supplier quotes, and manufacturer's recommendations. Naturally, the estimates presented herein are based on approximate disposal rates and "ballpark" calculations of system components, but should give you an idea of potential cost impacts for evaluation purposes.

1. Land Application: Subsurface Drip Irrigation
 - a. Without Tribe \$850,000 - \$950,000
 - b. With Tribe: \$1,100,000 - 1,200,000
2. Land Application: Subsurface Disposal (Mound System)
 - a. Without Tribe: \$1,300,000 - \$1,500,000
 - b. With Tribe: \$1,500,000 - \$1,700,000
3. Total Containment
 - a. Without Tribe \$55,000,000 - \$60,000,000
 - b. With Tribe \$65,000,000 - \$70,000,000

Geoflow Subsurface Dripline Disposal Field Calculation

Job Description: Plummer WWTP
 Engineer: Wyatt Engineering, Inc.
 Prepared by: Tracy Johnson
 Date: 10-Sep-02
 Project No. 685900

Worksheet - Field Design

	Single Zone	Multiple Zones	
Number of Zones	1	56	zone(s)
A) Quantity of effluent to be disposed per day		4,464	gallons / day
B) Hydraulic loading rate	0.2	0.2	gallons / sq.ft. / day
C) Determine total area required	1,250,000	22,321	square ft.
D) Choose spacing between WASTEFLOW lines	1	1	ft.
D) Choose spacing between WASTEFLOW emitters	1	1	ft.
E) Total linear ft.	1,250,000	22,321	each
F) Total number of emitters	1,250,000	22,321	each
G) Write "Classic" for WASTEFLOW Classic or write "PC" for pressure compensating dripline	PC	PC	WASTEFLOW dripline
H) Pressure at the beginning of the dripfield	25	25	psi
I) Feet of Head at the beginning of the dripfield	57.75	57.75	ft.
J) What is the flow rate per emitter in gph?	0.53	0.53	gallons per hour
K) Total flow for the area (gph)	662,500	11,830	gallons per hour
Total flow for the area (gpm)	11041.67	197.17	gallons per minute
L) Select pipe diameters for manifolds and submains	Refer to a PVC chart	6	inch
M) Select Vortex Filter (item no.)	Consult Factory	Consult Factory	
N) Maximum length of each WASTEFLOW line. Sketch a layout of the WASTEFLOW lines in the disposal plot to make sure that the maximum lateral length of each WASTEFLOW dripline is not exceeded.	260	260	ft.

with Tribe - 250,000 GPD

Estimated Cost for Construction: Mound Disposal System

Average Daily Flow = 0.25MGD

Item	Description	Qty	Unit	Unit Price	Contingency	Price
1	Tanks	5	EA	\$1,500	\$1,500	\$9,000
2	Electrical & Controls	1	LS	\$55,000	\$11,000	\$66,000
3	Electrical Conduit	1	LS	\$7,500	\$1,500	\$9,000
4	Site preparation	1	LS	\$20,000	\$4,000	\$24,000
5	C33 Sand mound fill	18,000	CY	\$25	\$90,000	\$540,000
6	Geotextile	170,000	SF	\$2	\$68,000	\$408,000
7	Effluent Screens	5	EA	\$200	\$200	\$1,200
8	Pump Chambers	2	EA	\$800	\$320	\$1,920
9	PVC Transport Pipe	5,000	LF	\$10	\$10,000	\$60,000
10	PVC Fittings	1	LS	\$500	\$100	\$600
11	PVC Laterals	60,000	LF	\$5	\$60,000	\$360,000
12	PVC Manifolds	750	LF	\$4	\$600	\$3,600
13	Valves/cleanouts	30	EA	\$250	\$1,500	\$9,000
14	Appurtenances	1	LS	\$50,000	\$10,000	\$60,000
15	Trench Backfilling	6,000	CY	\$8	\$9,600	\$57,600
16	Tank Backfilling	300	CY	\$8	\$480	\$2,880
17	Topsoil	600	CY	\$3	\$360	\$2,160
18	Grading/Finishing	1	AC	\$1,000	\$200	\$1,200
19	Seeding	5	AC	\$1,500	\$1,500	\$9,000

Total \$1,625,160

Estimated Cost of Construction (including 20% contingency) = \$1.5M - \$1.7M

Estimated Cost for Construction: Mound Disposal System

Average Daily Flow = 0.2MGD

Item	Description	Qty	Unit	Unit Price	Contingency	Price
1	Tanks	4	EA	\$1,500	\$1,200	\$7,200
2	Electrical & Controls	1	LS	\$55,000	\$11,000	\$66,000
3	Electrical Conduit	1	LS	\$7,500	\$1,500	\$9,000
4	Site preparation	1	LS	\$20,000	\$4,000	\$24,000
5	C33 Sand mound fill	15,000	CY	\$25	\$75,000	\$450,000
6	Geotextile	160,000	SF	\$2	\$64,000	\$384,000
7	Effluent Screens	4	EA	\$200	\$160	\$960
8	Pump Chambers	2	EA	\$800	\$320	\$1,920
9	PVC Transport Pipe	5,000	LF	\$10	\$10,000	\$60,000
10	PVC Fittings	1	LS	\$500	\$100	\$600
11	PVC Laterals	45,000	LF	\$5	\$45,000	\$270,000
12	PVC Manifolds	500	LF	\$4	\$400	\$2,400
13	Valves/cleanouts	20	EA	\$250	\$1,000	\$6,000
14	Appurtenances	1	LS	\$50,000	\$10,000	\$60,000
15	Trench Backfilling	5,000	CY	\$8	\$8,000	\$48,000
16	Tank Backfilling	200	CY	\$8	\$320	\$1,920
17	Topsoil	500	CY	\$3	\$300	\$1,800
18	Grading/Finishing	1	AC	\$1,000	\$200	\$1,200
19	Seeding	5	AC	\$1,500	\$1,500	\$9,000

Total \$1,404,000

Estimated Cost of Construction (including 20% contingency) = \$1.3M - \$1.5M

Plummer Wastewater Improvements Project
Plummer, ID

TKJ 9/11/02

Estimated Cost for Construction: Total Containment
Peak Daily Flow: 0.527MGD

Containment Area Dimensions: Length: 6000 feet
 Width: 3500 feet
 Depth: 4 feet

Item	Description	Qty	Unit	Unit Price	Contingency	Price
1	Excavation Inc. Haul	3,111,111	CY	\$14	\$4,355,556	\$47,911,111
2	Containment Area Grading/Comp	777,778	SY	\$4	\$311,111	\$3,422,222
3	Liner	21,040,008	LS	\$1	\$4,208,002	\$25,248,010
Total						\$76,581,343

Estimated Cost of Construction (including 10% contingency) = \$75M - \$80M

Price does not include land purchase (approximately 490 ac)

Estimated Cost for Construction: Total Containment

Peak Daily Flow: 0.477MGD

Containment Area Dimensions: Length: 6000 feet
 Width: 3000 feet
 Depth: 4 feet

Item	Description	Qty	Unit	Unit Price	Contingency	Price
1	Excavation Inc. Haul	2,666,667	CY	\$14	\$3,733,333	\$41,066,667
2	Containment Area Grading/Comp	666,667	SY	\$4	\$266,667	\$2,933,333
3	Liner	18,036,008	LS	\$1	\$3,607,202	\$21,643,210
Total						\$65,643,210

Estimated Cost of Construction (including 10% contingency) = \$65M - \$70M

Price does not include land purchase (approximately 420 ac)

APPENDIX VI

***Wastewater Treatment Plant
Cost Estimate Data***

Option 1 W/Tribe
City of Plummer, Idaho
WWTP Option 1 W/Tribe
Biological Treatment with Extended Aeration and Activated Sludge in Modified Lagoons-Irrigation
Opinion of Probable Cost

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Mobilization	1	LS	\$218,300.00	\$218,300.00
2	Influent Lift Station, Including Generator & Controls.	1	LS	\$120,000.00	\$120,000.00
3	Equalization Basin-Excavation, Compaction & Backfill	120000	CY	\$10.00	\$1,200,000.00
4	Equalization Basin-Liner	396000	SF	\$1.00	\$396,000.00
5	Equalization Basin - Piping incl. valving	160	LF	\$28.00	\$4,480.00
5	Retrofit Existing Cells (Piping, etc)	650	LF	\$28.00	\$18,200.00
	Anoxic C1, 2-New. Aer. C1,				
6	Excavation of Existing Cells (Dredging)	25542	CY	\$15.00	\$383,130.00
	Anoxic C1, 2-New. Aer. C1,				
7	Sludge Dredging and Disposal	12771	CY	\$15.00	\$191,565.00
	Anoxic C1, 2-New. Aer. C1,				
8	Impermeable Membrane Liner, existing & new cells	214550	SF	\$1.00	\$214,550.00
	Anoxic C1&2, New. Aer. C1&2, Anoxic C1&2				
9	Allum Injection into Additional Cell 1				
	Allum Injection Building	180	SF	\$120.00	\$21,600.00
	Flash mix tank & mixer	1	LS	\$5,000.00	\$5,000.00
	Pumps & Piping	1	LS	\$8,000.00	\$8,000.00
	Electrical and Instrumentation	1	LS	\$7,000.00	\$7,000.00
	Piping Force Main	300	LF	\$30.00	\$9,000.00
10	Aeration Diffusers, Blower Equipment with Sound Attenuation, and Installation	1	LS	\$218,000.00	\$218,000.00
11	Baffle Curtains	1	LS	\$95,000.00	\$95,000.00
12	Retrofit Filter Cells (Piping, flow channels, etc)	400	FT	\$28.00	\$11,200.00
	Filter Cell 1, Add. Cell 1, Filter Cell 2, Add Cell 2				
13	Excavation of Existing Filter Cells (Dredge Sand)	4000	CY	\$21.00	\$84,000.00
	Filter Cell 1 & Filter Cell 2, 3 & 4 (import new sand)				
14	Impermeable Membrane Liner, Install new	23000	SF	\$1.25	\$28,750.00
	Filter Cell 1 & Filter Cell 2, 3 & 4				
15	Ultra-Violet Light Disinfection and pH Adjustment	1	LS	\$105,000.00	\$105,000.00
16	Flow Paced Pump @ Plummer Creek Package VFD Paco or Equal	1	LS	\$40,000.00	\$40,000.00
17	Wet Well for Flow Pace Pump	1	LS	\$10,000.00	\$10,000.00
18	Extend 3PH Power to Flow Pace Pump	1	LS	\$5,000.00	\$5,000.00
19	Convert Chlorination Lagoon to Equalization Lagoon	2000	CY	\$21.00	\$42,000.00
20	Chlorination Lagoon Equalization Piping	100	LF	\$28.00	\$2,800.00
21	Chlorination Lagoon Equalization MH- Suction	1	LS	\$3,000.00	\$3,000.00
22	Impermeable Membrane Liner, Installed in new Equalization lagoon	11500	SF	\$1.25	\$14,375.00
23	Irrigation Area (Existing Retrofit)	1	LS	\$20,000.00	\$20,000.00
24	Irrigation Area (New Land Retrofit with Irrigation Equipment)	1	LS	\$65,000.00	\$65,000.00
25	Solids Handling Drying Bed				
	Excavation, compaction & debris removal	2378	CY	\$15.00	\$35,670.00
	Piping -Perf. (Gravity to Packaged Lift Station)	326	LF	\$25.00	\$8,150.00
	Drain Rock	40	CY	\$10.00	\$400.00
	Sand @ 6" of depth.	1189	CY	\$17.50	\$20,807.50
	Geofabric	2048	SF	\$1.00	\$2,048.00
	Liner	2048	SF	\$1.00	\$2,048.00
	Concrete to separate Discharge Structures.	40	CY	\$400.00	\$16,000.00
	Manhole	1	EA	\$3,000.00	\$3,000.00
	Discharge Structures.	8	EA	\$1,500.00	\$12,000.00
	4" Pressure Piping within Drying Bed	900	LF	\$28.00	\$25,200.00
	4" Pressure Piping Out Side Drying Bed	400	LF	\$28.00	\$11,200.00
	Valves	11	EA	\$500.00	\$5,500.00
26	Packaged Lift Station Return from Drying Bed (e-one or equal) + Elec.	1	LS	\$5,500.00	\$5,500.00
27	Sludge Collection Sump Pumps Within Anoxic Cells--Low Velocity	1	LS	\$35,000.00	\$35,000.00
	Concrete Sump within Anoxic Cells	1	LS	\$4,000.00	\$4,000.00
	3PH Electrical	1	LS	\$3,000.00	\$3,000.00
	Force Main Piping to Sludge Holding Tank	600	LF	\$28.00	\$16,800.00
	Valves	4	LS	\$500.00	\$2,000.00
28	Sludge Collection Sump Pumps Within Anoxic Cells--Low Velocity	1	LS	\$35,000.00	\$35,000.00
	Concrete Sump within Anoxic Cells	1	LS	\$4,000.00	\$4,000.00
	3 PH Electrical	1	LS	\$3,000.00	\$3,000.00
	Force Main Piping to Sludge Holding Tank	600	LF	\$28.00	\$16,800.00
	Valves	4	LS	\$500.00	\$2,000.00
29	Lift Station Return to Sludge Drying Beds-high velocity flow, Including sludge h	1	LS	\$90,000.00	\$90,000.00
	Force Main Piping to Sludge Drying Beds	1000	LF	\$28.00	\$28,000.00
	Valves	2	EA	\$500.00	\$1,000.00
30	Influent Wastewater Screen	1	Each	\$90,000.00	\$90,000.00
31	Return Flow from emergency bypass @ old chlorination cell to Aer. Cell 1 & 2				
	Retrofit existing pumps	1	LS	\$50,000.00	\$50,000.00
	Piping	300	FT	\$28.00	\$8,400.00
	Valves	4	EA	\$500.00	\$2,000.00
32	Construction dewatering during construction Including: pumps, piping				
	Pipe (perf.)	1539	LF	\$25.00	\$38,475.00
	Washed Rock	300	CY	\$10.00	\$3,000.00
	Geofabric	12312	SF	\$1.00	\$12,312.00
	Pipe, Washed Rock & Geofabric	1539	LF	\$35.00	\$53,865.00
	Wet Well	1	LS	\$3,000.00	\$3,000.00
	Sump Pump	1	LS	\$15,000.00	\$15,000.00
	Electrical	1	LS	\$10,000.00	\$10,000.00

\$1.6M

33 Yard piping-out side lagoons	1000 LF	\$35.00	\$35,000.00
Valves Out side Lagoon	10 Ea	\$500.00	\$5,000.00
34 Access Road	1600 SY	\$12.00	\$19,200.00
35 Fencing	2200 LF	\$12.00	\$26,400.00
36 Extend Power to Site	1 LS	\$10,000.00	\$10,000.00
37 Emergency Power Generator	1 Each	\$42,500.00	\$42,500.00
38 Lab Equipment BOD5, TSS, Fecal, TP	1 LS	\$50,000.00	\$50,000.00
39 Stream Sampler : Samples for BOD5, TSS, Fecal, TP	1 QTY		
Note: The Stream Sampler Will Auto sample for DO, PH			
Effluent Sampler (indoor) Sampler: Samples for BOD5, TSS, Fecal, TP	1 QTY		
Note: The Effluent Sampler Will Auto sample for DO, PH			
Influent Sampler: Sample for BOD5, TSS,	1 QTY		
Note: The Influent Sampler Will Auto sample for DO, PH			
Out Door Heaters for effluent & Influent Sampler	2 QTY		
Flow Meter (980)	1 QTY		
Sum:	1 LS		\$23,500.00
37 Main Electrical & Control Pannel & Instrumentation	1 LS	\$100,000.00	\$100,000.00
38 Mixer in anaerobic Cell	1 LS	\$7,000.00	\$7,000.00
39 Electrical	1 LS	\$3,000.00	\$3,000.00
40 Operations Building- Retrofit Existing	400 SF	\$120.00	\$48,000.00

Subtotal	\$4,584,725.50
Sales Tax at 5%	\$229,236.28
Land Purchase for irrigation area	\$230,000.00
Subtotal	\$5,043,961.78
Contingencies at 20%	\$1,008,792.36
Subtotal	\$6,052,754.13
Engineering at 20%	\$1,210,550.83
Interest to fund Engineering, 1 Year at 5%	\$60,527.54
Administrative and Legal	\$228,236.28
Total	<u>\$7,552,068.77</u>
Total - Engineering	\$6,341,517.95

7.5m

Inflow/Infiltration Removal

Construction Subtotal	\$873,900.00
Sales Tax at 5.0%	\$43,695.00
Land Purchase	\$0.00
Subtotal	\$917,595.00
Contingencies at 10%	\$91,759.50
Subtotal	\$1,009,354.50
Engineering at 20%	\$201,870.90
Interest to fund Engineering, 1 Year at 5%	\$10,093.55
Administrative and Legal	\$42,695.00
Total	\$1,284,013.95
Total-Engineering	\$1,062,143.05

1.2m

Total Project

Construction Subtotal	\$5,458,625.50
Sales Tax at 5.0%	\$272,931.28
Land Purchase	\$230,000.00
Subtotal	\$5,961,556.78
Contingencies at 10%, I/I, 20% WWT	\$1,100,551.86
Subtotal	\$7,062,108.63
Engineering at 20%	\$1,412,421.73
Interest to fund Engineering, 1 Year at 5%	\$70,621.09
Administrative and Legal	\$270,931.28
Total	\$8,816,082.72
Total-Engineering	\$7,403,660.99

Annual Operations and Maintenance Costs

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Class II Operator - 1	2080	Hours	\$29.00	\$60,320.00
2	Sludge Disposal	1250	CY	\$5.00	\$6,250.00
3	Motor and Pump Maintenance @ 2%	1	LS	\$10,930.00	\$10,930.00
4	Electricity	209600	kWh	\$0.07	\$14,672.00
5	Analytical (BOD5, TSS, Fecal, TP)	1	LS	\$5,000.00	\$5,000.00
6	Miscellaneous Supplies	1	LS	\$2,000.00	\$2,000.00
	Subtotal				\$99,172.00
	Contingencies at 20%				\$19,834.40
	Subtotal				\$119,006.40
	Administrative and Engineering Support@5%				\$5,950.32
	Total				\$124,956.72

Wow

Total Present Value

Present Value of Probable Construction Cost	at	4.00% ann. Inflation	\$8,816,082.72
Present Value of Probable Operations and Maintenance Cost	at	4.00% ann. Inflation	\$1,698,202.60
Total			\$10,514,285.32

Table 2 W/ Tribe
City of Plummer, Idaho
WWTP Option 2 W/ Tribe
Package Biological Treatment with Extended Aeration and Activated Sludge—Mechanical Package Plant—Irrigation
Opinion of Probable Cost

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Mobilization	1	LS	\$154,000.00	\$154,000.00
3	Site Work	1	LS	\$40,000.00	\$40,000.00
4	Preparation Earthwork On Site	5000	CY	\$10.00	\$50,000.00
5	Haul & Place Crush Material	3000	CY	\$20.00	\$60,000.00
6	Mechanical Influent Wastewater Bar Screen	1	LS	\$90,000.00	\$90,000.00
7	Electrical	1	LS	\$3,000.00	\$3,000.00
8	Influent Lift Station, Including Generator & Controls. Electrical	1	LS	\$120,000.00	\$120,000.00
9	Piping From Lift Station to Mechanical Building	500	LF	\$28.00	\$14,000.00
10	Gravity Piping to Existing Cell #2 for Equalization	400	LF	\$28.00	\$11,200.00
11	Equalization Basin-Excavation, Compaction & Backfill	9680	CY	\$10.00	\$96,800.00
12	Equalization Basin-Liner	459000	SF	\$1.00	\$459,000.00
13	Equalization Basin - Piping	200	LF	\$28.00	\$5,600.00
14	Equalization Basin Valving	4	EA	\$500.00	\$2,000.00
15	Sludge Dredging and Disposal Of Existing Cell 1 Aeration & Cell 2 Aeration	12404	CY	\$15.00	\$186,060.00
16	Return Flow from equalization basin to Mechanical Package Plant Retrofit existing pumps	1	LS	\$50,000.00	\$50,000.00
	Piping	300	FT	\$28.00	\$8,400.00
	Valves	4	EA	\$500.00	\$2,000.00
17	Mechanical Package Plant Anoxic Tank	1	LS	\$815,400.00	\$815,400.00
	Aerobic Tank				
	Anaerobic Tank				
	Aerobic Tank				
	Clarifier Tank				
	Aerobic Digester				
18	Sand Filter for phosphorus Removal	1		\$195,000.00	\$195,000.00
19	Ultra-Violet Light Disinfection and pH Adjustment	1	LS	\$105,000.00	\$105,000.00
21	Existing Irrigation field (Retrofit Piping & Irrigation Equipment for Equalization)	1	LS	\$20,000.00	\$20,000.00
22	New Irrigation field (Retrofit Piping & Irrigation Equipment for Equalization)	1	LS	\$65,000.00	\$65,000.00
23	Solids Handling Drying Bed Excavation, compaction & debris removal	2378	CY	\$ 15.00	\$ 35,670.00
	Piping -Perf. (Gravity to Packaged Lift Station)	326	LF	\$ 25.00	\$ 8,150.00
	Drain Rock	40	CY	\$ 10.00	\$ 400.00
	Sand @ 6" of depth.	1189	CY	\$ 17.50	\$ 20,807.50
	Geofabric	2048	SF	\$ 1.00	\$ 2,048.00
	Liner	2048	SF	\$ 1.00	\$ 2,048.00
	Concrete to separate Discharge Structures.	40	CY	\$ 400.00	\$ 16,000.00
	Manhole	1	EA	\$ 3,000.00	\$ 3,000.00
	Discharge Structures.	8	EA	\$ 1,500.00	\$ 12,000.00
	4" Pressure Piping within Drying Bed	900	LF	\$ 28.00	\$ 25,200.00
	4" Pressure Piping Out Side Drying Bed	400	LF	\$ 28.00	\$ 11,200.00
	Valves	11	EA	\$ 500.00	\$ 5,500.00
24	Packaged Lift Station Return from Drying Bed (e-one or equal) + Elec. To Mech. Plant	1	LS	\$5,500.00	\$5,500.00
25	Yard Piping from Mechanical Building to Sludge Drying Beds	200	FT	\$28.00	\$5,600.00
26	Fencing	2000	LF	\$15.00	\$30,000.00
27	Extend Power to Site	1	LS	\$10,000.00	\$10,000.00
28	Electrical and Instrumentation Controls	1	LS	\$40,000.00	\$40,000.00
29	Mechanical Package Plant Building	2500	SF	\$120.00	\$300,000.00
30	Pilot Study	1	LS	\$60,000.00	\$60,000.00
31	Lab Equipment BOD5, TSS, Fecal, TP	1	LS	\$50,000.00	\$50,000.00
32	Stream Sampler: Samples for BOD5, TSS, Fecal, TP Note: The Stream Sampler Will Auto sample for DO, PH Effluent Sampler (Indoor) Sampler: Samples for BOD5, TSS, Fecal, TP Note: The Effluent Sampler Will Auto sample for DO, PH Influent Sampler: Sample for BOD5, TSS, Note: The Influent Sampler Will Auto sample for DO, PH Out Door Heaters for effluent & Influent Sampler Flow Meter (980)	1	QTY		
	Sum:	1	LS		\$23,500.00
33	Power & Electrical for influent, effluent & indoor sampler	1	LS	\$10,000.00	\$10,000.00
	Subtotal				\$3,232,083.50
	Sales Tax at 5.0%				\$161,604.18
	Land Purchase for Mechanical Treatment Plant				\$30,000.00
	Land Purchase for Irrigation Equalization (23 Acres)				\$230,000.00
	Subtotal				\$3,423,687.68
	Contingencies at 20%				\$684,737.54
	Subtotal				\$4,108,425.21
	Engineering at 20%				\$821,685.04
	Interest to fund Engineering, 1 Year at 5%				\$41,084.25

Opt 1
is
1.6m
why
\$0.56m
here

Administrative and Legal	\$160,604.18
Total	\$5,131,798.68
Total-Engineering	\$4,310,113.64

Inflow/Infiltration Removal

Construction Subtotal	\$873,900.00
Sales Tax at 5.0%	\$43,695.00
Land Purchase	\$0.00
Subtotal	\$917,595.00
Contingencies at 10%	\$91,759.50
Subtotal	\$1,009,354.50
Engineering at 20%	\$201,870.90
Interest to fund Engineering, 1 Year at 5%	\$10,093.55
Administrative and Legal	\$42,695.00
Total	\$1,264,013.95
Total-Engineering	\$1,062,143.05

Total Project

Construction Subtotal	\$4,105,983.50
Sales Tax at 5.0%	\$205,299.18
Land Purchase	\$260,000.00
Subtotal	\$4,341,282.68
Contingencies at 10%, I/I, 20% WWT	\$776,497.04
Subtotal	\$5,117,779.71
Engineering at 20%	\$1,023,555.94
Interest to fund Engineering, 1 Year at 5%	\$51,177.80
Administrative and Legal	\$203,299.18
Total	\$6,395,812.62

Annual Operations and Maintenance Costs

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Class II Operator - 3/4 FTE	1560	Hours	\$29.00	\$45,240.00
2	Sludge Disposal	1250	CY	\$5.00	\$6,250.00
3	Motor and Pump Maintenance @ 2%	1	LS	\$4,310.00	\$4,310.00
4	Electricity	209600	kWh	\$0.07	\$14,672.00
5	Analytical (BOD5, TSS, Fecal, TP)	1	LS	\$5,000.00	\$5,000.00
6	Replacement UV	50	Each	\$20.00	\$1,000.00
7	Miscellaneous Supplies	1	LS	\$4,000.00	\$4,000.00
	Subtotal				\$80,472.00
	Contingencies at 20%				\$16,094.40
	Subtotal				\$96,566.40
	Administrative and Engineering Support@5%				\$4,828.32
	Total				\$101,394.72

Total Present Value

Present Value of Probable Construction Cost	at	4.00% ann. Inflation	\$6,395,812.62
Present Value of Probable Operations and Maintenance Cost	at	4.00% ann. Inflation	\$1,377,987.33
Total			\$7,773,799.96

Table 3
City of Plummer, Idaho
WWTP Alternative #3
Biological Treatment- Facilitative Lagoon, Total Containment
Opinion of Probable Cost

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Mobilization	1	LS	\$55,000.00	\$55,000.00
2	Mechanical Influent Wastewater Bar Screen	1	LS	\$80,000.00	\$80,000.00
3	Influent Lift Station, Including Generator & Controls.	1	LS	\$105,000.00	\$105,000.00
4	Extend Electrical to site:	1	LS	\$15,000.00	\$15,000.00
5	Sludge Dredging and Disposal	1	LS	\$200,000.00	\$200,000.00
6	Yard Piping	1	LS	\$5,000.00	\$5,000.00
7	Containment Lagoon Excavation	2666667	CY	\$14.00	\$37,333,333.33
8	Containment lagoon Import Fill	666666.7	SY	\$4.00	\$2,666,666.67
9	Containment Lagoon Liner	18036008	LS	\$1.00	\$18,036,008.00
10	Effluent Sampler (Indoor) Sampler: Samples for BOD5, TS:	1	QTY		
	Note: The Effluent Sampler Will Auto sample for DO, PH				
	Influent Sampler: Sample for BOD5, TSS,	1	QTY		
	Note: The Influent Sampler Will Auto sample for DO, PH				
	Out Door Heaters for effluent & Influent Sampler	2	QTY		
	Flow Meter (980)	1	QTY		
	Sum:	1	LS		\$18,700.00
11	Power & Electrical for influent Sampler	1	LS		
	Subtotal				\$58,514,708.00
	Sales Tax at 5.0%				\$2,925,735.40
	Land Purchase for Total Containment Area	1	LS	240000	\$240,000.00
	Subtotal				\$61,680,443.40
	Contingencies at 20%				\$12,336,088.68
	Subtotal				\$74,016,532.08
	Engineering at 20%				\$14,803,306.42
	Interest to fund Engineering, 1 Year at 5%				\$740,165.32
	Administrative and Legal				\$2,924,735.40
	Total				\$92,484,739.22
	Total-Engineering				\$77,681,432.80

Annual Operations and Maintenance Costs

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Class I Operator - 1/2	1040	Hours	\$29.00	\$30,160.00
2	Sludge Disposal	1250	CY	\$5.00	\$6,250.00
3	Motor and Pump Maintenance @ 2%	1	LS	\$2,100.00	\$2,100.00
4	Electricity	71428.57	kWh	\$0.07	\$5,000.00
5	Analytical (BOD5, TSS)	1	LS	\$0.00	\$0.00
6	Miscellaneous Supplies	1	LS	\$4,000.00	\$4,000.00
	Subtotal				\$47,510.00
	Contingencies at 20%				\$9,502.00
	Subtotal				\$57,012.00
	Administrative and Engineering Support@5%				\$2,850.60
	Total				\$59,862.60

Total Present Value

Present Value of Probable Construction Cost	at	4.00% ann. Inflation	\$92,484,739.22
Present Value of Probable Operations and Maintenance Cost	at	4.00% ann. Inflation	\$813,552.27
Total			\$93,298,291.48

Option 4 W/ Tribe
City of Plummer, Idaho
WWTP Option 4 W/ Tribe
Biological Treatment with Extended Aeration and Activated Sludge in Modified Lagoons-Cascading
Opinion of Probable Cost

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Mobilization	1	LS	\$111,000.00	\$111,000.00
2	Retrofit Existing Cells (Piping, etc) Anoxic C1, 2-New. Aer. C1,	650	LF	\$28.00	\$18,200.00
3	Sludge Dredging and Disposal Anoxic C1, 2-New. Aer. C1,	12770	CY	\$15.00	\$191,550.00
4	Impermeable Membrane Liner, existing & new cells Anoxic C1&2, New. Aer. C1&2, Anarobic C1&2	94158	SF	\$1.00	\$94,158.00
5	Aeration Diffusers, Blower Equipment with Sound Attenuation, and Installation	1	LS	\$218,000.00	\$218,000.00
6	Baffle Curtains	1	LS	\$87,350.00	\$87,350.00
7	Cascading Wet Land	1	LS	\$ 507,000.00	\$ 507,000.00
8	Solids Handling Drying Bed				
	Excavation, compaction & debris removal	2378	CY	\$ 15.00	\$ 35,670.00
	Piping -Perf. (Gravity to Packaged Lift Station)	326	LF	\$ 25.00	\$ 8,150.00
	Drain Rock	40	CY	\$ 10.00	\$ 400.00
	Sand @ 6" of depth.	1189	CY	\$ 17.50	\$ 20,807.50
	Geofabric	2048	SF	\$ 1.00	\$ 2,048.00
	Liner	2048	SF	\$ 1.00	\$ 2,048.00
	Concrete to separate Discharge Structures.	40	CY	\$ 400.00	\$ 16,000.00
	Manhole	1	EA	\$ 3,000.00	\$ 3,000.00
	Discharge Structures.	8	EA	\$ 1,500.00	\$ 12,000.00
	4" Pressure Piping within Drying Bed	900	LF	\$ 28.00	\$ 25,200.00
	4" Pressure Piping Out Side Drying Bed	400	LF	\$ 28.00	\$ 11,200.00
	Valves	11	EA	\$ 500.00	\$ 5,500.00
9	Packaged Lift Station Return from Drying Bed (e-one or equal) + Elec.	1	LS	\$5,500.00	\$5,500.00
10	Sludge Collection Sump Pumps Within Anoxic Cells--Low Velocity	1	LS	\$35,000.00	\$35,000.00
	Concrete Sump within Anoxic Cells	1	LS	\$4,000.00	\$4,000.00
	3PH Electrical	1	LS	\$3,000.00	\$3,000.00
	Force Main Piping to Sludge Holding Tank	600	LF	\$28.00	\$16,800.00
	Valves	4	LS	\$500.00	\$2,000.00
11	Sludge Collection Sump Pumps Within Anarobic Cells--Low Velocity	1	LS	\$35,000.00	\$35,000.00
	Concrete Sump within Anarobic Cells	1	LS	\$4,000.00	\$4,000.00
	3 PH Electrical	1	LS	\$3,000.00	\$3,000.00
	Force Main Piping to Sludge Holding Tank	600	LF	\$28.00	\$16,800.00
	Valves	4	LS	\$500.00	\$2,000.00
12	Lift Station Return to Sludge Drying Beds-high velocity flow, Including sludge holding tank	1	LS	\$90,000.00	\$90,000.00
	Force Main Piping to Sludge Drying Beds	600	LF	\$28.00	\$16,800.00
	Valves	2	EA	\$500.00	\$1,000.00
13	Influent Wastewater Screen	1	Each	\$90,000.00	\$90,000.00
14	Return Flow from old Aeration Cell 2 to Cascading Wet Land				
	Retrofit existing pumps to pump to Cascading Wet Land	1	LS	\$50,000.00	\$50,000.00
	Piping	300	FT	\$28.00	\$8,400.00
	Valves	4	EA	\$500.00	\$2,000.00
15	Yard piping-out side lagoons	500	LF	\$35.00	\$17,500.00
	Valves Out side Lagoon	10	Ea	\$500.00	\$5,000.00
16	Access Road	1600	SY	\$12.00	\$19,200.00
17	Fencing	5933	LF	\$12.00	\$71,196.00
18	Extend Power to Site	1	LS	\$10,000.00	\$10,000.00
19	Emergency Power Generator	1	Each	\$42,500.00	\$42,500.00
20	Lab Equipment BOD5, TSS, Fecal, TP	1	LS	\$50,000.00	\$50,000.00
21	Effluent Sampler (Indoor) Sampler: Samples for BOD5, TSS, Fecal, TP	1	QTY		
	Note: The Effluent Sampler Will Auto sample for DO, PH				
	Influent Sampler: Sample for BOD5, TSS,	1	QTY		
	Note: The Influent Sampler Will Auto sample for DO, PH				
	Out Door Heaters for effluent & Influent Sampler	2	QTY		
	Flow Meter (980)	1	QTY		
	Sum:	1	LS		\$15,500.00
22	Main Electrical & Control Pannel & Instrumentation	1	LS	\$80,000.00	\$80,000.00
23	Ultra-Violet Light Disinfection and pH Adjustment	1	LS	\$105,000.00	\$105,000.00
24	Mixer in anarobic Cell	1	LS	\$7,000.00	\$7,000.00
25	Electrical	1	LS	\$3,000.00	\$3,000.00
26	Operations Building- Retrofit Existing	400	SF	\$120.00	\$48,000.00
	Subtotal				\$2,228,477.50
	Sales Tax at 5%				\$111,423.88
	Subtotal				\$2,339,901.38
	Contingencies at 20%				\$467,980.28
	Subtotal				\$2,807,881.65
	Engineering at 20%				\$561,576.33

Interest to fund Engineering, 1 Year at 5%	\$28,078.82
Administrative and Legal	\$110,423.88
Total	\$3,507,960.67
Total - Engineering	\$2,946,384.34

Inflow/Infiltration Removal

Construction Subtotal	\$873,900.00
Sales Tax at 5.0%	\$43,695.00
Land Purchase	\$0.00
Subtotal	\$917,595.00
Contingencies at 10%	\$91,759.50
Subtotal	\$1,009,354.50
Engineering at 20%	\$201,870.90
Interest to fund Engineering, 1 Year at 5%	\$10,093.55
Administrative and Legal	\$42,695.00
Total	\$1,264,013.95
Total-Engineering	\$1,062,143.05

Total Project

Construction Subtotal	\$873,900.00
Sales Tax at 5.0%	\$2,272,172.50
Land Purchase	\$0.00
Subtotal	\$3,257,496.38
Contingencies at 10%, I/I, 20% WWT	\$559,739.78
Subtotal	\$3,817,236.15
Engineering at 20%	\$763,447.23
Interest to fund Engineering, 1 Year at 5%	\$38,172.36
Administrative and Legal	\$153,118.88
Total	\$4,771,974.62
Total-Engineering	\$4,008,527.39

Annual Operations and Maintenance Costs

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Class II Operator - 1	2080	Hours	\$29.00	\$60,320.00
2	Sludge Disposal	1250	CY	\$5.00	\$6,250.00
3	Motor and Pump Maintenance @ 2%	1	LS	\$7,270.00	\$7,270.00
4	Electricity	209600	kWh	\$0.07	\$14,672.00
5	Analytical (BOD5, TSS, Fecal, TP)	1	LS	\$5,000.00	\$5,000.00
6	Miscellaneous Supplies	1	LS	\$2,000.00	\$2,000.00
	Subtotal				\$95,512.00
	Contingencies at 20%				\$19,102.40
	Subtotal				\$114,614.40
	Administrative and Engineering Support@5%				\$5,730.72
	Total				\$120,345.12

Total Present Value

Present Value of Probable Construction Cost	at	4.00% ann. Inflation	\$4,771,974.62
Present Value of Probable Operations and Maintenance Cost	at	4.00% ann. Inflation	\$1,635,529.45
Total			\$6,407,504.07

Option 5 W/ Tribe
City of Plummer, Idaho
WWTP Option 5 W/ Tribe
Aeration in Modified Lagoons-Subsurface Irrigated Dripline
Opinion of Probable Cost

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Mobilization	1	LS	\$133,000.00	\$133,000.00
2	Retrofit Existing Cells (Piping, etc) Anoxic C1, 2-New. Aer. C1,	650	LF	\$28.00	\$18,200.00
3	Sludge Dredging and Disposal Anoxic C1, 2-New. Aer. C1,	12770	CY	\$15.00	\$191,550.00
4	Impermeable Membrane Liner, existing & new cells Anoxic C1&2, New. Aer. C1&2, Anarobic C1&2	94158	SF	\$1.00	\$94,158.00
5	Aeration Diffusers, Blower Equipment with Sound Attenuation, and Installation	1	LS	\$218,000.00	\$218,000.00
6	Baffle Curtains	1	LS	\$87,350.00	\$87,350.00
7	Irrigated Drip	1	LS	\$1,200,000.00	\$1,200,000.00
8	Solids Handling Drying Bed Excavation, compaction & debris removal Piping -Perf. (Gravity to Packaged Lift Station) Drain Rock Sand @ 6" of depth. Geofabric Liner Concrete to separate Discharge Structures. Manhole Discharge Structures. 4" Pressure Piping within Drying Bed 4" Pressure Piping Out Side Drying Bed Valves	2378 326 40 1189 2048 2048 40 1 8 900 400 11	CY LF CY CY SF SF CY EA EA LF LF EA	\$15.00 \$25.00 \$10.00 \$17.50 \$1.00 \$1.00 \$400.00 \$3,000.00 \$1,500.00 \$28.00 \$28.00 \$500.00	\$35,670.00 \$8,150.00 \$400.00 \$20,807.50 \$2,048.00 \$2,048.00 \$18,000.00 \$3,000.00 \$12,000.00 \$25,200.00 \$11,200.00 \$5,500.00
9	Packaged Lift Station Return from Drying Bed (e-one or equal) + Elec.	1	LS	\$5,500.00	\$5,500.00
10	Sludge Collection Sump Pumps Within Anoxic Cells--Low Velocity Concrete Sump within Anoxic Cells 3PH Electrical Force Main Piping to Sludge Holding Tank Valves	1 1 1 600 4	LS LS LS LF LS	\$35,000.00 \$4,000.00 \$3,000.00 \$28.00 \$500.00	\$35,000.00 \$4,000.00 \$3,000.00 \$16,800.00 \$2,000.00
11	Sludge Collection Sump Pumps Within Anarobic Cells--Low Velocity Concrete Sump within Anarobic Cells 3 PH Electrical Force Main Piping to Sludge Holding Tank Valves	1 1 1 600 4	LS LS LS LF LS	\$35,000.00 \$4,000.00 \$3,000.00 \$28.00 \$500.00	\$35,000.00 \$4,000.00 \$3,000.00 \$16,800.00 \$2,000.00
12	Lift Station Return to Sludge Drying Beds-high velocity flow, Including sludge holding tank Force Main Piping to Sludge Drying Beds Valves	1 600 2	LS LF EA	\$90,000.00 \$28.00 \$500.00	\$90,000.00 \$16,800.00 \$1,000.00
13	Influent Wastewater Screen	1	Each	\$90,000.00	\$90,000.00
14	Return Flow from old Aeration Cell 2 to Irigation Drip Retrofit existing pumps to pump to Cascading Wet Land Piping Valves	1 300 4	LS FT EA	\$50,000.00 \$28.00 \$500.00	\$50,000.00 \$8,400.00 \$2,000.00
15	Yard piping-out side lagoons Valves Out side Lagoon	500 10	LF Ea	\$35.00 \$500.00	\$17,500.00 \$5,000.00
16	Access Road	1600	SY	\$12.00	\$19,200.00
17	Fencing	2200	LF	\$12.00	\$26,400.00
18	Extend Power to Site	1	LS	\$10,000.00	\$10,000.00
19	Emergency Power Generator	1	Each	\$42,500.00	\$42,500.00
20	Lab Equipment BOD5, TSS, Fecal, TP	1	LS	\$50,000.00	\$50,000.00
21	Effluent Sampler (Indoor) Sampler: Samples for BOD5, TSS, Fecal, TP Note: The Effluent Sampler Will Auto sample for DO, PH Influent Sampler: Sample for BOD5, TSS, Note: The Influent Sampler Will Auto sample for DO, PH Out Door Heaters for effluent & Influent Sampler Flow Meter (980) Sum:	1 1 2 1 1	QTY QTY QTY QTY LS		\$15,500.00
22	Main Electrical & Control Pannel & Instrumentation	1	LS	\$80,000.00	\$80,000.00
23	Mixer in anarobic Cell	1	LS	\$7,000.00	\$7,000.00
24	Electrical	1	LS	\$3,000.00	\$3,000.00
25	Operations Building- Retrofit Existing	400	SF	\$120.00	\$48,000.00
Subtotal					\$2,793,681.50
Sales Tax at 5%					\$139,684.08
Land Purchase for irrigation area					\$230,000.00
Subtotal					\$3,163,365.58
Contingencies at 20%					\$632,673.12
Subtotal					\$3,796,038.69

Engineering at 20%	\$759,207.74
Interest to fund Engineering, 1 Year at 5%	\$37,960.39
Administrative and Legal	\$138,684.08
Total	\$4,731,890.89
Total - Engineering	\$3,972,683.15

Inflow/Infiltration Removal

Construction Subtotal	\$873,900.00
Sales Tax at 5.0%	\$43,695.00
Land Purchase	\$0.00
Subtotal	\$917,595.00
Contingencies at 10%	\$91,759.50
Subtotal	\$1,009,354.50
Engineering at 20%	\$201,870.90
Interest to fund Engineering, 1 Year at 5%	\$10,093.55
Administrative and Legal	\$42,695.00
Total	\$1,264,013.95
Total-Engineering	\$1,062,143.05

Total Project

Construction Subtotal	\$3,667,581.50
Sales Tax at 5.0%	\$183,379.08
Land Purchase	\$230,000.00
Subtotal	\$4,080,960.58
Contingencies at 10%, I/I, 20% WWT	\$724,432.62
Subtotal	\$4,805,393.19
Engineering at 20%	\$961,078.64
Interest to fund Engineering, 1 Year at 5%	\$48,053.93
Administrative and Legal	\$181,379.08
Total	\$5,995,904.83
Total-Engineering	\$5,034,826.20

Annual Operations and Maintenance Costs

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Class II Operator - 1	2080	Hours	\$29.00	\$60,320.00
2	Sludge Disposal	1250	CY	\$5.00	\$6,250.00
3	Motor and Pump Maintenance @ 2%	1	LS	\$7,270.00	\$7,270.00
4	Electricity	209600	kWh	\$0.07	\$14,672.00
5	Analytical (BOD5, TSS, Fecal, TP)	1	LS	\$5,000.00	\$5,000.00
6	Miscellaneous Supplies	1	LS	\$2,000.00	\$2,000.00
	Subtotal				\$95,512.00
	Contingencies at 20%				\$19,102.40
	Subtotal				\$114,614.40
	Administrative and Engineering Support@5%				\$5,730.72
	Total				\$120,345.12

Total Present Value

Present Value of Probable Construction Cost	at	4.00% ann. inflation	\$5,995,904.83
Present Value of Probable Operations and Maintenance Cost	at	4.00% ann. inflation	\$1,635,529.45
Total			\$7,631,434.29

Table 6 W/ Tribe
City of Plummer, Idaho
WWTP Option 6 W/ Tribe
Package Biological Treatment with Extended Aeration and Activated Sludge-Mechanical Package Plant (Drip Irrigation)
Opinion of Probable Cost

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Mobilization	1	LS	\$195,000.00	\$195,000.00
3	Site Work	1	LS	\$40,000.00	\$40,000.00
4	Preparation Earthwork On Site	5000	CY	\$10.00	\$50,000.00
5	Haul & Place Crush Material	3000	CY	\$20.00	\$60,000.00
6	Mechanical Influent Wastewater Bar Screen	1	LS	\$90,000.00	\$90,000.00
7	Electrical	1	LS	\$3,000.00	\$3,000.00
8	Influent Lift Station, Including Generator & Controls.	1	LS	\$120,000.00	\$120,000.00
	Electrical	1	LS	\$3,000.00	\$3,000.00
9	Piping From Lift Station to Mechanical Building	500	LF	\$28.00	\$14,000.00
10	Gravity Piping to Existing Cell #2 for Equalization	400	LF	\$28.00	\$11,200.00
11	Equalization Basin-Excavation, Compaction & Backfill	9680	CY	\$10.00	\$96,800.00
12	Equalization Basin-Liner	459000	SF	\$1.00	\$459,000.00
13	Equalization Basin - Piping	200	LF	\$28.00	\$5,600.00
14	Equalization Basin Valving	4	EA	\$500.00	\$2,000.00
15	Sludge Dredging and Disposal Of Existing Cell 1 Aeration & Cell 2 Aeration	12404	CY	\$15.00	\$186,060.00
16	Return Flow from equalization basin to Mechanical Package Plant				
	Retrofit existing pumps	1	LS	\$50,000.00	\$50,000.00
	Piping	300	FT	\$28.00	\$8,400.00
	Valves	4	EA	\$500.00	\$2,000.00
17	Mechanical Package Plant	1	LS	\$815,400.00	\$815,400.00
	Anoxic Tank				
	Aerobic Tank				
	Anaerobic Tank				
	Aerobic Tank				
	Clarifier Tank				
	Aerobic Digester				
22	Drip Line	1	LS	\$1,200,000.00	\$1,200,000.00
23	Solids Handling Drying Bed				
	Excavation, compaction & debris removal	2378	CY	\$ 15.00	\$ 35,670.00
	Piping -Perf. (Gravity to Packaged Lift Station)	326	LF	\$ 25.00	\$ 8,150.00
	Drain Rock	40	CY	\$ 10.00	\$ 400.00
	Sand @ 6" of depth.	1189	CY	\$ 17.50	\$ 20,807.50
	Geofabric	2048	SF	\$ 1.00	\$ 2,048.00
	Liner	2048	SF	\$ 1.00	\$ 2,048.00
	Concrete to separate Discharge Structures.	40	CY	\$ 400.00	\$ 16,000.00
	Manhole	1	EA	\$ 3,000.00	\$ 3,000.00
	Discharge Structures.	8	EA	\$ 1,500.00	\$ 12,000.00
	4" Pressure Piping within Drying Bed	900	LF	\$ 28.00	\$ 25,200.00
	4" Pressure Piping Out Side Drying Bed	400	LF	\$ 28.00	\$ 11,200.00
	Valves	11	EA	\$ 500.00	\$ 5,500.00
24	Packaged Lift Station Return from Drying Bed (e-one or equal) + Elec. To M	1	LS	\$5,500.00	\$5,500.00
25	Yard Piping from Mechanical Building to Sludge Drying Beds	200	FT	\$28.00	\$5,600.00
26	Fencing	2000	LF	\$15.00	\$30,000.00
27	Extend Power to Site	1	LS	\$10,000.00	\$10,000.00
28	Electrical and Instrumentation Controls	1	LS	\$40,000.00	\$40,000.00
29	Mechanical Package Plant Building	2500	SF	\$120.00	\$300,000.00
30	Pilot Study	1	LS	\$60,000.00	\$60,000.00
31	Lab Equipment BOD5, TSS, Fecal, TP	1	LS	\$50,000.00	\$50,000.00
32	Effluent Sampler (Indoor) Sampler: Samples for BOD5, TSS, Fecal, TP	1	QTY		
	Note: The Effluent Sampler Will Auto sample for DO, PH				
	Influent Sampler: Sample for BOD5, TSS,	1	QTY		
	Note: The Influent Sampler Will Auto sample for DO, PH				
	Out Door Heaters for effluent & Influent Sampler	2	QTY		
	Flow Meter (980)	1	QTY		
	Sum:	1	LS		\$15,500.00
33	Power & Electrical for influent, effluent & indoor sampler	1	LS	\$10,000.00	\$10,000.00
	Subtotal				\$4,080,083.50
	Sales Tax at 5.0%				\$204,004.18
	Land Purchase for Mechanical Treatment Plant				\$30,000.00
	Land Purchase for Irrigation Equalization (23 Acres)				\$230,000.00
	Subtotal				\$4,314,087.68
	Contingencies at 20%				\$862,817.54

Subtotal	\$5,176,905.21
Engineering at 20%	\$1,035,381.04
Interest to fund Engineering, 1 Year at 5%	\$51,769.05
Administrative and Legal	\$203,004.18
Total	\$6,467,059.48
Total-Engineering	\$5,431,678.44

Inflow/Infiltration Removal

Construction Subtotal	\$873,900.00
Sales Tax at 5.0%	\$43,695.00
Land Purchase	\$0.00
Subtotal	\$917,595.00
Contingencies at 10%	\$91,759.50
Subtotal	\$1,009,354.50
Engineering at 20%	\$201,870.90
Interest to fund Engineering, 1 Year at 5%	\$10,093.55
Administrative and Legal	\$42,895.00
Total	\$1,264,013.95
Total-Engineering	\$1,062,143.05

Total Project

Construction Subtotal	\$4,953,983.50
Sales Tax at 5.0%	\$247,699.18
Land Purchase	\$260,000.00
Subtotal	\$5,231,682.68
Contingencies at 10%, I/I, 20% WWT	\$954,577.04
Subtotal	\$6,186,259.71
Engineering at 20%	\$1,237,251.94
Interest to fund Engineering, 1 Year at 5%	\$61,862.60
Administrative and Legal	\$245,699.18
Total	\$7,731,073.42
Total-Engineering	\$6,493,821.48

Annual Operations and Maintenance Costs

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Class II Operator - 1/2 FTE	1040	Hours	\$29.00	\$30,160.00
2	Sludge Disposal	1250	CY	\$5.00	\$6,250.00
3	Motor and Pump Maintenance @ 2%	1	LS	\$4,310.00	\$4,310.00
4	Electricity	209600	kWh	\$0.07	\$14,672.00
5	Analytical (BOD5, TSS, Fecal, TP)	1	LS	\$3,500.00	\$3,500.00
6	Replacement UV	50	Each	\$20.00	\$1,000.00
7	Miscellaneous Supplies	1	LS	\$4,000.00	\$4,000.00
	Subtotal				\$63,892.00
	Contingencies at 20%				\$12,778.40
	Subtotal				\$76,670.40
	Administrative and Engineering Support@5%				\$3,833.52
	Total				\$80,503.92

Total Present Value

Present Value of Probable Construction Cost	at	4.00% ann. Inflation	\$7,731,073.42
Present Value of Probable Operations and Maintenance Cost	at	4.00% ann. Inflation	\$1,094,074.54
Total			\$8,825,147.97

Table 7 W/ Tribe
City of Plummer, Idaho
WWTP Option 7 W/ Tribe
Package Biological Treatment with Extended Aeration and Activated Sludge--Cascading Overland
Opinion of Probable Cost

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Mobilization	1	LS	\$133,000.00	\$133,000.00
2	Site Work	1	LS	\$40,000.00	\$40,000.00
3	Preparation Earthwork On Site	5000	CY	\$10.00	\$50,000.00
4	Haul & Place Crush Material	3000	CY	\$20.00	\$60,000.00
5	Mechanical Influent Wastewater Bar Screen	1	LS	\$90,000.00	\$90,000.00
6	Electrical	1	LS	\$3,000.00	\$3,000.00
7	Influent Lift Station, Including Generator & Controls.	1	LS	\$120,000.00	\$120,000.00
	Electrical	1	LS	\$3,000.00	\$3,000.00
8	Piping From Lift Station to Mechanical Building	500	LF	\$28.00	\$14,000.00
9	Mechanical Package Plant	1	LS	\$815,400.00	\$815,400.00
	Anoxic Tank				
	Aerobic Tank				
	Anaerobic Tank				
	Aerobic Tank				
	Clarifier Tank				
	Aerobic Digester				
10	Cascading Wet Land	1	LS	\$507,000.00	\$507,000.00
11	Solids Handling Drying Bed				
	Excavation, compaction & debris removal	2378	CY	\$ 15.00	\$ 35,670.00
	Piping -Perf. (Gravity to Packaged Lift Station)	326	LF	\$ 25.00	\$ 8,150.00
	Drain Rock	40	CY	\$ 10.00	\$ 400.00
	Sand @ 6" of depth.	1189	CY	\$ 17.50	\$ 20,807.50
	Geofabric	2048	SF	\$ 1.00	\$ 2,048.00
	Liner	2048	SF	\$ 1.00	\$ 2,048.00
	Concrete to separate Discharge Structures.	40	CY	\$ 400.00	\$ 16,000.00
	Manhole	1	EA	\$ 3,000.00	\$ 3,000.00
	Discharge Structures.	8	EA	\$ 1,500.00	\$ 12,000.00
	4" Pressure Piping within Drying Bed	900	LF	\$ 28.00	\$ 25,200.00
	4" Pressure Piping Out Side Drying Bed	400	LF	\$ 28.00	\$ 11,200.00
	Valves	11	EA	\$ 500.00	\$ 5,500.00
12	Packaged Lift Station Return from Drying Bed (e-one or equal) +	1	LS	\$5,500.00	\$5,500.00
13	Yard Piping from Mechanical Building to Sludge Drying Beds	200	FT	\$28.00	\$5,600.00
14	Fencing	5733	LF	\$15.00	\$85,995.00
15	Extend Power to Site	1	LS	\$10,000.00	\$10,000.00
16	Electrical and Instrumentation Controls	1	LS	\$40,000.00	\$40,000.00
17	Mechanical Package Plant Building	2500	SF	\$120.00	\$300,000.00
18	Pilot Study	1	LS	\$60,000.00	\$60,000.00
19	Lab Equipment BOD5, TSS, Fecal, TP	1	LS	\$50,000.00	\$50,000.00
20	Ultra-Violet Light Disinfection and pH Adjustment	1	LS	\$105,000.00	\$105,000.00
21	Effluent Sampler (Indoor) Sampler: Samples for BOD5, TSS, Fec	1	QTY		
	Note: The Effluent Sampler Will Auto sample for DO, PH				
	Influent Sampler: Sample for BOD5, TSS,	1	QTY		
	Note: The Influent Sampler Will Auto sample for DO, PH				
	Out Door Heaters for effluent & Influent Sampler	2	QTY		
	Flow Meter (980)	1	QTY		
	Sum:	1	LS		\$15,500.00
22	Power & Electrical for influent, effluent & indoor sampler	1	LS	\$10,000.00	\$10,000.00
	Subtotal				\$2,665,018.50
	Sales Tax at 5.0%				\$133,250.93
	Land Purchase for Mechanical Treatment Plant				\$30,000.00
	Subtotal				\$2,828,269.43
	Contingencies at 20%				\$565,653.89
	Subtotal				\$3,393,923.31
	Engineering at 20%				\$678,784.66
	Interest to fund Engineering, 1 Year at 5%				\$33,939.23
	Administrative and Legal				\$132,250.93
	Total				\$4,238,898.13
	Total-Engineering				\$3,560,113.47

Inflow/Infiltration Removal

Construction Subtotal	\$873,900.00
Sales Tax at 5.0%	\$43,695.00
Land Purchase	\$0.00
Subtotal	\$917,595.00
Contingencies at 10%	\$91,759.50
Subtotal	\$1,009,354.50
Engineering at 20%	\$201,870.90
Interest to fund Engineering, 1 Year at 5%	\$10,093.55
Administrative and Legal	\$42,695.00
Total	\$1,264,013.95
Total-Engineering	\$1,062,143.05

Total Project

Construction Subtotal	\$3,538,918.50
Sales Tax at 5.0%	\$176,945.93
Land Purchase	\$30,000.00
Subtotal	\$3,745,864.43
Contingencies at 10%, I/I, 20% WWT	\$657,413.39
Subtotal	\$4,403,277.81
Engineering at 20%	\$880,655.56
Interest to fund Engineering, 1 Year at 5%	\$44,032.78
Administrative and Legal	\$174,945.93
Total	\$5,502,912.08
Total-Engineering	\$4,622,256.51

Annual Operations and Maintenance Costs

No.	Description	Qty	Units	Unit Cost	Opinion of Probable Cost
1	Class II Operator - 1/2 FTE	1040	Hours	\$29.00	\$30,160.00
2	Sludge Disposal	1250	CY	\$5.00	\$6,250.00
3	Motor and Pump Maintenance @ 2%	1	LS	\$4,310.00	\$4,310.00
4	Electricity	209600	kWh	\$0.07	\$14,672.00
5	Analytical (BOD5, TSS, Fecal, TP)	1	LS	\$3,500.00	\$3,500.00
6	Replacement UV	50	Each	\$20.00	\$1,000.00
7	Miscellaneous Supplies	1	LS	\$4,000.00	\$4,000.00
	Subtotal				\$63,892.00
	Contingencies at 10%				\$6,389.20
	Subtotal				\$70,281.20
	Administrative and Engineering Support@5%				\$3,514.06
	Existing O&M on Collection System				\$0.00
	Total				\$73,795.26

Total Present Value

Present Value of Probable Construction Cost	at	4.00% ann. Inflation	\$5,502,912.08
Present Value of Probable Operations and Maintenance Cost	at	4.00% ann. Inflation	\$1,002,901.67
Total			\$6,505,813.74

APPENDIX VII

1982 NPDES Permit

U.S. ENVIRONMENTAL PROTECTION AGENCY

REGION X

1200 SIXTH AVENUE
SEATTLE, WASHINGTON 98101



REPLY TO
ATTN OF: Mail Stop 521

CERTIFIED MAIL - RETURN RECEIPT REQUESTED

AUG 31 1982

Honorable Harold Whitley
Mayor of Plummer
P.O. Box B
Plummer, Idaho 83851

Re: Administrative Modification of NPDES Permit No.: ID-002278-1

Dear Mayor Whitley:

It has been brought to our attention that some minor corrections are needed in the permit which we recently issued for your sewage treatment plant discharge to clarify the wording in the effluent limitations. Consequently, we have made these changes in your permit.

Attached are copies of the modified pages of your permit covering the changes.

Sincerely,

Robert S. Burd
Director, Water Division

Enclosures

cc: Idaho Operations Office
Idaho Department of Health and Welfare
Idaho Department of Health and Welfare, Coeur d'Alene Field Office



U.S. ENVIRONMENTAL PROTECTION AGENCY

REGION X

1200 SIXTH AVENUE
SEATTLE, WASHINGTON 98101

REPLY TO: Mail Stop 521
ATTN OF:

CERTIFIED MAIL - RETURN RECEIPT REQUESTED

AUG 18 1982

Honorable Harold Whitley
Mayor of Plummer
P.O. Box B
Plummer, Idaho 83851

Re: Reissuance of NPDES Permit No.: ID-002278-1

Dear Mayor Whitley:

The Environmental Protection Agency (EPA) has made the determination to reissue a National Pollutant Discharge Elimination System (NPDES) permit covering the discharge from your sewage treatment facility. This permit incorporates effluent limitations which must be complied with to satisfy the secondary waste treatment requirements and State of Idaho water quality standards.

Attached is your official copy of the reissued permit which demonstrates that your facility is duly authorized to discharge into Lake Chatcolet via Plummer Creek subject to certain specified requirements.

Since there were no comments received during the public notice period, the new permit is effective as of this date.

Sincerely,

Robert S. Burd
Director, Water Division

Enclosure

cc: Idaho Operations Office
Idaho Dept. of Health & Welfare
Idaho Dept. of Health & Welfare, Coeur d'Alene Field Office

Permit No.: ID-002278-1

Application No.: ID-002278-1

AUTHORIZATION TO DISCHARGE UNDER THE
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM

In compliance with the provisions of the Federal Water Pollution Control Act, as amended, (33 U.S.C. §1251 et seq; the "Act"),

City of Plummer

is authorized to discharge from a facility located in Plummer, Idaho to receiving waters named Lake Chatcolet via Plummer Creek in accordance with discharge point(s), effluent limitations, monitoring requirements and other conditions set forth herein.

This permit shall become effective August 18, 1982.


This permit and the authorization to discharge shall expire at midnight, August 17, 1987.

Signed this 18th day of August 1982.



Director, Water Division - Region X
U.S. Environmental Protection Agency

This permit administratively modified effective this 31st day of August 1982.



Director, Water Division - Region X
U.S. Environmental Protection Agency

I.A. EFFLUENT LIMITATIONS, MONITORING REQUIREMENTS AND COMPLIANCE SCHEDULE

1. Effluent Limitations - December through April

During the period beginning on the effective date of this permit and lasting until the expiration date, discharges from outfalls shall be limited and monitored by the permittee as specified below:

a. The monthly average quantity of effluent discharged from the wastewater treatment facility shall not exceed 380 cmd (0.10 mgd).

b. The pH shall not be less than 6.5 nor greater than 9.0.

c. There shall be no discharge of floating solids or visible foam other than in trace amounts.

d. The following limitations and monitoring requirements shall apply:

<u>Effluent Characteristics</u>	<u>Unit of Measurement</u>	<u>Monthly Average</u>	<u>Weekly Average</u>
<u>Effluent Concentrations</u>			
Biochemical Oxygen Demand (5-day)	mg/l	30	45
Suspended Solids	mg/l	30	45
Fecal Coliform Bacteria	No./100 ml	100	200
<u>Effluent Loadings</u>			
Biochemical Oxygen Demand (5-day)	kg/day (lb/day)	12(26)	18(39)
Suspended Solids	kg/day (lb/day)	12(26)	18(39)
<u>Monitoring Requirements</u>	<u>Unit of Measurement</u>	<u>Sampling Frequency</u>	<u>Type of Sample</u>
Total Flow	cmd (mgd)	5/week	Grab
Biochemical Oxygen Demand (5-day)	mg/l	Monthly	Grab
Suspended Solids	mg/l	Monthly	Grab
pH	pH Units	Weekly	Grab
Fecal Coliform Bacteria	No./100 ml	Monthly	Grab

85% Removal: The monthly average effluent concentrations shall not exceed 15% of the monthly average influent concentrations for Biochemical Oxygen Demand (5-day) (BOD₅) and Suspended Solids (SS) collected at approximately the same times during the same period (85% removal).

Influent BOD₅ and SS samples shall be monitored according to the effluent monitoring requirements for these parameters and at approximately the same times during the same period.

The percent BOD₅ and SS removal shall be reported on each monthly Discharge Monitoring Report form.

2. Effluent Limitations - May through November

During the period beginning on the effective date of this permit and lasting until the expiration date, no discharges from outfalls are allowed between May 1 and November 30, inclusive.

I.B. MONITORING AND REPORTING REQUIREMENTS

1. Representative Sampling

Samples and measurements taken as required shall be representative of the volume and nature of the monitored discharge. The permittee shall take samples and measurements to meet the monitoring requirements specified. Samples shall be taken in the effluent stream before its discharge to the receiving water, at the specific locations identified in Part A of this permit.

2. Reporting

a. Discharge Monitoring Reports

Monitoring results shall be summarized each month on a Discharge Monitoring Report Form (EPA No. 3320-1). These reports for the previous month shall be submitted monthly and are to be postmarked by the 10th day of the month following the end of the reporting period. Duplicate signed copies of these, and all other reports, shall be submitted to the Director, Water Division and the State agency at the following addresses:

United States Environmental Protection Agency
Region 10
1200 Sixth Avenue
Seattle, Washington 98101

Attn: Water Compliance Section M/S 513

State of Idaho
Department of Health and Welfare
Division of Environment
Statehouse
Boise, Idaho 83720

3. Definitions

a. The "monthly average", other than for fecal coliform bacteria, is the arithmetic mean of samples collected during a calendar month. The monthly average for fecal coliform bacteria is the geometric mean of samples collected during a calendar month.

b. The "weekly average", other than for fecal coliform bacteria, is the arithmetic mean of samples collected during a calendar week. The weekly average for fecal coliform bacteria is the geometric mean of samples collected during a calendar week.

II. GENERAL REQUIREMENTS

A. Duty to Comply

1. The permittee must comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the Clean Water Act and is grounds for enforcement action; for permit termination, revocation and reissuance, or modification; or for denial of a permit renewal application. The permittee shall also comply with any effluent standards or prohibitions established under Section 307(a) of the Clean Water Act for toxic pollutants within the time provided in the regulations that establish these standards or prohibitions, even if the permit has not yet been modified to incorporate the requirement.

2. The Clean Water Act provides that any person who violates a permit condition implementing Sections 301, 302, 306, 307, 308, 318, or 405 of the Clean Water Act is subject to a civil penalty not to exceed \$10,000 per day of such violation. Any person who willfully or negligently violates permit conditions implementing Sections 301, 302, 306, 307, or 308 of the Clean Water Act is subject to a fine of not less than \$2,500 nor more than \$25,000 per day of violation, or by imprisonment for not more than 1 year, or both.

B. Duty to Reapply

If the permittee wishes to continue an activity regulated by this permit after the expiration date of this permit, the permittee must apply for and obtain a new permit. Application must be made at least 180 days prior to the expiration date of this permit.

C. Need to Halt or Reduce Activity not a Defense

It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this permit. Upon reduction, loss or failure of the treatment facility, the permittee shall, to the extent necessary to maintain compliance with its permit, control production or all discharges or both until the facility is restored or an alternative method of treatment is provided. This requirement applies, for example, when the primary source of power of the treatment facility fails or is reduced or lost.

D. Duty to Mitigate

The permittee shall take all reasonable steps to minimize or correct any adverse impact on the environment resulting from noncompliance with this permit.

E. Duty to Provide Information

The permittee shall furnish to the Director, within a reasonable time, any information which the Director may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this permit, or to determine compliance with this permit. The permittee shall also furnish to the Director, upon request, copies of records required to be kept by this permit.

F. Inspection and Entry

The permittee shall allow the Director, or an authorized representative, upon the presentation of credentials and other documents as may be required by law to:

1. Enter upon the permittee's premises where a regulated facility or activity is located or conducted, or where records must be kept under the conditions of this permit;
2. Have access to and copy, at reasonable times, any records that must be kept under the conditions of this permit;
3. Inspect at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this permit; and
4. Sample or monitor at reasonable times, for the purposes of assuring permit compliance or as otherwise authorized by the Clean Water Act, any substances or parameters at any location.

G. Monitoring and Records

1. Samples taken in compliance with the monitoring requirements established under Part I shall be collected from the effluent stream prior to discharge into the receiving waters. Samples and measurements shall be representative of the volume and nature of the monitored discharge.

2. Monitoring must be conducted according to test procedures approved under 40 CFR Part 136, unless other test procedures have been specified in this permit.

3. The Clean Water Act provides that any person who falsifies, tampers with or knowingly renders inaccurate any monitoring device or method required to be maintained under this permit shall, upon conviction, be punished by a fine of not more than \$10,000 per violation, or by imprisonment for not more than 6 months per violation, or by both.

4. The permittee shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by this permit, and records of all data used to complete the application for this permit, for a period of at least 3 years from the date of the sample, measurement, report or application. This period may be extended by request of the Director at any time.

5. Records of monitoring information shall include:

- a. The date, exact place, and time of sampling or measurements;
- b. The individual(s) who performed the sampling or measurements;
- c. The date(s) analyses were performed;
- d. The individual(s) who performed the analyses;
- e. The analytical techniques or methods used; and
- f. The results of such analyses.

H. Reporting Requirements

1. Discharge Monitoring Reports

a. Monitoring results shall be summarized each month on a Discharge Monitoring Report form (DMR; EPA No. 3320-1). The reports shall be submitted monthly and are to be postmarked by the 10th day of

the following month. Duplicate copies of these, and all other reports herein, shall be signed and certified in accordance with the requirements of I., Signatory Requirements, and submitted to the Director, Water Division and the State agency at the following addresses:

United States Environmental Protection Agency
Region 10
1200 Sixth Avenue
Seattle, WA 98101

Attn: Water Compliance Section, Mail Stop 513

State of Idaho
Department of Health and Welfare
Division of Environment
Statehouse
Boise, ID 83720

b. Additional monitoring. If the permittee monitors any pollutant more frequently than required by the permit, using test procedures approved under 40 CFR 136, the results of such monitoring shall be included in the calculation and reporting of the data submitted in the DMR.

2. Noncompliance Reporting

a. The permittee shall report any noncompliance which may endanger health or the environment. Any information shall be provided orally within 24 hours from the time the permittee becomes aware of the circumstances. A written submission shall also be provided within 5 days of the time the permittee becomes aware of the circumstances. The written submission shall contain:

- (i) A description of the noncompliance and its cause;
- (ii) The period of noncompliance, including exact dates and times;
- (iii) The estimated time noncompliance is expected to continue if it has not been corrected; and

(iv) Steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance.

b. The following occurrences must be reported under paragraph a above:

(i) Any unanticipated bypass which exceeds any effluent limitation in the permit. (See Section K below).

(ii) Any upset which exceeds any effluent limitation in the permit. (See Section L below)

(iii) Violation of a maximum daily discharge limitation for any of the pollutants listed by the Director in the permit to be reported within 24 hours.

c. Anticipated noncompliance. The permittee shall give advance notice to the Director of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements.

d. Other noncompliance. The permittee shall report all instances of noncompliance not reported under paragraphs 1., a., b. and c. of this section, at the time monitoring reports are submitted. The reports shall contain the information listed in paragraph a. of this section.

3. Planned Changes. The permittee shall give notice to the Director as soon as possible of any planned physical alterations or additions to the permitted facility.

4. Notice of New Introduction of Pollutants. The permittee shall provide adequate notice to the Director, Water Division of:

a. Any new introduction of pollutants into the treatment works from an indirect discharger which would be subject to Sections 301 or 306 of the Act if it were directly discharging those pollutants; and

b. Any substantial change in the volume or character of pollutants being introduced into the treatment works by a source introducing pollutants into the treatment works at the time of issuance of the permit.

Adequate notice shall include information on:

(i) The quality and quantity of effluent to be introduced into such treatment works; and

(ii) Any anticipated impact of the change on the quantity or quality of effluent to be discharged from such publicly owned treatment works.

5. Other Information. When the permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in a permit application or any report to the Director, it shall promptly submit such facts or information.

6. Availability of Reports. Except for data determined to be confidential under Section 308 of the Clean Water Act, all reports prepared in accordance with the terms of this permit shall be available for public inspection at the office of the state water pollution control agency and the Director, Water Division. As required by the Act, effluent data shall not be considered confidential.

I. Signatory Requirements

1. Applications. All permit applications shall be signed by either a principal executive officer or ranking elected official.

2. Reports. All reports required by this permit and other information requested by the Director shall be signed by a person described in paragraph 1. of this section, or by a duly authorized representative of that person. A person is a duly authorized representative only if:

a. The authorization is made in writing by a person described in paragraph 1. of this section;

b. The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity, such as the position of plant manager, superintendent, or position of equivalent responsibility. (A duly authorized representative may thus be either a named individual or any individual occupying a named position.); and

c. The written authorization is submitted to the Director.

3. Changes to authorization. If an authorization under paragraph 2. of this section is no longer accurate because a different individual or position has responsibility for the overall operation of the facility, a new authorization satisfying the requirements of paragraph 2. of this section must be submitted to the Director prior to or together with any reports, information or applications to be signed by an authorized representative.

4. Certification. Any person signing a document under paragraphs 1. or 2. of this section shall make the following certification:

"I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment."

5. The Clean Water Act provides that any person who knowingly makes any false statement, representation, or certification in any record or other document submitted or required to be maintained under this permit, including monitoring reports or reports of compliance or noncompliance shall, upon conviction, be punished by a fine of not more than \$10,000 per violation, or by imprisonment for not more than 6 months per violation, or by both.

J. Proper Operation and Maintenance

The permittee shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the permittee to achieve compliance with the conditions of this permit. Proper operation and maintenance include effective performance, adequate funding, adequate operator staffing and training, and adequate laboratory and process controls, including appropriate quality assurance procedures.

K. Bypass

1. Definitions:

a. "Bypass" means the intentional diversion of waste streams from any portion of a treatment facility.

b. "Severe property damage" means substantial physical damage to property, damage to the treatment facilities which causes them to become inoperable, or substantial and permanent loss of natural resources which can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production.

2. Bypass not exceeding limitations. The permittee may allow any bypass to occur which does not cause effluent limitations to be exceeded, but only if it also is for essential maintenance to assure efficient operation. These bypasses are not subject to the provisions of paragraphs 3 and 4 which immediately follow.

3. Notification:

a. Anticipated bypass. If the permittee knows in advance of the need for a bypass, he shall submit prior notice, if possible at least 10 days before the date of the bypass.

b. Unanticipated bypass. The permittee shall submit notice of an unanticipated bypass within 24 hours of becoming aware of the circumstances as required under H.2 above.

4. Prohibition of bypass. Bypass is prohibited, and the Director may take enforcement action against a permittee for bypass, unless:

a. Bypass was unavoidable to prevent loss of life, personal injury, or severe property damage;

b. There were no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime. This condition is not satisfied if the permittee could have installed adequate backup equipment to prevent a bypass which occurred during normal periods of equipment downtime or preventive maintenance; and

c. The permittee submitted notices as required under paragraph 3. a above, and the bypass has been approved by the Director.

L. Upset

1. Definition: "Upset" means an exceptional incident in which there is unintentional and temporary noncompliance with technology based permit effluent limitations because of factors beyond the reasonable control of the permittee. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.

2. Effect of an Upset. An upset constitutes an affirmative defense to an action brought for noncompliance with technology-based permit effluent limitations if the requirements of paragraph 3 below are met. No determination made during administrative review of claims that noncompliance was caused by upset, and before an action for noncompliance, is final administrative action subject to judicial review.

3. Conditions necessary for a demonstration of upset. A permittee who wishes to establish the affirmative defense of upset shall demonstrate, through properly signed, contemporaneous operating logs, or other relevant evidence that:

a. An upset occurred and that the permittee can identify the specific cause(s) of the upset;

b. The permitted facility was at the time being properly operated; and

c. The permittee submitted notice of the upset as required under H.2 above.

d. The permittee complied with any remedial measures required under D. "Duty to Mitigate."

4. Burden of Proof. In any enforcement proceeding the permittee seeking to establish the occurrence of an upset has the burden of proof.

M. Control of Undesirable Pollutants

Under no circumstances shall the permittee allow introduction of the following wastes into the waste treatment system:

1. Wastes which will create a fire or explosion identify the specific cause(s) of the upset;
2. Wastes which will cause corrosive structural damage to treatment works, but in no case wastes with a pH lower than 5.0, unless the works is designed to accommodate such wastes.
3. Solid or viscous substances in amounts which cause obstructions to the flow in sewers, or interference with the proper operation of the treatment works.
4. Wastewaters at a flow rate and/or pollutant discharge rate which is excessive over relatively short time periods so that there is a treatment process upset and subsequent loss of treatment efficiency.
5. Any pollutant, including oxygen demanding pollutants (BOD, et.) released in a discharge of such volume or strength as to cause interference in the treatment works.

N. Requirements for Industrial Users

The permittee shall require any industrial user of these treatment works to comply with any applicable requirements of Sections 204(b), 307, and 308 of the Act, including any requirements established under 40 CFR Part 403.

O. Removed Substances

Collected screenings, grit, sludges, and other solids removed in the course of treatment or control of wastewaters shall be disposed of in a manner so as to prevent entry of those wastes or runoff from such materials into navigable waters unless otherwise authorized in this permit.

P. Permit Actions

This permit may be modified, revoked and reissued, or terminated for cause. The filing of a request by the permittee for a permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance, does not stay any permit condition.

Q. Property Rights

This permit does not convey any property rights of any sort, or any exclusive privilege.

R. Severability

The provisions of this permit are severable, and if any provision of this permit, or the application of any provision of this permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of this permit shall not be affected thereby.

S. State Laws

Nothing in this permit shall be construed to preclude the institution of any legal action or relieve the permittee from any responsibilities, liabilities, or penalties established pursuant to any applicable state law or regulation under authority preserved by Section 510 of the Clean Water Act.

APPENDIX VIII

2002 WLAP Permit



STATE OF IDAHO
DEPARTMENT OF
ENVIRONMENTAL QUALITY

2110 Ironwood Parkway • Coeur d'Alene, Idaho 83814-2648 • (208) 769-1422

Dirk Kempthorne, Governor
C. Stephen Allred, Director

April 30, 2002

CERTIFIED RETURN RECEIPT 7000 1670 0005 6151 4755

The Honorable Jack Bringman
Mayor, City of Plummer
P.O. Box B
Plummer, ID 83851

RE: Draft Wastewater Land Application Permit (WLAP) for the City of Plummer (#000004-02)

Dear Mayor Bringman:

Enclosed please find a copy for you and for presentation to the members of the City Council of the draft Wastewater Land Application Permit that this office prepared as the result of a permit application submitted by the city in 1996. This permit is required by the Idaho Wastewater Land Application Permit Regulations when treated wastewater is applied to the land for treatment and disposal. With your receipt of the draft 13-page permit, the city has thirty (30) days to review and comment back to DEQ with anything in the draft permit that the city feels deserves modification, revision, or changing. Also enclosed is a copy of the 6-page staff analysis prepared to provide supporting documentation for the draft permit.

Please pay special attention to the Section G on page 6 of the draft permit. This section contains specific actions and compliance dates for the city to address system deficiencies. DEQ wants the city to determine whether any residence west of the irrigation field is too close and might have a well at risk. We want the city to immediately install three shallow piezometers at the low end of the irrigation field to monitor for saturated conditions. And we want the city to take steps to study and upgrade the wastewater disinfection system which has shown significant non-compliance with the bacteria standard from the previous permit and non-compliance with the current bacteria standards for wastewater systems with land application close to public access. It is important that the city understand these items and feels you can reasonably comply with the dates specified for each item.

Once you have provided DEQ with comments on the draft permit, we will resolve and/or incorporate your comments into the permit and then issue a new and final five-year WLAP for the Plummer wastewater system. We recommend that the city ask your engineering consultant to also review and comment to DEQ on the draft permit. **Prior to May 31, 2002, we will expect to receive comments on the draft permit from the city.** Please respond in writing to DEQ whether you have or do not have any comments.

Sincerely,

Gary J. Gaffney
Gary J. Gaffney, P.E.

Enclosure (Draft WLAP and Staff Analysis)

c: Jeffrey Logan, Wyatt Engineering, Inc., 1220 North Howard, Inc., Spokane, WA (w/enc)
Donna Spier, City Clerk, City of Plummer, P.O. Box B, Plummer, ID 83851



STATE OF IDAHO
DEPARTMENT OF
ENVIRONMENTAL QUALITY

2110 Ironwood Parkway • Coeur d'Alene, Idaho 83814-2648 • (208) 769-1422

Dirk Kempthorne, Governor
C. Stephen Allred, Director

April 30, 2002

MEMORANDUM

TO: Roger Tinkey, Regional Manager, Coeur d'Alene Regional Office
John Tindall, Coeur d'Alene Regional Office
Richard Huddleston, State Water Quality Office, Boise State Office

FROM: Gary Gaffney *GG*

SUBJECT: Draft Staff Analysis for the City of Plummer Wastewater Land Application Permit,
LA-000004- 02 (Municipal Wastewater)

PURPOSE

The purpose of this memorandum is to satisfy the requirements of IDAPA 58.01.17.700 for issuing wastewater-land application permits.

SUMMARY OF EVENTS

In 1989, the City of Plummer was issued a five-year Wastewater Land Application Permit (WLAP) when the Wastewater Land Application Permit Regulations were first adopted. The initial WLAPs were issued to existing facilities and allowed the city to continue with irrigation of treated wastewater as had been done since the practice was started in 1982. In 1996, the city applied for renewal of their WLAP and a draft permit was sent on August 6, 1996 by DEQ to the city for comments. No comments were received on the draft permit. However, DEQ failed to issue the new permit at that time. The current WLAP is comparable to the 1997 draft but has been modified to be more relevant to the current operation. The operator has been submitting and DEQ-CdA has been reviewing and commenting on annual reports since 1996.

It is time to have this facility operating with a valid permit.

PROCESS DESCRIPTION

The City of Plummer operates a municipal wastewater treatment facility about one mile east of Highway 95 along Plummer Creek. The City presently serves a population of 990 consisting of approximately 400 sewer connections. In 1980 when the facility last underwent significant upgrading, the design capacity of the treatment facility was for a population of 700 with a 20-year design population of 1300. The treatment facility consists of gravity collection of whole sewage with delivery through a communitor to two surface-aerated lagoon cells with capacities of 5.7 million gallons (MG) and 3.9 MG. Wastewater from the second lagoon cell is disinfected with gas chlorine and delivered to a small contact lagoon. From the contact lagoon, wastewater is either pumped to the spray irrigation field or siphon dosed onto two intermittent sand filters with underdrains discharging to Plummer Creek per an existing but presently expired NPDES permit.

The NPDES permit only allows discharge to the creek from December 1 to May 1 while the old WLAP allows irrigation from June 1 to September 31st. During the months of November and May, neither discharge to Plummer

**SUBJECT: Staff Analysis for the City of Plummer Wastewater Land Application Permit,
LA-000004- 02 (Municipal Wastewater)**

April 30, 2002

Page 2

Creek or irrigation of the wastewater is allowed. This has caused the city problems in the past especially during wet years with high precipitation when the two aerated lagoons do not have sufficient capacity to hold the wastewater throughout the months of November or May. In these instances the city has discharged to Plummer Creek rather than overflow the lagoons.

The wastewater treatment system was last upgraded in 1981. In recent years, the City has undertaken a number of projects intended to improve the sewage collection system and reduce excessive inflow and infiltration (I/I) impacts. Excessive I/I has been identified by engineering reports as a major deficiency in this sewer system adversely affecting the treatment system performance. Reduction of excessive I/I has also been determined as the most cost-effective way to provide additional capacity in the system. In 2001, the city imposed a moratorium on construction requiring new sewer hookups and secured funding for a \$350,000 project aimed at improving the sewage collection system.

DESCRIPTION OF WASTEWATER TREATMENT AND LAND APPLICATION SYSTEM

The irrigation property is a 30-acre city owned property about 2000 feet north of the treatment plant along a gravel county road. The property is fenced and is about ½ mile (2,616 feet) long by 500 feet wide and was equipped with a buried irrigation distribution system onto which individual sprinkler risers are attached. The land has been used for wastewater land application and has been farmed by individuals under contract with the city for oats and for hay crops during the past 20 years. A twenty-five (25) foot buffer zone was originally established in 1980 between the irrigation area and the road right-of-way. There is one small residence located across the county road from the property probably using an individual well and on-site septic tank and drainfield. Otherwise, there are no other homes or businesses within close proximity of the irrigation field.

The city grew alfalfa on the irrigation site for many years after the land application was started in the early 1980s. In recent years, the city has contracted with a local farmer to grow oats on the field. The farmer prepares the site, plants the seed, and harvests the crop. Cenex sprays for weeds on the crop. The city sells the crop and pays the farmer based a flat fee for his services. In 2001, 64,680 pounds of oats were harvested from the 27 acre site, netting the city \$2737 for the oats and, when compared to expenses of \$1617, resulted in a profit to the city of \$1543 including a \$423 in Dept. of Agriculture conservation payment.

The parcel is of gently rolling topography typical of the Palouse area. A timbered parcel and seasonally wet low area is located adjacent to the southern boundary. This area has been reported as being wet in the spring and is being equipped with three shallow piezometers that the operator will have to monitor. If these monitoring pipes have ground water within 36-inches of the surface, the permit prohibits the operator from land applying the wastewater until the area dries.

The force main from the two 50 Hp, 530-660 gpm capacity irrigation pumps located in the operations building next to the lagoons is a 10-inch diameter ductile iron line up to the field. At the irrigation field this line changes to an 8-inch PVC pipe off of which twenty-six (26) 4-inch diameter lateral lines at 100-foot spacings are installed. The irrigation laterals are all individually valved have sprinkler heads at 101-foot spacings.

SUBJECT: Staff Analysis for the City of Plummer Wastewater Land Application Permit,
LA-000004- 02 (Municipal Wastewater)

April 30, 2002

Page 3

SITE CHARACTERISTICS

Other agricultural fields surround the irrigation field and there is no evidence of nearby drinking water wells with the exception of the well serving the residence west of the property. There is little information about local geology or ground water conditions in the area of this field. The general landform in this area exhibits fine grained and relatively deep soils with lengthy time of travel to the ground water and low ground water recharge rates. The low permeability of the silt loam soils and irrigation application rate approximating the consumptive use of the crops suggests that ground water recharge from the wastewater land application system is minimal. Without a significant ground water mapping effort, it would be difficult to design an effective ground water monitoring system and might not be worth the effort because of the low infiltration rates associated with the soils.

PROJECTED WASTEWATER QUALITY AND LOADING RATES

WASTEWATER QUANTITY and QUALITY

Based on 2001 flow of 37.075 MG and 990 users, the average per capita wastewater flow is 103 gpd and the average daily flow is 101,575 gpd, which is within range of the system's design criteria. The following table shows the wastewater quality results from the Annual Report for the 2001 year:

Constituent/ Date	BOD (mg/l)	Suspended Solids (mg/l)	Total Coliform (Organisms/100ml)	Fecal Coliform (Organisms/100ml)
June, 2001	16	26	No Sample	300, 30, 80, 900
July, 2001	17	61	>1600, >1600, 220	50
August, 2001	28	76	1600, 80	4
September, 2001	No Sample	No Sample	No Sample	No Sample
October, 2001	10	52	>1600, 1600, >1600	No Sample
Design Goal	10-25	15-25	23 or 230	NA

As can be seen from the above table, the treatment levels were not consistently below the goals established by the system design but are close enough to suggest that land application of the wastewater does not pose a high risk to contaminating ground water. However, the failure of the system to meet the disinfection standard and the need to bring the system into compliance with a higher disinfection standard, makes upgrading the disinfection system at this facility a condition of the new WLAP.

With the new WLAP, only total coliform will be considered relevant when considering compliance with the disinfection standard. Although the irrigation site does not meet the current 230 guidelines for buffer zones of 300 feet from the edge of the irrigation field to public access and 1000 feet to inhabited dwellings but it is fenced and posted.

SUBJECT: Staff Analysis for the City of Plummer Wastewater Land Application Permit,
LA-000004- 02 (Municipal Wastewater)

April 30, 2002

Page 4

The permit will contain compliance items requiring the city to upgrade in a two year period the disinfection system to meet the 23/100 ml standard consistent with current guidance for a site close to a public road. This will involve an engineer studying the existing disinfection system and submitting plans and specifications for recommended improvements during the first year. The second year is given for the city to implement the improvements and achieve the required disinfection level.

With the new permit, it is proposed that the city substitute COD for BOD sampling, eliminate the suspended solids monitoring, and start sampling the wastewater for nitrogen and phosphorous concentrations. Permit limits for COD at the guidance level and for nitrogen and phosphorous at the uptake rate for the oat or grass hay crop were assigned. All of the three parameters when sampled in the city wastewater prior to land application are expected to be well below the guidance value and the crop uptake values.

HYDRAULIC LOADING RATES

The wastewater application period for this installation will be within the May 1st to October 31st period (184 days) based on the irrigated crop requirements for water. Wastewater land application will not be allowed when the ground is frozen or when shallow piezometers located at the low section of the field have water present any closer than three feet below ground surface (bgs). Wastewater land application during November 1st to April 30th will not be allowed.

The wastewater application rate for this site was established based on application of the guidance in the standard WLAP permit. This uses mean irrigation water requirements from consumptive use data from Tensed (Allen and Brockway 1983) for spring grain. No application is allowed during April because the site is typically not dry enough to irrigate until May. This determination assigned a 75% irrigation efficiency which resulted in 22.4-inch annual application rate between May and August. This will allow the city to apply up to 16.4 MGA on the 27 acres. The permit does not allow irrigation during September or October because the grain crop is harvested in early September. The city will need to determine whether they must irrigate during these two months in order to store wastewater until discharge to Plummer Creek is permitted.

The permit prohibits spray irrigating if there is ground water present in any of the three shall piezometers. This will prevent the city from land applying on saturated soils or contributing to site runoff due to saturated soils. Slow permeability of the silt loam soils will reduce the application rates even further and prevent the practice from approaching rates where ground water impacts might be suspected.

CONSTITUENT LOADING RATES

Constituent loading rates for COD shall conform to the guidelines shown in the *State of Idaho Handbook for Land Application of Municipal and Industrial Wastewater (Handbook)*. N loading rate shall be limited to crop uptake values and P loading shall be limited to the recommended 18% of the Total N uptake.

GROUND WATER CONSIDERATIONS

The land application site is in an agricultural area without any public water supply wells within 1000 feet. One non-public well may be supplying a nearby residence but there is no information pertaining to the depth and quality of water from this water well. The permit will require the city to submit a well log (if available) and nitrate and coliform bacteria sample results from this well and to resample the well for the same parameters during the third

SUBJECT: Staff Analysis for the City of Plummer Wastewater Land Application Permit,
LA-000004- 02 (Municipal Wastewater)

April 30, 2002

Page 5

year of the five-year permit. Since ground water is not readily available in significant quantities, when found is commonly found at over 200 foot depths, and is overlaid with fine-grained material with a long travel time and low permeability, the risk to the ground water by this facility does not justify the installation of a ground water monitoring system.

The flow data in the last six annual reports (1995 to present) submitted by the city and in the below table show that the average annual collected wastewater has decreased from a maximum of 67.6 MG in 1997 to a low in 2001 of 37.1 MG. This may be attributed to efforts by the city to reconstruct the sewage collection system. The volume of wastewater land applied during these six years has been in the 11 to 13 MG range except in 1997 when 35.4 Mg was reported as being land applied for some unspecified reason. It is unlikely that the growth in the city during the next five year permit period will increase the volume needing land application much past the 13 to 15 MG amount. Any attempt to eliminate the NPDES discharge from Plummer Creek will require major study and funding of additional lagoon storage facilities and purchase of additional irrigation property. A permit revision would be needed in such a case.

Plummer Wastewater Flows

<u>Year</u>	<u>Lagoon Influent</u>	<u>NPDES Discharge</u>	<u>Land Applied Wastewater</u>	<u>Lagoon Effluent</u>	<u>Unaccounted Wastewater</u>	<u>Unaccounted/ Influent</u>
1996	43.1	28.3	12.5	40.8	2.3	5%
1997	67.6	30.5	35.4	65.9	1.7	2.5%
1998	58.7	25.0	14.5	39.5	19.2	32.7%
1999	42.5	17.7	13.1	30.8	11.7	27%
2000	40.7	17.1	13.3	30.4	10.3	25%
2001	37.1	21.1	11.3	32.4	4.7	12%

The possibility of the two lagoons leaking more than the 1/8th-inch per day standard is suggested because the lagoons are sealed using native clay and there has been unaccounted for annual wastewater volumes of 1.7 to 19.2 MGA. However, since the unaccounted for wastewater volume is not consistent and dropped significantly in 2001 to below the volume allowed by the 1/8th-inch per day standard, staff does not recommend seepage testing of the lagoons as part of the permitting process. If and when the city undertakes upgrading of the wastewater treatment plant now being proposed and likely to occur within 5 to 10 years, DEQ will require that the project includes installation of a liner in each of the lagoons.

BUFFER ZONES

Recommended buffer zones for a disinfection level of 23 and 230-organisms/100 ml as shown below are contained in the permit to remind the city that their irrigation site needs to be managed to minimize public exposure. The Plummer irrigation site is located 25 feet from a county rural gravel road and within 300 feet from a single residence and it's associated private water source. The property appears to exceed the buffer zone distances from streams and public water sources. Since the facility is not in compliance with the current disinfection buffer

**SUBJECT: Staff Analysis for the City of Plummer Wastewater Land Application Permit,
LA-000004- 02 (Municipal Wastewater)**

April 30, 2002

Page 6

distances, the permit will require the city to upgrade the disinfection system to accomplish disinfection less than 23/100 ml. This is consistent with the location of the irrigation field within 25 feet from a public road.

Any new land application areas being developed by the city will need to comply with the current guidance, which calls for a disinfection level of 23-organisms/100 ml.

Disinfection Level for Total Coliform (TC)*	Distance to Public Access	Distances to Inhabited Dwellings	Distance to streams	Distance to Private water sources	Distance to Public water sources	Single Sample maximum TC
23/100 ml	50 feet	300 feet	50 feet	500	1000	240/100ml
230/100ml	300 feet	1,000 feet	50 feet	500	1000	2400/100ml

SITE SPECIFIC CONDITIONS

- The permit requires the city to install three shallow piezometers on the low end of the irrigation field and to monitor these piezometers for the presence of shallow ground water during the irrigation season and avoid land applying wastewater if there is water within three feet of the ground surface.
- The permit requires the city to submit information on a nearby private drinking water well and to sample the well in 2002 and 2005 for bacteria and nitrate contamination. While it is considered unlikely the city irrigation system has affected ground water and this well, staff feels it is important to sample the well for these two indicator parameters.
- The permit will require the operator to revise his annual reporting format to include new items required by the re-issued WLAP.

RECOMMENDATION: DEQ staff recommends issuance of the attached draft permit. This will provide the city with a current WLAP and upgrade the monitoring requirements to reflect current practices.

cc: WLAP Source File No. LA-000004-02

**MUNICIPAL
WASTEWATER LAND APPLICATION PERMIT
LA-000004-02
City of Plummer**

City of Plummer, P.O. Box B, Plummer, ID 83851, IS HEREBY
AUTHORIZED TO CONSTRUCT, INSTALL AND OPERATE A
WASTEWATER-LAND APPLICATION TREATMENT SYSTEM IN
ACCORDANCE WITH THE WASTEWATER-LAND APPLICATION
RULES (IDAPA 58.01.17), THE WATER QUALITY STANDARDS
AND WASTEWATER TREATMENT REQUIREMENTS (IDAPA
58.01.02), AND THE GROUND WATER QUALITY RULE (IDAPA
58.01.11) AND ACCOMPANYING PERMIT, APPENDICES, AND
REFERENCE DOCUMENTS. THIS PERMIT IS EFFECTIVE FROM
THE DATE OF SIGNATURE AND EXPIRES FIVE YEARS FROM THE
DATE OF SIGNATURE.

Gwen P. Fransen, Regional Administrator
Idaho Department of Environmental Quality

Signed this _____ day of _____, 2002

**DEPARTMENT OF ENVIRONMENTAL QUALITY
2110 IRONWOOD PARKWAY
COEUR D'ALENE IDAHO 83814
(208) 769-1422
(208) 769-1404 FAX**

POSTING ON SITE RECOMMENDED

City of Plummer LA-000004-02	April 30, 2002	Page 1
------------------------------	----------------	--------

DRAFT

B. Permit Contents and Reference Documents

	<u>Page</u>
A. Permit Certificate	1
B. Permit Contents and Reference Documents	2
C. Facility Information	3
D. Site Map	4
E. Environmental Monitoring Serial Numbers	5
F. Reference Documents incorporated into the permit	6
G. Compliance Schedule For Required Activities	6
H. Special Conditions	7
I. Standard Permit Limits and Conditions	7
J. Standard Monitoring Requirements	8
K. Standard Reporting Requirements	9
L. Standard Permit Conditions: Procedures and Reporting	10
M. Standard Permit Conditions: Modifications, Violation, and Revocation	11
Appendix A – Annual Report Outline	12
Appendix B – Piezometer Detail and Locations	13


The Sections, Appendices, and Reference Documents listed on this page are all elements of Wastewater-Land Application Permit and are enforceable as such. This permit does not relieve the permittee from responsibility for compliance with other applicable federal, state or local laws, rules, standards or ordinances.

C. Facility Information

Legal Name of Permittee	City of Plummer
Type of Waste	Municipal wastewater
Method of Treatment	Slow Rate Irrigation on Agricultural Land
Type of Facility	Municipal
Site Acres	27 effective in a 30 acre city owned parcel
Facility Location	Plummer, Idaho
Legal Location	T46N, R4W, Section 8
County	Benewah
USGS Quad	Chatolet
Soils on Site	Taney silt loam (Soil Survey for Benewah County)
Depth to Ground Water	Greater than 100 feet to seasonal high ground water
Beneficial Uses of Ground Water	Agricultural, Drinking water
Nearest affected Surface Water	Plummer Creek, a tributary to Lake Chatolet and Lake Coeur d'Alene
Beneficial Uses of Surface Water	Agriculture
Facility Contact Persons Mailing Address Phone/Fax Number	Mayor, Jack Bringman or Donna Spier, City Clerk David Janson, Operator City of Plummer P.O. Box B Plummer, ID 83851 Phone 208/686-1641

DRAFT

D. Site Map



City of Plummer
Land Application Permit LA-000004

E. Environmental Monitoring Serial Numbers

HYDRAULIC MANAGEMENT UNITS		
Description	Acres	Serial No.
30 Acre Irrigation Field	27	MU-0004-01

WASTEWATER SAMPLING POINTS	
Description	Serial No.
Discharge point of wastewater to land application	WW-0004-01

LAGOONS		
Description	Location	Serial No.
Lagoon 1 – Aerated with 3.9 MG capacity	Plant site	LG-0004-01
Lagoon 2 – Aerated with 5.7 MG capacity	Plant site	LG-0004-02

SOIL MONITORING UNITS		
Description	Associated Hydraulic Unit	Serial No.
Throughout 30 Acre Irrigation Field	MU-0004-01	SU-0004-01

GROUNDWATER MONITORING and PIEZOMETERS		
Description	Location	Serial No.
Three shallow ground water piezometers (See Appendix B)	South boundary of MU- 0004-01	PZ-0004-01 PZ-0004-02 PZ-0004-03

DRAFT

F. Reference Documents incorporated into the Permit

1. As-built plans and specifications for the City of Plummer, Idaho; Water Pollution Control Facilities 1980 – Wastewater Treatment System by H&V Engineering, Inc. dated 9/16/81 (EPA Project No. C-16 0199-02).
2. Operation and Maintenance Manual (August 1981) City of Plummer Water Pollution Control Facilities Wastewater Treatment System by H&V Engineering, Inc.
3. Wastewater – Land Application Permit Program Resource and Training Manual (September 1999). Available from DEQ-Boise.
4. "Estimating Consumptive Irrigation Requirements for Crops in Idaho" published in 1983 by R. G. Allen and C. E. Brockway. A Research Technical Completion Report submitted to Idaho Department of Water Resources.

G. Compliance Schedule For Required Activities

The Activities in the following table shall be completed on or before the Completion Date unless modified by the DEQ in writing.

Compliance Activity Number Completion Date	Compliance Activity Description
CA-00004-01 January 31, 2003	Revise the Annual Report to include Section J Facility Monitoring Schedule requirements. See Appendix A for guidance.
CA-000004-02 January 31, 2003 January 31, 2006	Submit a copy of the Well Driller's Report (Well log) and total coliform bacteria and nitrate sample results for any non-public drinking water well located within 500 feet of the perimeter of the irrigation field. Repeat the total coliform bacteria and nitrate sampling from these same well(s) and submit results with the 2005 Annual Report.
CA-00004-03 August 1, 2002	Install three 6-8-foot deep piezometers at the northern boundary of the WLAP for detection of saturated soil conditions prior to startup of irrigation. Monitor at least monthly for water depths in the three piezometers and report the data in the Annual Reports. See Appendix B for guidance.
CA-00004-04 August 1, 2003	Submit to DEQ an engineering analysis of the wastewater disinfection system and construction plans and specifications for improvements to the disinfection system necessary to consistently achieve a Total Coliform level of less than 23 organisms/100 ml. in land applied wastewater.
CA-00004-05 August 1, 2004	Complete construction of the improvements to the disinfection system necessary to achieve a Total Coliform standard of 23-organisms/100 ml in accordance with CA-00004-04.

H. Special Conditions - None

I. Standard Permit Limits and Conditions

- 1) The Permittee is allowed to apply wastewater and treat it on a land application site as prescribed in the tables below and in accordance with all other applicable permit conditions and schedules.

Category		Permitted Limits and Conditions																														
Type of Wastewater		Municipal Wastewater treated and discharged from the City of Plummer Wastewater Treatment Facility.																														
Application Site Area		Slow Rate Irrigation																														
Application Season and Restrictions		Growing Season only starting on May 1 and ending on October 31 No wastewater land application when piezometers detect groundwater within three feet of the ground surface.																														
Maximum Monthly Hydraulic Loading Rate Guidance		For Grain Crops: <table><tr><td><u>Month</u></td><td><u>Application Rate (inches)</u></td><td><u>Application Volume (MG)</u></td></tr><tr><td>May</td><td>3.17.....</td><td>2.32</td></tr><tr><td>June.....</td><td>7.33.....</td><td>5.37</td></tr><tr><td>July</td><td>10.0.....</td><td>7.34</td></tr><tr><td>August</td><td>1.6.....</td><td>1.17</td></tr><tr><td>September.....</td><td></td><td></td></tr><tr><td>October.....</td><td></td><td></td></tr><tr><td>Total</td><td>22.1</td><td>16.2</td></tr></table> <p>The monthly application rates are based on irrigation of spring grain, a 75% irrigation efficiency, and no irrigation during April. The application volume is based on even application to the 27 irrigated acres where one inch of wastewater is equal to 0.733 million gallons.</p> <p>For other crops, the city must provide for DEQ approval specific application rates and volumes based on irrigation needs of the crop.</p>							<u>Month</u>	<u>Application Rate (inches)</u>	<u>Application Volume (MG)</u>	May	3.17.....	2.32	June.....	7.33.....	5.37	July	10.0.....	7.34	August	1.6.....	1.17	September.....			October.....			Total	22.1	16.2
<u>Month</u>	<u>Application Rate (inches)</u>	<u>Application Volume (MG)</u>																														
May	3.17.....	2.32																														
June.....	7.33.....	5.37																														
July	10.0.....	7.34																														
August	1.6.....	1.17																														
September.....																																
October.....																																
Total	22.1	16.2																														
Ground Water		No application to any areas with saturated soil or standing water at the surface. Ground Water Quality shall be in compliance with Idaho <i>Ground Water Quality Rule</i> IDAPA 58.01.11																														
Grazing		Grazing is not allowed.																														
Allowable crops		Crops grown for direct human consumption are not allowed.																														
Signing		Signs shall be posted and maintained every 500 feet designating the fields as wastewater reuse areas or equivalent.																														
Disinfection Standard		230 org./100ml until August 1, 2004; 23 org./100ml after August 1, 2004																														
COD, N, and P Loadings		Less than 50 lbs./acre/day, 150 lbs./acre, and 27 lbs./acre																														
Recommended Buffer Zone Distances	Disinfection Level for Total Coliform (TC)*	Distance to Public Access	Distances to Inhabited Dwellings	Distance to streams	Distance to Private Water Sources	Distance to public water sources	Single Sample maximum TC																									
	23/100 ml	50 feet	300 feet	50 feet	500	1000	240/100ml																									
	230/100 ml.	300 feet	1,000 feet	50 feet	500	1000	2400/100ml																									

*Compliance determination method for the 230 / 100 ml disinfection level shall involve the median value of the last three (3) results not exceeding 230 / 100 ml. In addition, no single sample value shall exceed 2400 / 100 ml.

J. Standard Monitoring Requirements

- 1) Appropriate analytical methods, as given in the *Handbook for Land Application of Municipal and Industrial Wastewater, April 1996*, or as approved by the Idaho Department of Environmental Quality (hereinafter referred to as DEQ), shall be employed
- 2) The permittee shall monitor and measure parameters as stated in the Facility Monitoring Schedule in this section. Samples shall be collected at times and locations that represent typical environmental and process parameters being monitored.
- 3) Monitoring locations are described in Section E. Environmental Monitoring Serial Numbers.
- 4) Monitoring is required at the frequency shown in the table below if wastewater is applied anytime during the time period shown.

Facility Monitoring Schedule

Frequency	Monitoring Point	Description and Type of Monitoring	Parameters
Monthly	Influent to Treatment Lagoons	Total Volume of Wastewater	Total Gallons received into the Treatment Facility/month
Monthly May through September	Flow meter on Irrigation Pump Discharge.	Total Volume of Wastewater land applied during the month.	Total Gallons & Inches Applied*
July and September	Sampling Tap after Irrigation Pump	Grab sample during irrigation.	Total nitrogen, COD, and total phosphorus
Twice per week when land applying from May through September	Discharge Point of Wastewater to Land Application Field	Grab sample during irrigation.	Total Coliform*** and Free Chlorine Residual
Annually	Irrigation Field	Acres used for land application	Acres
May through September during the first of the month	Three Piezometers	Distance below Ground Surface	Depth to Ground Water or No Water Present
Annually	Irrigation Field	COD, N, and P loading calculations	COD, total nitrogen and total Phosphorus in lbs/acre/year**
Annually	Irrigation Field	Crop Type and Yield	Pounds, Tons, or Bushels
October, 2003 and October, 2006	Irrigation Field	Composite Soil Sample****	Electrical Conductivity, nitrate-nitrogen, ammonium-nitrogen, plant available phosphorous, and pH

* To convert total gallons per month to inches applied on the 27-acre irrigation field, divide the number of gallons by 733,115. For example, 5,000,000 gallons applied in July would equal $(5,000,000/733115) = 6.82$ inches applied.

** To calculate pounds/ acre/year multiply the average concentration in mg/l (for COD, nitrogen, or phosphorous) times the volume of applied wastewater in million gallon (MG) times 8.34 and divide by 27 irrigated acres. For example, if the two nitrogen samples are 30 and 50 mg/l (averaging 40 mg/l) and 15 MG of wastewater was land applied, the nitrogen-loading would be equal to $(40 \times 15 \times 8.34)/27 = 185$ pounds/acre/year.

*** Analysis for both total coliform and fecal coliform counts are acceptable for operating information but only total coliform results can be used to determine permit compliance. Any bacteria sample analyzed for just fecal coliform bacteria will not be considered towards permit compliance.

**** Five (5) soil sample locations shall be selected. Two (2) soil samples shall be collected at each sample location, one at 0-12 inches and the other at 12-24 inches. The soil samples collected at 0-12 inches from each sample location shall be composted. Similarly, all soil samples collected at 12-24 inches shall be composited. This method will yield two samples for analysis, one for 0-12 inches and one for 12-24 inches.

K. Standard Reporting Requirements

1. The permittee shall submit an Annual Wastewater-Land Application Site Performance Report ("Annual Report") prepared, signed, and dated by a competent environmental professional or certified wastewater treatment plant operator no later than January 31 of each year which shall cover the previous year from January 1 through December 31. The Annual Report shall include results for monitoring required in Section E, status of compliance activities, and an interpretive discussion of monitoring data results with particular respect to environmental impacts by the facility. See Appendix A for an outline of Annual Report content.

DRAFT

L. Standard Permit Conditions: Procedures and Reporting

1. The permittee shall at all times properly maintain and operate all structures, systems, and equipment for treatment, operational controls and monitoring, which are installed or used by the permittee to comply with all conditions of the permit or the Wastewater-Land Application Permit Regulations, in conformance with a DEQ approved, current Plan of Operations (Operations and Maintenance Manual) which describes in detail the operation, maintenance, and management of the wastewater treatment system. This Plan of Operations shall be updated as necessary to reflect current operations.

2. Wastewater(s) or recharge waters applied to the land surface must be restricted to the premises of the application site unless permission has been obtained from the DEQ authorizing a discharge into the waters of the State as stated in IDAPA 58.01.02.600.02.

3. Wastewater must not create a public health hazard or nuisance condition as stated in IDAPA 58.01.02.600.03. In order to prevent public health hazards and nuisance conditions the permittee shall:

- a. Apply wastewater as evenly as practicable to the treatment area;
- b. Prevent organic solids (contained in the wastewater) from accumulating on the ground surface to the point where the solids putrefy or support vectors or insects; and
- c. Prevent wastewater from ponding in the fields to the point where the ponded wastewater putrefies or supports vectors or insects.

4. As a result of the land application of wastewater, ground water of the state must not contain contaminants exceeding those values as referenced under IDAPA 58.01.11.200a, b and c of the Ground Water Quality Rule, unless otherwise specified in this permit.

5. The permittee shall:

- a. Manage the wastewater land application treatment site as an agronomic operation where vegetative cover is grown and harvested or grazed to utilize the nutrients and minerals in the wastewater, and,
- b. Not hydraulically overload any particular areas of the wastewater land application treatment site.

6. All waste solids, including dredgings and sludges, shall be utilized or disposed in a manner which will prevent their entry, or the entry of contaminated drainage or leachate therefrom, into the waters of the state such that health hazards and nuisance conditions are not created; and to prevent impacts on designated beneficial uses of the ground water and surface water. The permittee's management of waste solids shall be governed by the terms of the DEQ approved Waste Solids Management Plan, which upon approval shall be an enforceable portion of this permit.

7. If the permittee intends to continue operation of the permitted facility after the expiration of an existing permit, the permittee shall apply for a new permit at least six months prior to the expiration date of the existing permit in accordance with the Waste Water Land Application Permit Regulations and include seepage tests on all lagoons per latest DEQ procedures.

8. The permittee shall allow the Director of the Idaho Department of Environmental Quality or the Director's designee (hereinafter referred to as Director), consistent with Title 39, Chapter 1, Idaho Code, to:

- a. Enter the permitted facility,
- b. Inspect any records that must be kept under the conditions of the permit.
- c. Inspect any facility, equipment, practice, or operation permitted or required by the permit.
- d. Sample or monitor for the purpose of assuring permit compliance, any substance or any parameter at the facility.

9. The permittee shall report to the Director under the circumstances and in the manner specified in this section:

- a. In writing thirty (30) days before any planned physical alteration or addition to the permitted facility or activity if that alteration or addition would result in any significant change in information that was submitted during the permit application process.
- b. In writing thirty (30) days before any anticipated change which would result in non-compliance with any permit condition or these regulations.
- c. Orally within twenty-four (24) hours from the time the permittee became aware of any non-compliance which may endanger the public health or the environment at telephone numbers provided in the permit by the Director (see below)

DEQ Regional Office: see Permit Certification Page
Emergency 24 Hour Number 1-800-632-8000

d. In writing as soon as possible but within five (5) days of the date the permittee knows or should know of any non-compliance unless extended by the DEQ. This report shall contain:

- i. A description of the non-compliance and its cause;
- ii. The period of non-compliance including to the extent possible, times and dates and, if the non-compliance has not been corrected, the anticipated time it is expected to continue; and
- iii. Steps taken or planned to reduce or eliminate reoccurrence of the non-compliance.

e. In writing as soon as possible after the permittee becomes aware of relevant facts not submitted or incorrect information submitted, in a permit application or any report to the Director. Those facts or the correct information shall be included as a part of this report.

10. The permittee shall take all necessary actions to prevent or eliminate any adverse impact on the public health or the environment resulting from permit noncompliance.

11. The permittee shall determine (on an on-going basis) if any noxious weed problems relate to the permitted sites. If problems are present, coordinate with the Idaho Department of Agriculture or the local County authority regarding their requirements for noxious weed control. Also address these control operations in an update to the Operations and Maintenance Manual.

M. Standard Permit Conditions: Modifications, Violations, and Revocations

1. The permittee shall furnish to the Director within reasonable time, any information including copies of records, which may be requested by the Director to determine whether cause exists for modifying, revoking, re-issuing, or terminating the permit, or to determine compliance with the permit or these regulations.
2. Both minor and major modifications may be made to this permit as stated in IDAPA 58.01.17.700.01 and 02 with respect to any conditions stated in this permit upon review and approval of the DEQ.
3. Whenever a facility expansion, production increase or process modification is anticipated which will result in a change in the character of pollutants to be discharged or which will result in a new or increased discharge that will exceed the conditions of this permit, or if it is determined by the DEQ that the terms or conditions of the permit must be modified in order to adequately protect the public health or environment, a request for either major or minor modifications must be submitted together with the reports as described in G. Reporting Requirements, and plans and specifications for the proposed changes. No such facility expansion, production increase or process modification shall be made until plans have been reviewed and approved by the DEQ and a new permit or permit modification has been issued.
4. Permits shall be transferable to a new owner or operator provided that the permittee notifies the Director by requesting a minor modification of the permit before the date of transfer.
5. Any person violating any provision of the Waste Water Land Application Permit Regulations, or any permit or order issued thereunder shall be liable for a civil penalty not to exceed ten thousand dollars (\$10,000) or one thousand dollars (\$1,000) for each day of a continuing violation, whichever is greater. In addition, pursuant to Title 39, Chapter 1, Idaho Code, any willful or negligent violation may constitute a misdemeanor.
6. The Director may revoke a permit if the permittee violates any permit condition or the Wastewater Land Application Permit Regulations.
7. Except in cases of emergency, the Director shall issue a written notice of intent to revoke to the permittee prior to final revocation. Revocation shall become final within twenty (20) days of receipt of the notice by the permittee, unless within that time the permittee request an administrative hearing in writing to the Director.
8. The Director shall notify the permittee in writing of any revocation hearing at least twenty (20) days prior to the date set for such hearing. The hearing shall be conducted in accordance with Title 67, Chapter 52, Idaho Code.
9. If, pursuant to Idaho Code § 67-5247, the Director finds the public health, safety or welfare requires emergency action, the Director shall incorporate findings in support of such action in a written notice of emergency revocation issued to the permittee. Emergency revocation shall be effective upon receipt by the permittee. Thereafter, if requested by the permittee in writing the Director shall provide the permittee a revocation hearing and prior notice thereof. Such hearings shall be conducted in accordance with Title 67, Chapter 52, Idaho Code.
10. The provisions of this permit are severable and if a provision or its application is declared invalid or unenforceable for any reason, that declaration will not affect the validity or enforceability of the remaining provisions.
11. The permittee shall notify the DEQ at least six (6) months prior to permanently removing any permitted land application site from service. Prior to commencing site closure activities, the permittee shall: a) participate in a pre-site closure meeting with the DEQ; b) develop a site closure plan that identifies specific closure or cleanup tasks with scheduled task completion dates in accordance with agreements made at the pre-site closure meeting; and c) submit the completed site closure plan to the DEQ for review and approval within forty-five (45) days of the pre-site closure meeting. The permittee must complete the DEQ approved site closure plan.

DRAFT

Appendix A: Annual Report Checklist

The WLAP LA-00004-02 Annual Report needs to contain (preferably in table form where possible) the following data and information for the calendar year covered by the report:

I. Wastewater Quantity:

- Monthly Treatment Plant Inflow from January to December in total gallons each month and total for the calendar year.
- Irrigation Application Volumes from May through October in total gallons each day and total for each month, the number of days each month used for irrigation, and total irrigation volume for the season.
- Monthly Discharge Volume from NPDES Discharge Monitoring Reports from January to the end of April and during December in gallons per month and total gallons for the calendar year.
- A wastewater inventory showing the volume of wastewater received at the facility, the amount land applied and discharged to Plummer Creek, and the estimated change in storage volume in the lagoons during the calendar year. Precipitation volumes per month from the Tensed weather station can be included.

II. Wastewater Quality:

- Wastewater sample results for COD, total N and Total P taken during each of the months of July and September.
- Calculation of the annual COD, Total N, and Total P loading rates per acre for the irrigation season.
- A table of the Total Coliform bacteria results and free chlorine measurements taken from the irrigation wastewater prior to application at least twice per month during the irrigation season months of May through October.

III. Crop Production:

- All results of water depth measurements from the three piezometers taken on the first of the months of May through October or as necessary to determine acceptable dry conditions (36-inches minimum) for irrigation practices to proceed.
- Identification of the acres used during the season for crop irrigation, the type of crop produced, the yield from the harvest, and the period of time during the irrigation season.
- A description of the cropping plan for the next growing season identifying the crop to be grown and the farmer contracted or hired by the city to manage the operation.

IV. Compliance Activities:

- In the Year 2002 Annual Report included Total Coliform, Nitrate, and a well log for the private well near the WLAP site.
- In the 2002 and 2003 Annual Reports, a summary of disinfection system improvements.
- In the year 2005 Annual Report include Total Coliform and Nitrate sampling results for any private wells sampled previously.

V. Certification:

- Signature and dating of the Annual Report by the system operator, the person who prepared the report and the Mayor of Plummer.

APPENDIX IX

2002 EPA Compliance Order



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 10
1200 Sixth Avenue
Seattle, WA 98101

AUG 20 2002

Reply To
Attn Of: OW-133

CERTIFIED MAIL - RETURN RECEIPT REQUESTED



Brian West, Council President
City of Plummer
P.O. Box B
Plummer, Idaho 83851

Re: Request for Information and Modified Compliance Order
Docket No. CWA-10-2002-0024

Dear Mr. West:

Enclosed is a Request for Information and Modified Compliance Order ("Modified Compliance Order") issued to the City of Plummer ("City") pursuant to Section 309(a) of the Clean Water Act, 33 U.S.C. §§ 1318 and 1319(a). EPA has adjusted the schedule in the Modified Compliance Order consistent with the information Wyatt Engineering, Inc. submitted on behalf of the City to EPA in a letter dated July 25, 2002.

Questions concerning these actions may be addressed to Robert Grandinetti at (206) 553-1283, or Cara Steiner-Riley, Assistant Regional Counsel, at (206) 553-1142.

Sincerely,

Randall F. Smith
Director
Office of Water

Enclosure

cc: Gwen Fransen, Regional Administrator, IDEQ - Coeur d'Alene

1
2 UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

3 REGION 10
4
5

6 In the matter of:

7 City of Plummer
8 Plummer, Idaho,

9 Respondent.
10
11

) Docket No. CWA-10-2002-0024
)
)

) REQUEST FOR INFORMATION
) AND MODIFIED COMPLIANCE ORDER
)

12 The following FINDINGS AND CONCLUSIONS are made and this REQUEST FOR
13 INFORMATION AND MODIFIED COMPLIANCE ORDER ("Modified Compliance Order") is issued
14 pursuant to the authority vested in the Administrator of the United States Environmental Protection
15 Agency ("EPA") by Sections 308 and 309 of the Clean Water Act ("Act"), 33 U.S.C. §§ 1318 and 1319.
16 This authority has been delegated to the Regional Administrator, EPA Region 10, and has been duly
17 redelegated to the undersigned Director, Office of Water, EPA Region 10.
18

19 **I. STATUTORY AUTHORITY AND FACTUAL BACKGROUND**

20 1. Section 402 of the Act, 33 U.S.C. § 1342, provides that EPA may issue National
21 Pollutant Discharge Elimination System ("NPDES") permits for the discharge of any pollutant into
22 waters of the United States upon such specific terms and conditions as EPA may prescribe.

23 2. Section 301(a) of the Act, 33 U.S.C. § 1311(a), prohibits the discharge of any
24 pollutant by any person except as authorized by an NPDES permit or other specified statutory
25 sections.

26 3. City of Plummer ("Respondent") owns and operates a domestic wastewater treatment
27 facility ("Facility") in Plummer, Idaho.

28 4. Respondent is a "person" within the meaning of Section 502(5) of the Act,

1 33 U.S.C. § 1362(5).

2 5. Respondent is authorized to discharge pollutants from the Facility under NPDES
3 Permit No. ID-002278-1 ("Permit"). The Permit became effective on August 18, 1982, expired on
4 August 18, 1987, and is currently administratively extended.

5 6. The Permit specifies the conditions under which the Respondent may discharge
6 treated effluent from the Facility.

7 7. The Facility, which was under Respondent's control at all times relevant to this action,
8 discharged "pollutants," within the meaning of Section 502(6) and (12) of the Act, 33 U.S.C.
9 § 1362(6) and (12), from a "point source," within the meaning of Section 502(14) of the Act, 33
10 U.S.C. § 1362(14). Respondent discharged pollutants to Plummer Creek which is "waters of the
11 United States," as defined in section 502(7) of the Act, 33 U.S.C. § 1362(7).

12 8. During the period from January 1998 to May 2001, the Facility exceeded the Permit's
13 effluent limits for Biological Oxygen Demand ("BOD"), Total Suspended Solids ("TSS"), pH, BOD
14 percent removal, and Suspended Solids ("SS") percent removal as detailed in Attachment A to this
15 Modified Compliance Order.

16 9. Respondent submitted a work plan to EPA on July 31, 2001, and sent addenda on
17 November 27, 2001 and February 26, 2002. The work plan and addenda detailed the work
18 Respondent intended to perform to come into compliance with Respondent's Permit including
19 replacing and repairing the Facility's collection system and constructing a new treatment facility.

20 10. EPA issued a Request for Information and Compliance Order to Respondent on April
21 26, 2002 alleging violations of Section 402(a) of the Act, 33 U.S.C. § 1342(a) and Section 301 of the
22 Act, 33 U.S.C. § 1311(a). EPA ordered Respondent to come into compliance with the effluent limits
23 specified in its Permit by January 1, 2004 by completing construction of the new treatment facility.

24 11. Wyatt Engineering, Inc., on behalf of Respondent, submitted new information to EPA
25 in a letter dated July 25, 2002. The letter explained that Respondent would complete construction of
26 its new treatment facility on January 1, 2007. Accordingly, EPA is modifying the original Request
27 for Information and Compliance Order to reflect the new schedule.

II. ORDER

12. Based upon the foregoing FINDINGS, and pursuant to Sections 308 and 309 of the Act, 33 U.S.C. §§ 1318 and 1319, it is hereby ORDERED as follows:

13. Respondent shall eliminate inflow and infiltration into the collection system by December 31, 2004.

14. Respondent shall complete construction of its new treatment facility by January 1, 2007.

15. Respondent shall provide an annual report by December 31 each year this Modified Compliance Order is in effect detailing Respondent's compliance with the schedule set forth above.

16. In the event that the Respondent is unable to comply with any requirement of this Modified Compliance Order, Respondent shall, within ten (10) days of becoming aware of such inability, provide the following:

a. A summary of the specific reasons why Respondent is unable to comply with the requirement;

b. A summary of all actions taken by Respondent or others that Respondent allege demonstrate "good faith efforts" to comply with the requirement; and

c. The date by which Respondent expects to comply with the requirement.

17. Submittals required by this Request for Information and Modified Compliance Order shall be sent to:

U.S. Environmental Protection Agency
Region 10
1200 Sixth Avenue, OW-133
Seattle, Washington 98101
Attn: Robert Grandinetti

18. Pursuant to 40 C.F.R. §§ 2.201 - 2.311, Respondent may assert a business confidentiality claim covering any portion of the submitted information which is entitled to confidential treatment and which is not effluent data. For any such claim, describe the basis for the claim under the applicable regulation. Any material for which business confidentiality is claimed should be placed in a separate envelope labeled, "Confidential Business Information." Failure to assert a claim in the manner described in 40 C.F.R. § 2.203(b) allows EPA to release the submitted

1 information to the public without further notice. EPA may disclose information subject to the
2 business confidentiality claim only to the extent set forth in the above-cited regulations. Special
3 rules governing information obtained under the Act appear in 40 C.F.R. § 2.302.

4 19. Nothing in this Modified Compliance Order shall be construed to relieve Respondent
5 of the requirement to obtain and comply with any NPDES permit or other applicable requirements of
6 other federal, state, or local law. EPA reserves the right to take enforcement action as authorized by
7 law for any violation of this Modified Compliance Order, and for any future or past violation of any
8 permit or other applicable legal requirement.

9 **III. SANCTIONS**

10 20. Notice is hereby given that violation of, or failure to comply with, any of the
11 provisions of the foregoing Modified Compliance Order may subject Respondent to (1) civil
12 penalties of up to \$27,500 per day for each violation, pursuant to Section 309(d) of the Act, 33
13 U.S.C. § 1319(d); (2) civil action in federal court for injunctive relief, pursuant to Section 309(b) of
14 the Act, 33 U.S.S. § 1319(b); or (3) administrative penalties of up to \$11,000 per day for each
15 violation, pursuant to Section 309(g) of the Act, 33 U.S.C. § 1319(g).

16
17 Date this day 28 of August, 2002

18
19 Tim Henne for
20 Randall F. Smith
21 Director
22 Office of Water
23
24
25
26
27
28

ATTACHMENT A

Date of DMR	Outfall Number	Permitted Parameter ¹	Permit Limit	Actual Discharge	Unit
Jan 98	001B	TSS	26	38.5	lb/day
Feb 98	001B	pH (daily maximum)	6.5	6.2	su
Feb 98	001B	BOD	85	77	% removal
Feb 98	001B	SS	85	70	% removal
Mar 98	001B	BOD	26	28	lb/day
Mar 98	001B	TSS	30	47	mg/l
Mar 98	001B	BOD	85	24	% removal
Mar 98	001B	SS	85	38	% removal
May 98	001B	BOD	85	68	% removal
May 98	001B	SS	85	68	% removal
Dec 98	001B	pH (daily maximum)	6.5	6.35	su
Dec 98	001B	TSS	26	29.5	lb/day
Dec 98	001B	TSS	30	31	mg/l
Dec 98	001B	SS	85	76.8	% removal
Jan 99	001B	BOD	85	82	% removal
Jan 99	001B	SS	85	79	% removal
Feb 99	001B	BOD	85	77	% removal
Feb 99	001B	SS	85	63	% removal
Mar 99	001B	BOD	85	58	% removal
Mar 99	001B	SS	85	56	% removal
Apr 99	001B	TSS	26	29	lb/day
Apr 99	001B	BOD	85	67.7	% removal
Apr 99	001B	SS	85	64.8	% removal
May 00	001B	SS	85	71	% removal

¹ Those not specified as daily maximums are monthly averages.

10/24

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28

May 00	001B	SS	85	81	% removal
Feb 01	001B	SS	85	78	% removal
Mar 01	001B	BOD	26	37.98	lb/day
Mar 01	001B	TSS	26	55.24	lb/day
Mar 01	001B	TSS	30	32	mg/l
Mar 01	001B	BOD	85	56	% removal
Mar 01	001B	SS	85	44	% removal
May 01	001B	SS	85	84.5	% removal

21/34

APPENDIX X

Selected Correspondence



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 10
1200 Sixth Avenue
Seattle, Washington 98101

MAR 05 1999

Reply To
Attn Of: OW-133

CERTIFIED MAIL - RETURN RECEIPT REQUESTED

2ND EPA WARNING LETTER

A.F. Booth, Plant Supervisor
City of Plummer
P.O. Box B
Plummer, Idaho 83851


Dear Mr. Booth:

On April 28, 1998, the U.S. Environmental Protection Agency (EPA) issued your facility a warning letter for violations of the Clean Water Act as result of your facility's noncompliance with its National Pollutant Discharge Elimination System (NPDES) permit (ID0022781). Since that warning letter, EPA has documented additional violations of the permit. The enclosed attachment provides the details of the violations.

Please be advised that continued violation may result in a formal enforcement action which may include monetary penalties. Clean Water Act violations can be subject to penalties of up to \$27,500 per day for each violation. In such an event, in determining the appropriate penalty, EPA may consider all past violations including those listed in the attachment.

We urge your facility to take immediate corrective measures to ensure full compliance with its NPDES permit as well as all other applicable federal, state, and local requirements. Should you have any comments or questions regarding this letter, please contact Armina Nolan, or Robert Grandinetti, Compliance Officer's by phone at (206) 553-0530, or (206) 553-1283 respectively, or at the address above.

Sincerely,


Leroy S. Loiselle, Manager
NPDES Compliance Unit

Enclosure

City of Plummer

P.O. BOX 8
PLUMMER, ID 83851
PH. 208-686-1641

May 27, 1999

Mr. Robert Grandinetti
Mail Stop OW-133
US Environmental Protection Agency
1200 Sixth Avenue
Seattle, Washington 98101-1128

RE: Request for Information - NPDES Permit No. ID-002278-1 - City
of Plummer

Dear Mr. Grandinetti,

We are pleased to offer the following response to your letter
request of April 15, 1999:

1. The City has reviewed operation, maintenance, and sample
testing data for the period January 1998 through February 1999
in order to determine probable causes for the violations
listed on your enclosure.

Our review reveals the following:

- a. January 1998 - TSS violation attributable to short
circuiting of sand filters. Excessive flow attributed to
I/I at a time aeration cells were full.
- b. February 1998 - pH was low - no known cause and it has
occurred only one other time. Low percent removal of
BOD5 and TSS is attributed to sand filter short
circuiting.
- c. March 1998 - The violations of BOD5 and TSS are
attributed to excessive I/I which skewed the percent
removals and hydraulically overload the plant causing
higher discharging of BOD and TSS.
- d. May 1998 - Percent removals for BOD5 and TSS were skewed
by low influent values caused by excessive I/I.
- e. December 1998 - The low pH has only occurred one previous
time and the cause is not known. TSS values are only
marginally excessive.
- f. January 1999 - Values were reported as follows:

Eff. BOD5	6 lbs./day	8 ppm
Eff. TSS	9 lbs./day	12 ppm
EFF. Fecal		<2 lbs./100 ml

The lower percent removal of BOD5 and TSS, although
marginal, is attributed to the low value of influent
caused by excessive I/I.

May 27, 1999
Mr. Robert Grandinetti
Page 2

g. February 1999 - Values were reported as follows:

Eff. BOD5	6 lbs./day	7 ppm
Eff. TSS	8 lbs./day	14 ppm
Eff. Fecal		13 lbs./100 ml

The marginally lower percent of removals for BOD5 and TSS are attributable to low influent values caused by excessive I/I.

2. In 1995, the City launched a rehabilitation program to correct some of the system I/I, targeting the oldest section of the system. \$362,500 was spent toward that goal. This amount was sufficient to complete only a portion of identified needs. the 1998/99 budget for the wastewater system O&M is \$111,493 and includes \$30,000 for system improvements.
3. Subsequent flow volumes at the treatment plant have confirmed that additional rehabilitation work will be required on the collection and transportation system. In March of 1999, the Indian Health Services agreed to assist the City with a study to evaluation "the condition and adequacy of the City of Plummer, Idaho, community wastewater collection, treatment, and disposal facilities." That report "identifies major system deficiencies, makes recommendations for corrections and provides alternatives with cost estimates for expansion...for future development..."

That report is expected in three (3) months and will serve to guide future programs for system improvements.

The City is evaluating some modifications to the pipe systems feeding the sand filters in an effort to reduce short circuiting and improve filter efficiency.

As a final attempt to address violations, the City, on May 10, 1999, submitted a proposal to Region 10 EPA Specialist Nickie Arnold in Boise, Idaho, requesting permit modifications to allow flow-based (in the receiving stream, Plummer Creek) discharge with a suggested 10:1 stream to wastewater ratio as an additional management tool for the City's wastewater system. Such a change would not reduce the need or intent to complete the aforementioned activities.

4. The studies to explore piping revisions in the sand filters and the I/I problems are not complete and cost estimating is premature at best.

City of Plummer


P.O. BOX 8
PLUMMER, ID 83851
PH. 208-686-1641

May 27, 1999
Mr. Robert Grandinetti
Page 3

5. The studies should be complete on or about September 1, 1999, after which a timetable can be developed for any improvements.
6. The current permit expired August 17, 1987, and subsequent letters for renewal were last answered March 5, 1993, indicating that EPA was unable to process the application due to a backlog of higher priority requests.

The information contained in this response has been gleaned from City records and is accurate to our best information and belief. We are pleased to submit this information in response to your request and trust you will contact us if anything further is needed.

Sincerely,



Harold Whitley, Mayor
City of Plummer

c: Wyatt Engineering, Inc.



STATE OF IDAHO
DIVISION OF
ENVIRONMENTAL QUALITY

2110 Ironwood Parkway • Coeur d'Alene, Idaho 83814-2648 • (208) 769-1422

February 2, 2000

IC Rob Handlin
Dirk Kempthorne, Governor
C. Stephen Alfred, Administrator

2/17/00

The Honorable Harold Whitley
Mayor, City of Plummer
P.O. Box B
Plummer, ID 83851

RE: 1999 Annual Report, Wastewater Land Application Permit (WLAP) LA-000004-01

Dear Mayor Whitley:

We have reviewed the Annual Report submitted by Albert "Corky" Booth on January 11, 2000 for the wastewater land application system serving the City of Plummer's wastewater treatment system. We would like to offer to you the following observations based on the report:

Infiltration/Inflow: First of all, we noted a dramatic decrease in flow into the treatment facility from 58.7 million gallons (MG) in 1998 to 42.5 MG last year. If this is the result of the recent work by the city to eliminate excessive inflow and infiltration (I/I), then we compliment the city on the success of these efforts.


As suggested by the city's recent work with consultants to continue to study the I/I problem, it appears the city has recognized that additional efforts are needed. Even with the recent flow reduction, the sewage treatment plant, which was designed for a capacity of 100,000 gallons per day (gpd), may be overloaded unless annual flows are kept below 36.5 MG.

DEQ would like to work with the city and your consultants on any proposals to re-construct the city's sewage collection system. DEQ is required by state law to approve plans and specifications for any modifications to your sewer or water systems.

Lagoon Seepage: The discrepancy in 1999 between the 30.8 MG of wastewater land applied (13.1 MG) or discharged to Plummer Creek (17.7 MG) and the 42.5 MG of wastewater received into the treatment lagoons is a concern. We suspect that the 11.7 MG of unaccounted for wastewater may have been lost to seepage out of the lagoon bottom.

Excessive seepage from the lagoons can adversely impact ground water quality. The city utilizes ground water to supply your drinking water system. We suggest that any studies of the city sewer system include an evaluation of lagoon seepage. When the lagoons were upgraded in 1980, they were lined with native material. A membrane liner should be installed if lagoon seepage is found to be excessive.

WLAP: We assume you are operating the land application system per the draft WLAP dated August 1, 1996. For some reason, a final permit was never issued for your facility.



RE: 1999 Annual Report, Wastewater Land Application Permit (WLAP) LA-000004-01
February 2, 2000
Page 2

The disinfection limit in this permit requires less than 230 total coliform organisms / 100 ml. in the applied wastewater. The bacteria reports submitted in the 1999 report indicated total coliform levels in many samples were greater than 1600 organisms/ 100 ml. The operator needs to increase the chlorine dosage or make other modifications to ensure disinfection levels are consistently less than 230 organisms/100 ml.


Crop: The report indicated that the irrigation oat crop was harvested on October 4, 1999 after land application had stopped on September 2, 1999. We shall assume that the purchaser of the oat crop was somehow informed that the oat crop was grown on land irrigated with reclaimed wastewater. If not, please make sure this type of information is provided to future purchasers of the crop harvested from the site.

NPDES: The city's proposal to have the NPDES discharge permit for this facility modified needs to be approved by the US Environmental Protection Agency (EPA). DEQ agrees with the proposal to allow a discharge to Plummer Creek whenever creek flows are in excess of 1.5 cfs and a 10:1 dilution is provided. We suggest that the city continue to request action by EPA in this matter.

Additional Irrigation Land: The need to provide additional land application area for the city has been discussed with DEQ for many years. City efforts to secure additional irrigation land is encouraged by DEQ. Please notify DEQ before you select any additional land for wastewater irrigation so that we can evaluate the suitability of the proposed site for land application and include the area in the WLAP.

Thank you for having this annual report submitted. DEQ will attempt to formally re-issue the city's WLAP during the next few months. In the meanwhile, we would like to be involved with the city and the Indian Health Service, Wyatt Engineering, and Idaho Rural Water Association in efforts to address wastewater system problem in Plummer.

Sincerely,


Gary J. Gaffney, P.E.

- c: Albert Booth, City of Plummer, P.O. Box B, Plummer, ID 83851
Richard Huddleston, DEQ-Boise
Donald Hutson, Indian Health Service, W. 904 Riverside Ave. Rm 408, Spokane, WA
Jeff Logan, Wyatt Engineering, Inc., 1220 North Howard, Spokane, WA 99201
Nickie Arnold, US E.P.A., ~~422 Washington Street~~, Boise, ID 83702



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 10
1200 Sixth Avenue
Seattle, Washington 98101

February 4, 2000

Honorable Harold Whitley
Mayor of Plummer
P.O. Box B
Plummer, Idaho 83851

Re: Wastewater Treatment Plant National Pollutant Discharge Elimination System (NPDES)
Compliance Inspection

Dear Mayor Whitley,

January
On ~~August~~ 24, 2000 we conducted a NPDES compliance inspection of Plummer's sewage treatment plant. Enclosed is a copy of the report/checklist that summarize our findings. Although we did not take samples at the time of the inspection, the latest Discharge Monitoring Report for the period indicated the plant was in compliance with its permit.

However, in an April 15, 1999 letter, EPA requested information relating to previous discharge violations and the steps necessary to bring the facility back into compliance on a regular basis. The City responded in a May 27, 1999 letter outlining certain steps it was taking. Reference was made to an engineering study to be completed by September 1, 1999. It is our understanding that this study has not yet been completed.

We ask the City to immediately complete its study and propose a schedule that would return the plant to continued compliance and address the problems associated with excessive infiltration/inflow, the current land application site and the sand filters.

We extend our appreciation to Corky Booth, Plant Supervisor, for the assistance and courtesy shown us during the inspection. Mr. Booth appears to be doing the best possible job with the given situation.

If you have additional questions, please contact me in Boise at (208) 378-5754.

Sincerely,

Michael Silverman
Environmental Engineer

enclosures

cc: John Tindall, DEQ-CDA
Alfred Nomee, CDA Tribe

NPDES Water Compliance Inspection Report

City of Plummer (ID-0022781)

Facility Mailing Address: City of Plummer
P.O. Box B
Plummer, Idaho 83851

Inspection Date: January 24, 2000

Report Date: January 27, 2000

Contact: A.F. (Corky) Booth, Plant Supervisor; (208) 686-1386

Authorized representative: Honorable Mayor Harold Whitley

Those Present at the Inspection: Corky Booth, Plant Supervisor
Scott Fields, CDA Tribe
Mike Silverman, EPA-IOO

Facility Description: Headworks comprised of a grinder, parshall flume, sonic flow totalizer; two aerated lagoon cells; chlorination; two sand filters; and discharge in winter to Plummer Creek and in the summer to a 27 acre land application system.

Date of last previous inspection: unknown

Findings/Items to follow up on:

- The plant is subject to high I/I flows--at times in excess of 400,000 gpd. It is also in need of modifications and/or expansion. There are plans to acquire a new 80 acres land application site. The site is upland and more suitable than the current lowland site which is subject to drainage and tight clay soil problems that often prevent its early season use.

EPA has sent the City two letters noting various effluent limit violations. In a May 27, 1999 letter responding to EPA's enforcement letter of April 15, 1999, the City noted that a study was underway intending to identify the plant's problems and schedule steps for achieving compliance. The study was to be complete by September 1, 1999. The study had not yet been completed at the time of the inspection.

The City needs to immediately complete this engineering study and establish a schedule for achieving compliance.

- Problems exist with the mode of operation and performance of the existing sand filters.
 - Although no samples were taken at the time of the inspection, the DMR for the most recent time period showed removal rates of 95% and 96% for BOD and TSS respectively.
-

Entry and Credentials

yes | no | n/a Showed credentials upon entry
yes | no | n/a Contacted person in charge - Corky Booth, Plant Supervisor

Records and Reports

yes | no | n/a Records and reports maintained as required by permit.
yes | no | n/a Permit on file at facility
yes | no | n/a Sampling date, time, location, person
yes | no | n/a Analyses dates, time, person-- **BOD, fecals, and TSS are analyzed by the Idaho State Lab in CDA on a contract basis.**
yes | no | n/a Analytical methods used - Standard Methods
yes | no | n/a Results (consistent with DMRs)
yes | no | n/a Monitoring records kept for minimum 3 years

Permit Verification

yes | no | n/a Inspection observations verify the permit
yes | no | n/a Correct name and mailing address
yes | no | n/a Facility is as described in permit
yes | no | n/a Principal products and rates as set forth in permit application (**municipality**)
yes | no | n/a Treatment processes are as described in application
yes | no | n/a Notification given of new, different or increased discharges
yes | no | n/a Accurate records of raw water volume maintained--**Sonic flow totalizer at headworks measures flow and is periodically calibrated against parshall flume.**
yes | no | n/a Number and location of discharge points as described in permit
yes | no | n/a Correct name and location of receiving waters

Operation and Maintenance

yes | no | n/a Treatment facility properly operated and maintained
yes | no | n/a Standby power or other equivalent provisions provided--**No major lift station at plant--if power goes out, aerators and chlorinator will go down--one small lift station in collection system serves only a few connections.**
yes | no | n/a Adequate alarm system for power or equipment failures available
yes | no | n/a Sludge management plan and disposal sites approved
yes | no | n/a All treatment units in service
yes | no | n/a Established procedures available for training new operators
yes | no | n/a Adequate number of qualified operators--**1 operator; OK**
yes | no | n/a Files maintained on spare parts, equipment specifications, suppliers--
yes | no | n/a Maintenance record system adequate
yes | no | n/a Operation and maintenance manual maintained
yes | no | n/a EPA /State notified of diversions
yes | no | n/a Any bypassing since last inspection
yes | no | n/a Any hydraulic or organic overloads experienced--**Periodic I/I hydraulic problems-- see above comment**

Safety items satisfactory

<u>yes</u>		no		n/a	Adequate storage of fuels, chemicals, oil
<u>yes</u>		no		n/a	Personal protective clothing provided: helmets, ear protectors, goggles, gloves, rubber boots with steel toes, eyewashes, pipette suction bulbs, fume hood, shower
<u>yes</u>		no		n/a	Safety devices available: fire extinguishers, oxygen deficiency/explosive gas indicator, safety harness, first aid kits, ladder to enter manholes or wetwells, traffic control cones, safety buoys, life preservers
<u>yes</u>		no		n/a	General safety structures: rails, covers
<u>yes</u>		no		n/a	Plant personnel immunized for typhoid and tetanus
<u>yes</u>		no		<u>n/a</u>	No cross connections, backflow preventer properly installed and tested-- No potable water at plant.
<u>yes</u>		no		n/a	Chlorine safety: approved air pack, chlorine cylinders chained, personnel trained in the use of chlorine, repair kit available, leak detector tied into plant alarm system, ventilation fan with outside switch, posted safety precautions.
<u>yes</u>		no		n/a	Facility has complied with the 6 employer responsibilities for the Worker Right-to-Know Law
<u>yes</u>		no		n/a	Emergency action plan and phone numbers
<u>yes</u>		no		n/a	Warning signs: no smoking high voltage, non-potable water, chlorine hazard, watch your step, and exits

Compliance Schedules

yes		no		<u>n/a</u>	Permitted is meeting compliance schedule-- Need to develop a compliance schedule
-----	--	----	--	------------	---

Self-Monitoring Program

<u>yes</u>		no		n/a	Flow measurement meets the requirements and intent of the permit-- an instantaneous flow measurement is taken once per day from reading an effluent weir; this data is used to calculate DMR (lbs./day/ and % removal) information.
yes		no		<u>n/a</u>	Influent flow meter properly installed, operated, calibrated, maintained Describe flow meter: parshall flume, sonic transducer flow totalizer
yes		no		<u>n/a</u>	Effluent flow meter properly installed, operated, calibrated, maintained Describe flow meter: parshall flume, sonic transducer
<u>yes</u>		no		n/a	Sampling meets the requirements and intent of the permit.
<u>yes</u>		no		n/a	Locations adequate for representative samples
<u>yes</u>		no		n/a	Parameters and sampling frequency agree with permit.
<u>yes</u>		no		n/a	Permitted is using method of sample collection and handling as required by permit and approved procedures
yes		no		<u>n/a</u>	Flow proportioned samples obtained where required by permit
<u>yes</u>		no		n/a	Sample holding times in conformance with 40 CFR 136.3
<u>yes</u>		no		n/a	Monitoring and analyses being performed more frequently than required by permit
yes		no		<u>n/a</u>	If yes, are results reported in permitted's DMR

Laboratory

<u>yes</u>	no	n/a	Permitted lab procedures meet the requirements and intent of the permit
<u>yes</u>	no	n/a	Approved QA/QC-- City uses State Lab on a contractual basis
<u>yes</u>	no	n/a	EPA approved analytical testing procedures used
yes	no	<u>n/a</u>	If alternate procedures are used, proper approval obtained
<u>yes</u>	no	n/a	Adequate calibration and maintenance of instruments and equipment
<u>yes</u>	no	n/a	Duplicate samples are analyzed % of time
<u>yes</u>	no	n/a	Spiked samples are used % of time
<u>yes</u>	no	n/a	Quality control procedures used
<u>yes</u>	no	n/a	Commercial laboratory used-- City uses State Lab on a contractual basis
<u>yes</u>	no	n/a	Commercial laboratory certified-- City uses State Lab on a contractual basis

Effluent/Receiving Water Observations


<u>yes</u>	no	n/a	Outfall inspected: no oil, grease, turbidity, foam, solids, etc. found
------------	----	-----	--

Sampling Inspection Procedures and Observations

<u>yes</u>	no	n/a	Grab Samples obtained
yes	no	<u>n/a</u>	Composite obtained
yes	no	<u>n/a</u>	Flow proportioned sample
yes	<u>no</u>	n/a	Automatic sampler used
yes	<u>no</u>	n/a	Sample split with permitted
yes	<u>no</u>	n/a	Sample obtained from facility sampling device
<u>yes</u>	no	n/a	Sample representative of volume and nature of discharge

Other Comments and/or Observations: see attached letter

Inspector(s): Mike Silverman EPA-IOO (208) 378-5754



Signature

EPAEnvironmental Protection Agency
Washington, D.C.

OMB No. 2040-0057

WATER COMPLIANCE INSPECTION REPORT**Section A: National Data System Coding (i.e., PCS)**

Transaction Code Type	NPDES	yr/mo/day	Inspection Type	Inspector	Fac
1) <u>N</u> 2) <u>5</u>	3) <u>ID002278-1(11)</u>	12) <u>00/01/24(17)</u>	18) <u>C</u>	19) <u>R</u>	20) <u>1</u>
21) _____	(66)				
Inspection Work Days	Facility Self-Monitoring Evaluation Rating	B1	QA	Reserved	
67) <u>5.0(69)</u>	70) <u>5</u>	71) <u>N</u>	72) <u>N</u>	73) <u>(74)</u>	75) <u>(80)</u>

Section B: Facility Data

Name and Location of Facility Inspected (For industrial users discharging to POTW, also include POTW name and NPDES number):

City of Plummer Sewage Treatment Plant

P.O. Box B

Exit Time/Date: 13:30:01/24/00Permit Expiration Date: 08/17/87 extended

Plummer, Idaho 83851

Name(s) of On-Site Representative(s)/Title(s)/Phone and Fax Number(s)

Other Facility Data

A.F.(Corky) Booth, Plant Supervisor (208) 686-1386

Name, Address of Responsible Official/Title/Phone and Fax No.

Contacted Yes No X

Honorable Mayor Harold Whitley, Plummer, ID 83851: (208) 686-1641

Section C: Areas Evaluated During Inspection (Check only those areas evaluated)

<input checked="" type="checkbox"/> Permit	<input checked="" type="checkbox"/> Flow Measurement	<input checked="" type="checkbox"/> Operations & Maintenance	<input type="checkbox"/> CSO/SSO (Sewer Overflow)
<input checked="" type="checkbox"/> Records/Reports	<input checked="" type="checkbox"/> Self-Monitoring Program	<input checked="" type="checkbox"/> Sludge Handling/Disposal	<input type="checkbox"/> Pollution Prevention
<input checked="" type="checkbox"/> Facility Site Review	<input type="checkbox"/> Compliance Schedules	<input type="checkbox"/> Pretreatment	<input type="checkbox"/> Multimedia
<input checked="" type="checkbox"/> Effluent/Receiving Waters	<input checked="" type="checkbox"/> Laboratory	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Other:

Section D: Summary of Findings/Comments (Attach additional sheets of narrative and checklists as necessary)

See attached letter.

Name(s) and Signature(s) of Inspector(s)

Agency/Office/Phone and Fax Numbers
EPA-IOO: (208) 3 78-5754; FAX 378-5744Date
2/3/00

Signature of Management Q A Reviewer

Agency/Office/Phone and Fax Numbers

Date

REC'D AUG 23 2001

City of Plummer

P.O. BOX B
PLUMMER, ID 83851
PH. 208-686-1641

August 22, 2001

Wally Hubbard
CDA Tribal Planning & Development Corp
S 30001 Highway 95
Worley, Idaho 83876


Dear Wally,

On August 9, 2001 the Plummer City Council took action to lift the moratorium on sewer connections once a letter was received assuring that an administrative order would be issued by EPA. This letter has arrived and I am happy to announce that the moratorium is officially lifted at this time.

The administrative order is based on the time line we supplied to EPA showing work that will be accomplished to reduce the storm water flow into the sewer plant. The City must follow through with this action to avoid being under the threat of fines again.

Step one of several is complete. Progress is back on track in Plummer, Idaho. Thank you.

Sincerely,



Donna Spier
City Clerk

Cc: Mary Miner, IHS
Marcus Marinez, IHS
Jeff Logan, Wyatt Engineering



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 10
1200 Sixth Avenue
Seattle, WA 98101

APR 29 2002

Reply To
Attn Of: OW-133

CERTIFIED MAIL - RETURN RECEIPT REQUESTED

Brian West, Council President
City of Plummer
P.O. Box B
Plummer, Idaho 83851

Re: Compliance Order
Docket No. CWA-10-2002-0024

Dear Mr. West:

Enclosed is a Request for Information and Compliance Order ("Order") issued to the City of Plummer ("City") pursuant to Section 309(a) of the Clean Water Act, 33 U.S.C. §§ 1318 and 1319(a).

The Order provides a schedule for the City to come into full compliance with the NPDES Permit ID0020184. The Order also provides a requirement to submit annual reports detailing the City's compliance with this Order.

Questions concerning these actions may be addressed to Robert Grandinetti at (206) 553-1283, or Cara Steiner-Riley, Assistant Regional Counsel, at (206) 553-1142.

Sincerely,

Randall F. Smith
Director
Office of Water

Enclosure

cc: Gwen Fransen, Regional Administrator, IDEQ - Coeur d'Alene

City of Plummer

P.O. BOX 8
PLUMMER, ID 83851
PH. 208-686-1641

May 6, 2002


Jeff Logan
Wyatt Engineering
1220 N Howard
Spokane, Washington 99201

Dear Jeff,

We have received our Compliance Order from EPA for our NPDES Permit. A copy is enclosed for your review and records.

I am also enclosing a copy of the Draft Wastewater Land Application Permit from DEQ. You may already have this permit. Mr. Gaffney is requesting comments prior to May 31st. Your review and comments would be appreciated. I have included a few questions of my own that I think the Council may be interested in. Both of these documents will be reviewed by the City Council at their meeting this week. Thank you.

Sincerely,



Donna Spier
City Clerk

Alan Gay

From: Scott Fields [sffields@cdatribe.com]
Sent: Wednesday, September 11, 2002 8:52 AM
To: Alan Gay
Cc: Alfred M. Nomee
Subject: RE: Plummer Creek Water Quality Standards

Alan, I agree that your synopsis provided below is a accurate description of the issues we discussed this morning I must add though that those are my initial findings on this matter and they may change with further analysis.
Thanks
Scott.

-----Original Message-----

From: Alan Gay [mailto:AGay@uskh.com]
Sent: Wednesday, September 11, 2002 8:43 AM
To: Scott Fields
Subject: Plummer Creek Water Quality Standards

Scott:

To reiterate our phone conversation of this morning, I'm emailing you regarding what I percieve we agreed upon. If you would please respond when you are able if you agree with my interpretation (or what you take exception to if you don't) I would very much appreciate it.

Based on the spreadsheet that I emailed to you yesterday (PlummerCrk wq projection.xls, dated 9/10/02, time 10:21 am), you said the numbers look pretty good. You also said that you had concern about the low flow discharge ratios. I responded that our design (though not the above-noted spreadsheet) incorporates an equalization basin and controls on the discharge rate that will allow us to flow-pace the discharge from the Plummer WWTP at 10% or less of Plummer creek streamflow. Your reply was that this approach was acceptable.

You also questioned the chlorine limit included below. I responded that this figure was only included to indicate the low chlorine residual necessary based on comparable waters, and that we will be using either UV or ozone disinfection in the future plant.

Following are the water quality parameters (as before) that we are proposing for the Plummer WWTP once the plant improvements are completed by January, 2007:

BOD: 30 mg/L maximum weekly average, 20 mg/L maximum monthly average
TSS: 30 mg/L maximum weekly average, 20 mg/L maximum monthly average
DO: 6 mg/L minimum
pH: between 6 and 8
Total Phosphorus: 0.50 mg/L maximum weekly average, 0.25 mg/L maximum monthly average
Total Coliform: 200 count/100 mL, by geometric mean
Chlorine: 0.1 mg/L

Once again, I look forward to your reply, and I greatly appreciate your assistance in resolving this matter.
Thanks,
Alan Gay